

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

JANUARY 1960



VOL. LV. NO. I

FIFTY-FIFTH YEAR OF PUBLICATION

PRICE 2s.

ANNUAL SUBSCRIPTION 24s. POST FREE. \$1.70 in Canada and U.S.A.

NEW YEAR DOUBLE NUMBER

	PAGE
Towards the Robot	1
Design of a Helical Stair Built in 1908	3
Designs for an Elevated Road: Competition Result	10

Illustrated descriptions of
reinforced and prestressed
concrete structures recently
completed and in progress.

No. 626

ISSUED MONTHLY

Registered for
Canadian Magazine Post

BOOKS ON CONCRETE

For Catalogue of "Concrete Series" books on
concrete and allied subjects, send a postcard to:

CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., LONDON, S.W.1.

INDEX OF ADVERTISERS

A.B. MOULD & CONSTRUCTION CO. LTD.
ABELSON & CO. (ENGINEERS) LTD.
A.C.E. MACHINERY LTD.
ALLAN, E. P., & CO. LTD.

BARREY, A. & C. LTD.
BERRY'S ENGINEERING CO.
BICKERTON & PARTNERS LTD.
BOOT, HENRY, & SONS LTD.
BOULDER EQUIPMENT LTD.
BOYER, W., & SONS LTD.
BRADFORD, F., & CO. LTD.
BRETT, ROBERT, & SONS LTD.
B.R.C. ENGINEERING CO. LTD.
BRITISH STEEL PILING CO. LTD.
BYRD, A. A., & CO. LTD.

CAPLIN ENGINEERING CO. LTD.
CEMENT MARKETING CO. LTD.
CEMENT & STEEL LTD.
CHAPMAN, H. W., LTD.
CHEMICAL BUILDING PRODUCTS LTD.
CHERTHWAITE, ALEX. J., LTD.
CONCRETE LTD.
COLES, A. N. (CONTRACTORS) LTD.
CONCRETE LTD.
CONCRETE PILING LTD.
CONCRETE PROOFING CO. LTD.
CONCRETE PUMP CO. LTD.
CONCRETE SERVICES LTD.
COWEYBEARD & CO. LTD.
CORNWELL EQUIPMENT CO. LTD.
COWLIN, WILLIAM, & SONS LTD.

D.A. MODELS LTD.
DAVIDSONS PAPER SALES LTD.
DICKENS, STUART B., LTD.
DEMOLITION & CONSTRUCTION CO. LTD.
DORMAN LONG & CO. LTD.
DOUGLAS, ROBERT M. (CONTRACTORS) LTD.

ENGINEERING DESIGN & CONSTRUCTION LTD.
EONIC ENGINEERING CO. LTD.
EVOLVE LTD.
EXPANDITE LTD.

FARLINGTON, LEONARD, LTD.
FAIRFORD READY-MIXED CONCRETE CO. LTD.
FARR, A. E., LTD.
FARROW, HOWARD, LTD.
FER (GREAT BRITAIN) LTD.
FERROCONCRETE (LANCE) LTD.
FLEXIBLE DRIVE & TOOLS CO. LTD.
FORD MOTOR CO. LTD.
FRAM REINFORCED CONCRETE CO. LTD.

G.K.N. REINFORCEMENTS LTD.
GEI, WALKER & SLATER LTD.
GIRLING'S FERRO-CONCRETE CO. LTD.
GLEESON, M. J. (CONTRACTORS) LTD.
GREENWOOD, GEORGE, & SONS.
GUINIER CONSTRUCTION CO. LTD.

HALL & CO. LTD.
HILL, RICHARD, LTD.
HILTON GRAVEL LTD.
HOLLAND & HANNAN AND COFFITS (GT. BRITAIN) LTD.
HOLMAN BROS. LTD.
HOLST & CO. LTD.
HOWARD, C. A. E. C., LTD.
HUNTLEY & SPARKS LTD.

IMPERIAL CHEMICAL INDUSTRIES LTD.

JOHNSON, RICHARD, & NEPHEW LTD.
JOHNSON'S REINFORCED CONCRETE ENGINEERING CO.
LTD.
JOHNSON, T. C., & CO. LTD.

Page
lxvi
viii
xxvii
xxvii

KERNER-GREENWOOD & CO. LTD.
KING, J. A., & CO. LTD.

ix
xviii
xxiv
iii
xi
c
xlii, xliii
xxiv
cxv
—
xix

LAPARIS ALUMINUM CEMENT CO. LTD.
LAWLER, AYERS & CO. LTD.
LAWS & SON (STAINES) LTD.
LEARY'S FIBREBOARD LTD.
LEEDS OIL & GREASE CO. LTD.
LENSCETRE LTD.
LILLINGSTON, GEORGE, & CO. LTD.
LIND, PETE, & CO. LTD.
LONDOR, GEORGE, & SONS LTD.

MC CALL & CO. (SHREWSFIELD) LTD.
MC CALLS MACALLOV LTD.

MCKINNEY FOUNDATIONS LTD.
MAY & BUTCHER LTD.

MICANITE & INSULATORS CO. LTD.

MILWAKEE FLOORS LTD.

MILLARS' MACHINERY CO. LTD.

MILLERS, JAMES, & PARTNERS LTD.

MILLS SCAFFOLD CO. LTD.

MOSE, A., & CO. LTD.

MORAN, WHITLEY, & CO. LTD.

MULCASTER, WM., & CO. (CONTRACTORS) LTD.

P.S.C. EQUIPMENT CO. LTD.

PASLEY & TRENCHER LTD.

PLUMPER, GEO. H., LTD.

PORTASLIO LTD.

PRELOAD LTD.

PRESTRESSING SALES LTD.

PRIEST, B., & SONS LTD.

Page
lxvi
viii
xxvii
xxvii
ix
xv
vi
vii
ix

xcv
xcvii
viii
lxvii
lxvii
lxvii
lxvii
lxvii
lxvii

xcvii
xcvii
lxvii
lxvii
lxvii
lxvii

xcviii
xlv
xvii
xvii

xcviii
xcviii
xcviii

</

1½ MILLION CUBIC YARDS OF CONCRETE

HAVE BEEN AIR-ENTRAINED WITH

FEBCRETE A.E.A.

ON BRITISH GOVERNMENT CONTRACTS
DURING THE PAST TWO YEARS

FEBCRETE Air-Entraining Agent without adding to cost improves the flowability and workability of concrete, allows the water-cement ratio to be reduced and increases resistance to the passage of water and to repeated cycles of freezing and thawing.



It ensures that full compaction and maximum compressive strength are obtained without excessive vibration, reduces segregation of the aggregates and prevents bleeding. Write for brochure.

FEB (GREAT BRITAIN) LTD

LONDON : 102 Kensington High Street, W.8. Telephone: WEStern 0444
MANCHESTER : Albany Works, Albany Road, Chorlton-cum-Hardy.
Telephone: CHOrton 1063

GLASS FIBRE SHUTTERING

for all in-situ concrete work



Glass Fibre is unequalled as a material for simple and intricate shuttering for all forms of concrete construction. The illustration on the left shows glass fibre shuttering supplied by us for columns with splayed heads for new premises constructed by Gravesend Wholesale Co-operative Society. Architect : Mr. W. J. Reed, F.R.I.B.A.

**NO STICKING · NO CLEANING
STRONG AS STEEL · FIRM AS A ROCK**

FOR HIRE Glass Fibre Moulds for Flooring

Consult

D. A. MODELS • LTD

108 WOODSTOCK ROAD, LONDON. W.4.

TELEPHONE: CHISWICK 2011

YORKSHIRE HENNEBIQUE

Contracting Co. Ltd.

ESTABLISHED 1904

CIVIL ENGINEERING CONTRACTORS

HEAD OFFICE :

HENNEBIQUE HOUSE
The Mount • York


Telephone : YORK 54656 (4 lines)

Branch Offices :

HULL : 30 WINCOLMLEE. Telephone : Hull 29501

LEEDS : ROYDS WORKS, LOWER WORTLEY, LEEDS 12.

SHOREHAM HARBOUR DEVELOPMENT



The improvement of the harbour facilities at Shoreham to accommodate larger colliers feeding Brighton 'B' power station comprised the construction of three new breakwaters, a new lock, lay-by wharves and ancillary works including extensive dredging


consulting engineers
Sir William Haircaw and Partners

CONTRACTORS

PETER LIND & COMPANY LIMITED
LONDON

ROMNEY HOUSE, TUFTON STREET, LONDON, S.W.1
TELEPHONE ABBEY 7361

PROJECT FOR SUPERTANKERS



This illustration of the supertanker berths at Tranmere is reproduced by courtesy of the Mersey Docks and Harbour Board

Construction of the berths is being carried out under the direction of their Engineer-in-Chief


CONTRACTORS

PETER LIND & COMPANY LIMITED
LONDON

ROMNEY HOUSE, TUFTON STREET, LONDON, S.W.1
TELEPHONE ABBEY 7361

WOOD MOULD

for roof-light surrounds for



The mould illustrated above is 10 ft. by 10 ft., and is one of many designed and supplied by us for this contract.

We are specialist mould makers to the concrete industry, and can supply wood moulds for all types and sizes of precast concrete. Accuracy is guaranteed in every detail and a 25-years experience is always at your service. Many new methods introduced by LAWS & SONS have been adopted by our customers for use in their own shops.

MESSRS.
WATES LTD

*In the
construction of the*

**U.S.A.
EMBASSY
LONDON**

LAWS
& SONS (STAINES) LTD.

(CONTRACTORS TO
H.M. GOVERNMENT)

Langley Road Works, Staines,
Middlesex
Telephone: Staines 53700

ABELSON for SKIPS



Circular skipping skips 2½ cu. yds.



Concrete pouring skip side
discharge 10 cu. yds. to 37 cu. yds.




Circular bottomed discharge
bottom discharge 1 cu. yd. to 1½ cu. yds.



Square bottoming or breaking
skip 4-22 cu. cu. yds. capacity.



Roller skips 5 cu. yds. capacity.



Tilt skips 5 cu. yds. to 7 cu. yds.



Concrete pouring skips bottom
discharge 10 cu. yds. to 37 cu. yds.

ABELSON
& CO. (ENGINEERS) LTD.

**SHELDON
BIRMINGHAM. 26**

TEL: SHELDON 2424-310 (10 lines)

*Announcing the
amalgamation of*

• **A. & C. BUILDINGS · LTD**
with
BARVIS PARTNERS
to form
A. & C. BARVIS · LTD



The book illustrated here gives details of this amalgamation, which includes companies experienced in building and civil engineering, and now incorporates the A & C BUILDINGS DIVISION, an established organisation carrying out design, manufacture, and erection of reinforced and prestressed prefabricated concrete structures. This book also includes some valuable information, giving in detail, with illustrations, the construction of several important concrete structures (reinforced and prestressed) carried out by the A & C Buildings Division. It represents a valuable guide for those preparing schemes for structures for all purposes, and of every size in any part of the country.

A FREE COPY

of this authoritative guide to economical building construction is readily available on request.

A. & C. BARVIS LTD A. & C. BUILDINGS DIVISION

MANOR WORKS, CHURCH ROAD, THUNDERSLEY, ESSEX. TELEPHONE: SOUTH BENFLEET 2575-7
LONDON OFFICE: 76 VICTORIA STREET, S.W.1. TELEPHONE: VICTORIA 5094

TUBING FOR
PRE-STRESSED CONCRETE
PRE-TENSIONED OR
POST-TENSIONED OPERATIONS

**UNI-TUBE SEMI-RIGID
CONVOLUTED STEEL TUBING**

Made from strip steel, convoluted, spirally wound and locked to prevent splitting. Bonds perfectly with surrounding concrete, becoming an integral part of installation. Supplied in straight 20 ft. lengths which can be easily joined together with screw type connectors or in longer lengths in coils. Suitable for straight runs or parabolic curves.



**UNI-TUBE RIGID
STEEL TUBING**

Supplied in maximum 20 ft. lengths with separate connectors or with telescopic ends.



**KOPEX PLIABLE
STEEL TUBING
(LOCKED-RIB)**

Bends easily without distortion of bore. Ribbed on the outside to give perfect bond with surrounding concrete. On drums or in coils and easily cut on site to required lengths.




Illustration shows formation of Uni-Tube semi-rigid convoluted steel tubing and ease of connection of 20 ft. lengths



Specimen tubing,
technical data and prices
supplied on request

**UNI-TUBES
LTD**

197 KNIGHTSBRIDGE,

LONDON, S.W.7.

TEL: KNIGHTSBRIDGE 7811/5

WORKS: ALPHA STREET,


SLOUGH, BUCKS.

TEL: SLOUGH 25476/8

RECORD

fully
automatic
and rapid

BAR BENDER



THE SMALL MACHINE WITH A BIG OUTPUT


We illustrate here a machine that will cater for all bending requirements for bars up to 1½ in. in diameter, with accuracy and with unskilled labour. Bending angle is pre-set on a large dial for accuracy and repetition. Clockwise or anti-clockwise bends on the same bar can be made without reversing. Foot or hand control. Please ask for illustrated leaflet No. 47CE.

CORNELLY EQUIPMENT CO. LTD

39 VICTORIA STREET

Telephone: Abbey 5702-3. Cables: Cornelly, London. Telegrams: Cornelly, Sowest, London.

LONDON S.W.1



Various Colliery Structures designed and built by Holst & Co Ltd

DESIGN AND CONSTRUCTION

HOLST
& CO LTD

Civil Engineering Contractors, Reinforced Concrete

Head Office: 46 CLARENDON ROAD, WATFORD

Telephone: Watford 34481

Branches : BIRMINGHAM, MANCHESTER, LEEDS, DURHAM, EDINBURGH, CARDIFF

Lillington's in the
NO. 1 METALLIC LIQUID

factory floors of another famous firm



Periodically Aveling-Barford Limited, of Grantham, who are the largest manufacturers in the World of heavy road rollers, dumpers, tractors and other agricultural machinery, extend their factories to meet the ever increasing demand.

It is essential that their concrete floors are waterproofed, case-hardened and dustless. To ensure these results, No. 1 Metallic Liquid is always added to the gauging water; a simple and inexpensive operation.

For nearly fifty years, architects have specified No. 1 Metallic Liquid, the scientifically prepared admixture that makes concrete completely waterproof and dustless as well as accelerating the setting time. No. 1 Metallic Liquid is a necessity for waterproof cement renderings to walls and basements, in mass concrete retaining walls, foundations, flat roofs and tanks. You can rely on Lillington's No. 1 Metallic Liquid to give complete satisfaction because **IT IS THE ONLY PROOFER SOLD UNDER GUARANTEE**

FROM **5/-** PER GALLON

Special terms for bulk contracts

Write for Booklet 56

**GEORGE LILLINGTON
AND COMPANY LIMITED**

Willow Lane, Mitcham, Surrey • Telephone: Mitcham 1066
For Scotland: 42 High Street, Greenock

AP/3184

ALL OUR PRODUCTS NOW SOLD IN FREE CONTAINERS

Lillington's

NO. 1 METALLIC LIQUID



CANADA CHOOSES RYLANDS WIRE FOR PRESTRESSED CONCRETE BEAMS

... in the construction of an Ice Rink for the Corporation of the City of Westmount, Montreal.



CONTRACTORS

Messrs. Douglas Bremner Construction Ltd.,
5965 Monkland Avenue, Montreal.

ARCHITECTS

Messrs. Wiggs, Lawton & Walker,
4350 Sherbrooke Street West, Montreal.

ENGINEERS

Messrs. Wiggs Walford Frost & Lindsay,
4350 Sherbrooke Street West, Montreal.

RYLANDS

RYLANDS BROTHERS LIMITED WARRINGTON ENGLAND

STORERS

W.M. T. STORER & Co. LTD.

TIMBER IMPORTERS AND MERCHANTS

Established 1913



Sawing and Planing Mills:
RIVER ROAD, BARKING, ESSEX

Telephone: RIPpleway 0301 (10 lines)

FOR
SOFTWOOD

Three is company



In modern construction the only way to be sure of 'smooth sailing' throughout a project is to have all the experts in at the start. Co-ordination at inception ensures efficient, economic and uninterrupted progress to prompt completion. This means that the contractor, with his wealth of practical experience in current constructional techniques and their specialised applications, must be on hand, together with the client and his consultant, at the planning stage to advise on design, materials and plant in relation to the specific requirements of each individual contract. Eliminate the chance of errors or omissions—modifications during construction are costly and difficult and cause expensive delays. Many clients make sure by availing themselves of Monk's experience and 'know-how' from the earliest analysis. Our resources are at your service, call on them now and insure against error or delay.



WARRINGTON & LONDON
A MONK & COMPANY LIMITED
Offices at Hull, Middlesbrough, Stamford

CIVIL ENGINEERING, BUILDING AND REINFORCED CONCRETE CONTRACTORS

U-KLIPON



**the name
that always
stands for**

ACCURACY IN BAR SPACING

Complying in ALL respects to the British Standard & Codes of Practice, there is no more surer means of avoiding inadequate cover of reinforcement than with the **U-KLIPON BAR SPACER** illustrated here. Its revolutionary design incorporates many unsurpassed distinctive features including: Simple operation . . . instant fixing on mesh or any form of prefabricated reinforcement . . . easily adjusted after assembly of steel to any part of the mould or shuttering . . . a vice-like grip . . . time-saving . . . permanent . . . economical . . . practical . . . unaffected by heavy tamping or vibrating.

CONSULT

THE B.E.C. BAR-SPACER SERVICE

which has been responsible for the most outstanding contribution to accurate bar-spacing, and has played an important part in the reinforced concrete industry in solving bar-spacing problems with efficiency and economy. Many millions of U-Klipon "K" Type and B.E.C. "M" Type spacers have been sold to date. Over 120 stock sizes enable us to give immediate attention to requirements.

Patent Nos. 597,505, 715,563, 789,018, 818,538. Registered Nos. 870,560, 886,239. English and Foreign Patents pending.



FLASH !

for GROUND BEAMS

BARREL ROOFING

MAT WORK, ETC.

We invite you to write for full details of this revolutionary unit, or our Technical Consultant will be pleased to call and discuss any problems on request to:

BERRY'S ENGINEERING CO.

SOLE MANUFACTURERS:

Middle Road, Shoreham-by-Sea, Sussex

Phone and Grams: Shoreham-by-Sea 3541-2

CONTRACTORS TO MINISTRY OF SUPPLY, ETC., ETC.



**PRECAST
CONCRETE
WALL
FRAMES**

Illustration of office building at Stanlow Oil Refinery, near Chester, for the Shell Petroleum Co., Ltd., showing the precast concrete wall frames supplied by us. Architects: Messrs. Grenfell Baines & Hargreaves. Consulting Engineers: Messrs. F. J. Samuels & Partners.

SUPPLIED BY

GEORGE GREENWOOD & SON

**SPECIALIST PRODUCERS OF REINFORCED
AND PRESTRESSED STRUCTURAL MEMBERS •
"MYKO" SUSPENDED FLOOR BEAMS •
GENERAL CONCRETE PRODUCTS**

Whatever your requirements in precast concrete, we can offer the best service with every possible economy. Include our name on your list for future contracts.

18 KING CROSS STREET HALIFAX
TELEPHONE: 67291 (10 lines)

*for anything in PRECAST CONCRETE

SEND YOUR ENQUIRIES TO

ST. IVES

SAND & GRAVEL CO. LTD

22 THE BROADWAY - ST. IVES - HUNTS. Telephone: St. Ives 2441-4

ALL STRUCTURAL MEMBERS

reinforced or prestressed—supplied to any design
and size to contracts in most parts of the country.

PRESTRESSED CONCRETE BEAMS

REINFORCED CONCRETE PILES

OMNIA FLOORING

PREFABRICATED BUILDINGS, GARAGES - ETC.

including farm and agricultural structures.


HYDRAULICALLY-PRESSED KERBS AND PAVING SLABS

FENCING OF ALL TYPES - CONCRETE BUILDING BLOCKS

DUNBRIK PRECISION FACING BRICKS

**READY-MIXED
CONCRETE**

From our ready-mixed concrete plants at St. Ives (Tel. 2444) and Peterborough (Tel. 3256) we can deliver supplies to any specification, and in any quantity, to contracts in Huntingdonshire, Northamptonshire, Cambridgeshire, Bedfordshire.



**THE WIDNES
SKEWBACK PIER
for the
NEW RUNCORN-WIDNES
ROAD BRIDGE**

**OTHER CONTRACTS
RECENTLY
CARRIED OUT BY
US IN REINFORCED
CONCRETE INCLUDE**

**LEONARD
FAIRCLOUGH
LTD**

**CONTRACTORS FOR REINFORCED CONCRETE,
CIVIL ENGINEERING AND BUILDING WORK**

HEAD OFFICE: Adlington, Lancs.

LONDON OFFICE: Gordon House Road, N.W.5

MANCHESTER OFFICE: 573 Chester Road, Old Trafford, 16.

HAYDOCK OFFICE: Vista Road, Haydock, Nr. St. Helens.

LIVERPOOL OFFICE: 47 Oriel Chambers, 14 Water Street.

NEWCASTLE OFFICE: 53 Ironmarket, Newcastle, Staffs.

Colliery Blending Bunkers.
Weighbridge Foundations.
Washery and Coal Preparation
Plants. Power House and Wind-
ing Engine Houses (N.C.B.).
Roadways. Road, Railway and
Canal Bridges. Warehouses.
Factories. Sewage Disposal
Works

Telephone: Adlington 264/3 6/7

Telephone: Gulliver 7309 & 7408

Telephone: Trafford Park 1060

Telephone: Ashton-in-Makerfield 7503-4

Telephone: Central 3016

Telephone: Newcastle 65413

DUCTEX

Rigid metal sheathing

for ducts in
prestressed concrete

now



Ductex 'B' is rigid tubing supplied in standard lengths of 10'. Available in diameters between 1" and 3". Bellied at one end to provide the fastest, simplest and cheapest form of coupling.

and up to

30%

cheaper
by home production

Write for samples and prices to

PRESTRESSED SALES LIMITED

64/66 Battersea High Street • London S.W.11 • Telephone Battersea 9221/9

X
E
M
T
E
D
U

Flexible metal tubing

for ducts in
prestressed concrete

now

DUCTIFLEX 'B'

b means British made



- * Diameters between 1" and 3"
- * Extremely strong with great flexibility.
- * Screw couplers available for all sizes.


flexible · cheap · strong

Write for samples and prices to PRESTRESSED SALES LIMITED

64-66 Battersea High Street • London S.W.11 • Telephone Battersea 9221/9



A 1400-TONS prestressed roof cast on the ground was raised 46 ft. high with



YOUNGS JACKS

The illustration above shows one of three prestressed concrete roofs, each weighing 1400 tons, constructed by John Laing & Son Ltd. for a hangar at Abingdon. This method of constructing roofs on the ground and raising them in position with Youngs Jacks (shown in the left illustration) was used because the elimination of scaffolding and the reduced formwork costs provided a cheaper and more efficient means of constructing barrel vault roofs.

As specialists in Jacking Systems for many years, we are pleased to record that our equipment is the choice of more and more leading civil engineering and building companies for use on major contracts throughout the world. Full details of the jacks shown above, and other jacking systems supplied by us for those engaged in concrete construction, will be sent on request.

YOUNGS


LIFTING APPLIANCES LTD

RYLAND STREET WORKS, BIRMINGHAM, 16

Telephone : Edgbaston 3508-9

LONDON OFFICE: 17 VICTORIA STREET, S.W.1

Telephone: ABBey 2908



**STRUCTURAL
PRECAST
CONCRETE by**

Precast concrete three-hinge arches for a church at Greenford. All precast concrete was supplied and erected by us. Architects: Messrs. David Stokes & Partners. Consulting Engineers: Considerre Constructions Ltd.

**GIRLING'S'
FERRO-CONCRETE CO. LTD**


FOR ALL FORMS OF PRECAST CONCRETE

We can supply, or supply and erect, precast concrete structural members for contracts of all kinds in any part of the country.

**GREAT SOUTH WEST ROAD, FELTHAM, MIDDX. TELEPHONE: HOUNslow 1158
ALSO AT**

ROTHWELL, near LEEDS. Telephone: Rothwell 3174 (Leeds extension)

**and
SOUTHBANK ROAD, KIRKINTILLOCH, GLASGOW. Telephone: Kirkintilloch 2242.**



**have been regularly used
.....
by leading Contractors for
.....
reinforced concrete work
.....
since 1903**

We were the pioneers in the supply of steel bars for reinforced concrete work and have given to the industry over 50 years of unbroken service, unequalled for quality and dependability. Contracts on which WHITEHEAD STEEL has been used include some of the largest and most important in the country.

We can supply mild steel with an ultimate tensile stress of 28/33 tons to the square inch; medium tensile 33/38 tons to the square inch, and high tensile 37/43 tons per square inch.

We can also supply high tensile bars 40/45 tons to the square inch with a minimum yield of 60,000 pounds per square inch.

LONDON OFFICE: Steel House, Tothill Street, S.W.1. Telephone: Whitehall 2984.

BIRMINGHAM OFFICE: King Edward House, New Street, 2. Telephone: Midland 0412-3.

MANCHESTER OFFICE: Chronicle Buildings. Telephone: Blackfriars 1603/4.

GLASGOW OFFICE: 50 Wellington Street, C.2. Telephone: Central 1528.

for PILE SHOES AND TIE RODS

consult



EIGHTY YEARS'
EXPERIENCE

In catering for the requirements of Civil Engineering and Public Works Contractors engaged in piling and foundation work enables us to give a first-class service in the supply of pile shoes of all designs and sizes, including special fittings for prestressed concrete piles, tie rods up to 4 in. diameter for sheet steel piling work, and foundation bolts of all types and sizes. Our completely informative Catalogues on Pile Shoes and Bollards, and a fully dimensioned leaflet on tie rods, are available on request.

W. RICHARDS & SONS LTD

BRITANNIA FOUNDRY, MIDDLESBROUGH. TEL: 45261



PIN YOUR FAITH
TO THE TESTED
BRAND

THIS LABEL ON
EVERY BARREL
CARRIES WITH
IT FIFTY YEARS'
EXPERIENCE OF
MANUFACTURE.


NONE OTHER IS
"JUST AS GOOD"

THE LEEDS OIL & GREASE CO.

Phone 22480

LEEDS, 10

"Grams : "Grease."



RELIANCE PRESTRESSED FLOOR AND ROOF BEAMS

CIVIC COLLEGE • IPSWICH

for which we supplied prestressed concrete beams for all floors and roof and other precast concrete members.
Architects : Messrs. Johns, Slater & Howard. Consulting Engineers : Messrs. Felix J. Samuely & Partners.

MANUFACTURED BY

SAUNDERS

IPSWICH _____ LTD

FOR ALL FORMS OF PRECAST CONCRETE

including reinforced and prestressed precast structural members of all sizes and for all purposes. Cladding slabs with a large variety of textured finishes. Cast stone to any requirement. All general precast concrete products for building and public works contracts.

HADLEIGH ROAD, IPSWICH

TELEPHONE: 54401



THE CONCEPTION AND CONSTRUCTION OF MODERN BUILDINGS

HALL & CO. LTD

BRITAIN'S LEADING BUILDERS' MERCHANTS


offer service to Architects, Surveyors, and
Building Contractors. Over a century's
experience—supported by a delivery fleet
of more than a thousand road vehicles.

CONCRETE AGGREGATES AND READY-MIXED CONCRETE GENERAL BUILDING MATERIALS

Head Office : VICTORIA WHARF, CROYDON Tel. : CROYDON 4444
London Office : CHANTREY HOUSE, ECCLESTON ST., S.W.1 Tel. : SLOane 7122

NEARLY A HUNDRED DEPOTS AND PITS COVER
THE SOUTHERN HALF OF ENGLAND

PRESTRESSED & REINFORCED PRECAST CONCRETE



Architects: J. & S. Shrigley
Consulting Engineers: P. M.
Whitacre, S. S.

BEAMS • COLUMNS • PLANKS

were supplied and erected by us for this 170 ft. long by 126 ft. wide warehouse for Clayton Aniline Co. Ltd., at Manchester.


THE
FRAM
REINFORCED CONCRETE CO. LTD
FOR ALL FORMS OF REINFORCED AND PRESTRESSED
CONCRETE DESIGN AND CONSTRUCTION
IN-SITU AND PRECAST

HEAD OFFICE: 165 Plymouth Grove, Manchester 13. Ardwick 4521

MIDLAND WORKS: Whitacre Heath, Coleshill, Warwicks. Coleshill 3357

MANCHESTER WORKS: Paston Road, Wythenshawe. Wythenshawe 5565

LONDON OFFICE: 27 Ashley Place, Westminster, S.W.1. Tate Gallery 8631/6



OUTSTANDING BUILDING . . .

*Outstanding
products . . .*

CHEMICAL
BUILDING
PRODUCTS
LIMITED
Warble Works
Cleveland Road
Hemel Hempstead
Herts

CHEMICAL BUILDING PRODUCTS LTD

Telephone: Boxmoor
4900 (5 lines)
Telegrams: Prolithu
Hemel Hempstead

We shall be pleased
to supply full des-
criptive literature.

PROLAPIN Liquid Cement Waterproofer

LITHURIN Concrete Floor Hardener

QUICKSOCRETE P.Q. & D. Rapid Hardeners and
Setters

WETEXI 'S' Colourless Silicone Waterproofer

CONPLAST Concrete Plasticiser

CONPLAST 'W' Anti-freeze and Plasticiser

CEBEX 112 Mortar Improver

CEBEX 113 Expanding Grouting Material

CEBEX 124 Multi-purpose Slurry Liquid

ROAD CONPLAST Air Entrainner and Plasticiser

CONBEX Plasticised Expanding Grouting Material

LIFTOYL Floor Cleaner and Degreaser

ORKIT & TEKTAM Bituminous Coatings and
Compounds

CONCURE Concrete Curing Agent

NITOLUX & ROBRITE Paints

The American approach to foundation piling



The recently formed British company, McKinney Foundations Ltd., backed by the resources of John Laing and Son Limited, makes available, for the first time in this country, the considerable American experience in the design and construction of bored pile and caisson foundations for multi-storey buildings and civil engineering structures.

Using modern heavy duty mobile equipment similar in conception to off-the-highway mobile oil drilling rigs, McKinney Foundations can sink borings from one to eight feet in diameter down to depths of 65 feet at high speed.

(Greater diameters and depths are possible by special arrangement.)

The introduction of this service will make a valuable contribution to the economy and speed of foundation construction.

If you would like further details, please write to:

**MCKINNEY FOUNDATIONS
LIMITED**

Manor Way, Boreham Wood, Hertfordshire
Telephone: Elstree 2854

exposed aggregate panels are more attractive with

the colour "dry-dash"
which is interesting
and everlasting

DURITE CHIPPINGS

used throughout the British Isles

PRODUCED BY
BRETT'S
OF CANTERBURY

DURITE is an economical material which provides Architects and Engineers with an opportunity of specifying a highly attractive exposed-aggregate surface finish for precast and in-situ concrete for contracts in any part of the British Isles. Free samples are readily available on request.

WE ARE ALSO PRODUCERS OF
CONCRETE AGGREGATES AND
READY-MIXED CONCRETE IN


**EAST
KENT**

INCLUDING: Canterbury,
Sheerness, Margate,
Ramsgate, Deal, Dover,
Folkestone, Faversham,
Sittingbourne, Whitstable,
and district.

Details and samples are available on request.

ROBERT BRETT & SONS LTD.

ST. LAWRENCE HOUSE, NEW DOVER ROAD, CANTERBURY. TELEPHONE: 3211




MONITOR ROOF CONSTRUCTION USING POST-TENSIONED PRECAST UNITS

The illustration below shows the precast monitor roof of the new Battersea factory of S. N. Bridges and Co., Ltd. The roof beams span 78 ft. and are spaced at 38 ft. centres. They are made up of 11 ft. 10 in. precast units supported initially on scaffolding, alternating with U-shaped precast units which support pre-tensioned beams carrying 14 in. by 6 in. hollow pre-tensioned purlins. Post-tensioning was applied externally using 4-wire P.S.C. anchorages. The top picture shows a U-shaped precast unit being hoisted into position during frame erection.

Architects :
L. D. TOMLINSON & PARTNERS

Quantity Surveyor :
K. H. BOLE, F.R.I.C.S.

General Contractors :
W. H. GAZE & SONS
Design and erection
of concrete frame,
CONCRETE LIMITED.



BISON

floors, beams and concrete frame structures

SPEED & STRENGTH

CONCRETE LIMITED are the largest structural precast concrete specialists in the world

CONCRETE (SOUTHERN) LIMITED Green Lane, Hounslow, Middlesex Hounslow 2323

London Sales Office: 16 Northumberland Avenue, W.C.2 Whitehall 5504

DOVEHOUSE FIELDS, LICHFIELD, STAFFS. LICHFIELD 3553

BIRMINGHAM Sales Office: Winchester House, 5 Victoria Square, Birmingham 2 MIDLAND 0331

STOURTON, LEEDS 10 LEEDS 75421

MANCHESTER Sales Office: 40 King Street West, MANCHESTER 3 BLACKFRIARS 5676

EINA ROAD, FALKIRK FALKIRK 2366

GLASGOW Sales Office: EMBANKMENT STREET, GLASGOW C.2 CITY 3292

CON. 158

*For faster placing
and better concrete
use the*



HUMDINGER

IMMERSION VIBRATOR

AVAILABLE WITH GRINDING ATTACHMENTS



Here is an immersion vibrator that will cut your concrete-placing costs in a half-dozen ways. High vibrating frequencies of up to 12,000 r.p.m. give stronger concrete and speed up placing—and you can strike shattering sooner. At the same time, the 'Humdinger' flexible shafts operate at QUARTER SPEED.

And this means longer life and less maintenance—the drives just keep on running week after week.

Plant records prove that contractors and civil engineers are changing to 'Humdinger' after seeing the difference they can make in concrete placing. Prove it for yourself by using one on your next vibrating job. You can have a 'Humdinger' on trial or hire (with option).

PETROL AND ELECTRIC MODELS AVAILABLE

ACE MACHINERY LIMITED


VIBRATOR DEPT., PORDEN ROAD, BRIXTON, LONDON, S.W.2 Telephone: Brixton 3293 (9 lines)

Buy and you buy RELIABILITY

BIERRUM & PARTNERS · LTD

CIVIL ENGINEERS
AND CONTRACTORS

350 FT. HIGH REINFORCED
CONCRETE CHIMNEY
FOR
IMPERIAL CHEMICAL INDUSTRIES LTD.




167-173 IMPERIAL DRIVE

HARROW

MIDDX.

one yard - or hundreds

**from a small transportable concrete
batching and central mixing plant**



Photograph by kind permission of Stamford Construction Ltd.

MILLARS'

will be happy to supply details on the above 'Universal' set-up, which is one of the handiest, most economical and up-to-date plants yet designed for the production of dry-lean and quality concrete, or for the batching of truck mixers.

Ask also for information on other batching and central mix plants, the Millars' range of mixers, wellpoint dewatering system and asphalt and coated macadam plant.

MILLARS' MACHINERY CO. LTD

Licensees of the Vacuum Concrete, Rheax sand classification and Prepackt concrete grouting processes.

Head Office: Pinners' Hall, Great Winchester Street, E.C.2. Tel: London Wall 4266/9

Works: Bishop's Stortford, Herts. Tel: Bishop's Stortford 694/5



It's Evodyne, of course—
No special primer required—
Proof against acids, alkalis,
corrosive gases and salt water.

EVODYNE

CHLORINATED RUBBER PAINTS

A PRODUCT OF **EVODE** OF STAFFORD

Manufacturers of: BITUGEL, EVOKOTE and EVOTECT paints

SEND FOR LITERATURE EVODE LTD. (PAINTS DIVISION) STAFFORD. Telephone: 2241 (5 lines)


London Office: 82 VICTORIA STREET, S.W.1. Telephone: ABBey 4622 (3 lines)

* Are YOU using the EVO~~D~~E PERSONAL SERVICE to DESIGNERS? Write or phone our London Office for details

P-10-184

BOULDER-BUILT

better-service equipment



THE BOULDER CONCRETOR

for GUNITE work

The BOULDER CONCRETOR makes Gunite work an easy and economical operation. Its high speed of application enables Gunite 2 in. thick to be applied to vertical surfaces at up to 360 square feet per hour. Its low working cost also makes it suitable for many purposes for which Gunite is not normally specified.



THE BOULDER GROUTER

*for GROUTING and
cable-duct grouting
for prestressed concrete*

The BOULDER GROUTER is ideal equipment for placing grout at low to medium pressure in tunnels, mines, etc., raising road and floor slabs, consolidating bridge piers, general foundations, rock fills and the stabilisation of railway embankments. This is also very suitable equipment for prestressed concrete work for grouting cable ducts.

ASK FOR LITERATURE


BOULDER EQUIPMENT LTD

HIGH STREET, BARNET, HERTS. TELEPHONE: BARNET 4141

JANUARY, 1960. CONCRETE AND CONSTRUCTIONAL ENGINEERING

21

FLEET BUILDING • LONDON



ARCHITECT: W. S. FROST, A.M.T.P.I., SENIOR ARCHITECT TO MINISTRY OF WORKS

ANOTHER PROJECT

BY

TERSONS

LONDON • BIRMINGHAM • EDINBURGH

BRADFORDS FOR CONCRETE DESIGN AND CONSTRUCTION

Bradford's record stretches back to
the beginning of the concrete industry.

Over the past sixty-two years
they have accumulated great experience,
adding to their skills
and consistently exploiting all
fresh developments in their craft.

1898



REINFORCED CONCRETE STRUCTURES

HOLLOW-BLOCK FLOORS

'OMNIA' FLOORS (Licensees)

PRE-CAST UNITS

GRANOLITHIC PAVING

STAIRCASES

CAST STONE

WATERPROOF CEMENT RENDERING

1960



F. BRADFORD & CO. LTD · ANGEL ROAD · LONDON · N.18

Edmonton : 4267

**BRADFORDS
FOR CONCRETE
DESIGN AND
CONSTRUCTION**

**CONCRETE
PROOFING
Co. LTD.**

**GUNITE
SPECIALISTS**

Expert advice and schemes submitted for gunite work of every kind. Complete information on the various uses of gunites will be gladly sent on request

116 Richmond Road, Kingston-upon-Thames, Surrey. KINGSTON 7853 and 9232
Telephone:

*Ensure
safety
with*

**DORMAN
LONG Steel Trench Sheeting**
(Regd. Design No. 850,839)

**The ideal for temporary lining,
easy to drive: can be used over and over again**

PROMPT DELIVERY

Prices and full particulars on application to

DORMAN LONG (Steel) LTD., SHEET DEPT., AYRTON WORKS, MIDDLESBROUGH
London Office: Terminal House, 52 Grosvenor Gardens, S.W.1





BUILDING AND CIVIL ENGINEERING BY

Simon-Carves Ltd

STOCKPORT, ENGLAND
SIMON
CARVES GROUP

and at CALCUTTA
SC 225

JOHANNESBURG

SYDNEY

TORONTO

Designing and building handsome colliery structures like these is one of the ways in which Simon-Carves are helping to implement the N.C.B.'s current policy of retrenchment and modernisation.

The pictures were taken at Bilston Glen, where a new colliery is under construction for the Scottish Division of the N.C.B. Above: the men and materials winding headframe and airlock, and associated buildings, seen from the coal-winding headframe. Below: a general view of the site, with the washery and settling tank in the foreground. Simon-Carves Ltd. are responsible for all structural design at this new colliery, as well as for the design and supply of the skip and cage-winding plants and the coal preparation plants.

Further constructional and reconstructional contracts for the N.C.B. are currently being carried out at Killoch Colliery, Scottish

FOR THE MINES

Division, at Bold Colliery, Agecroft Colliery and Clockface Colliery, North Western Division, and at Cotgrave Colliery, East Midlands Division.

3 DEPENDABLE SERVICES FOR YOUR CONTRACTS IN

BEDFORDSHIRE. LINCOLNSHIRE. LEICESTERSHIRE. DERBYSHIRE.
NOTTINGHAMSHIRE. NORTHAMPTONSHIRE. BUCKINGHAMSHIRE.
OXFORDSHIRE. HERTFORDSHIRE. CAMBRIDGESHIRE.

HOWARD'S of BEDFORD

for supplies of
**CONCRETE
AGGREGATES**

We supply the best washed and graded aggregates and sand, provide an excellent delivery service to your schedule, and give immediate attention to all requirements.

HOWARD'S of BEDFORD

for supplies of
**PRECAST
CONCRETE**

Well-matured stocks of concrete kerbs, fencing posts, paving slabs, lintels, cycle blocks, etc., are always available for prompt delivery in any quantity.

HOWARD'S of BEDFORD

**CONCRETE
BUILDING
BLOCKS**

Standard concrete building blocks of excellent quality can be supplied by us ex-stock in any quantity—large or small.

C. A. E. C. **HOWARD LTD**

ST. JOHN'S WORKS, BEDFORD. TELEPHONE: 4024-6



LINLITHGOW BRIDGE TRUNK ROUTE A9

UNDER CONSTRUCTION FOR SCOTTISH
HOME DEPARTMENT

Engineers
F. A. MACDONALD & PARTNERS

THE REINFORCED CONCRETE ARCH
HAS A CLEAR SPAN OF 108 FEET



CONTRACTORS

JAMES MILLER & PARTNERS LIMITED

BUILDING & CIVIL ENGINEERING CONTRACTORS
18 GEORGE STREET EDINBURGH 2 CAL 1331

Also at:

GLASGOW · LONDON · HAYES, MIDDX. · WAKEFIELD · BIRMINGHAM

1994



**On the subject of
PIPES, moulds and
equipment . . .**




As manufacturers of all types of steel moulds and formwork for precast and in-situ concrete production, we welcome your enquiries in this specialised field. If required our experienced staff will plan a comprehensive scheme for the manufacture of your precast units on site.

Coneybeare

THE ORIGINAL PIPE MOULDS

CONEYBEARE & CO. LTD., 89-91 Greenwich Church St.,
London S.E.10

Telephone: Greenwich 0821



For compacting mortar cubes
for compression tests to

B.S. 12/1958, 146, 1370, 915

Automatic Time Control

"CAPCO"

H.F. VIBRATOR

"CAPCO" CONCRETE TESTING APPARATUS also includes:
Cube Moulds; Slump Cones; Tensile, Vicat and Cylindrical
Moulds; Compacting Factor Apparatus—Standard and Auto-
matic; Sieve Vibrators and Sieves ; etc.

CAPLIN ENGINEERING CO. LTD

ALPAX WORKS, ST. LEONARDS ROAD, WILLESDEN JUNCTION, LONDON, N.W.10
'Phone: ELGAR 7191. Grams: CAPLINKO, London, N.W.10. Cables: CAPLINKO, LONDON



A FIRST-CLASS SERVICE FOR ALL TYPES OF

REINFORCEMENT

DESIGN SUPPLY BENDING · FIXING OF
MILD STEEL · COLD WORKED BARS AND
HIGH TENSILE FABRIC

WE ARE THE SOLE MANUFACTURERS OF

COROBAR

(TRADE MARK)

THE COLD WORKED BAR
FOR
CONCRETE REINFORCEMENT

OFFICES :

ARDSHIEL HOUSE
EMPIRE WAY
WEMBLEY, MDDX.



WORKS :

RIGBY LANE
DAWLEY ROAD
HAYES, MDDX.


**THE ENGINEERING DESIGN & CONSTRUCTION
COMPANY LIMITED**

TELEPHONE: WEMBLEY 9474 TELEGRAMS: EDCON WEMBLEY






**EXTERNAL VIBRATORS
IMMERSION VIBRATORS
VIBRATING TABLES**



External .
Available in two sizes.



Immersion : Available in
diameters 30, 50, 70 and 100 mm.

**for all
concrete
vibration
in-situ and
precast**



Electric Shutter Vibrators



Vibrating Tables

**FOR TROUBLE - FREE AND
ECONOMICAL PERFORMANCE**

When you invest in Sinex Concrete Vibrating Equipment, the return is a 100 per cent. consolidated concrete, plus the advantage of easy handling with a consequent increase in the speed of placing. A frequency of 18—20,000 r.p.m. is obtainable. Two air-cushioned moving parts and no bearings, together with robust construction, ensure a long working life with negligible maintenance costs and freedom from breakdowns.



Worldwide sales and service. The largest compressed air equipment manufacturers in the Commonwealth.

Sole manufacturers **SINEX ENGINEERING CO. LTD.**
NORTH FELTHAM TRADING ESTATE, FELTHAM, MIDDLESEX Telephone: FELTHAM 5081

PRELOAD

design and construction of
PRESTRESSED CONCRETE



PRESTRESSED TANK

with a capacity of 2,000,000 gallons, designed and constructed by us for the River Dove Water Board at Whatborough, Leicestershire.

Engineer : Mr. H. Wallhouse, M.I.C.E.,
M.Am.S.C.E., M.I.W.E., A.M.I.Mech.E.

We specialise in the design and construction of prestressed concrete tanks, for which preliminary designs and estimates of cost are offered without obligation.


PRELOAD Ltd.

20 LOWNDES STREET,
LONDON, S.W.1.
Telephone : Belgravia 3276

CLIFTONVILLE,
NORTHAMPTON.
Telephone : 32235

if your
contract
is in this
area . . .

Specify



FAIRLOP READY-MIXED CONCRETE

CONCRETE AT ITS BEST

CONCRETE — to your specification

CONCRETE — designed to your requirements

CONCRETE — delivered — Plant- or Truck-Mixed

FAIRLOP READY MIXED CONCRETE CO. LTD.

FOREST ROAD, FAIRLOP, ILFORD, ESSEX TELEPHONE: HAINAULT 5665/6 & 6111

**"Your
attention
appears
to be
wandering,
Abercrombie"**

"I was just looking at the new houses, sir."

"But surely you've seen new houses before?"

"Yes, sir, but Boots are building these, sir. That's why they're going up so jolly fast. My father says if everyone built houses as fast as Boots, there jolly well wouldn't be any shortage. Same goes for factories, sir, and schools and hospitals and bridges and airfields and roads, sir. Boots build



them all and lots more things besides. I'll bet there isn't anything they can't build quicker and better than anyone else, sir."

"If you knew as much about pitching tents, Abercrombie, you'd have been a patrol leader six months ago."

Henry Boot



HOUSING ESTATES · RAILWAYS · WATER DISTRIBUTION SCHEMES
ROADS · SOIL STABILISATION · BUILDING PROJECTS OF EVERY
DESCRIPTION

HENRY BOOT & SONS LTD., BANNER CROSS HALL, SHEFFIELD 11. TEL: 54331.
LONDON: 10 The Boltons, London, S.W.10. BIRMINGHAM: Phessey Estate, Great Barr, Birmingham, 22A.
GLASGOW: Baillieston, Lanarks. MANCHESTER: Atlantic Street, Broadheath, Altrincham.
LIVERPOOL: Heysham Road, Dunnings Bridge, Aintree, Liverpool 10.

NOW! SLASH LABOUR AND TRANSPORT COSTS ON SLAB SHUTTERING WITH THE

MILLS

pecco-beam



- * Proven safety factor 2.2:1
- * Lightning adjustment from 8' 6" to 27' 7"
- * Unique one-stroke wedge lock
- * Makes propping obsolete
- * Free work areas for kindred trades below
- * Two basic components: lattice section and plate section
- * Immediate delivery from nearest **MILLS** depot

**The new all-steel
eliminates propping**

LOWEST EVER LABOUR COSTS

Here's the quickest, easiest and safest slab shuttering support ever devised—the Mills Pecco-Beam.

In minutes, the components can be telescoped to any span between 8' 6" and 27' 7". The span is locked with a steel wedge—rammed home with one blow of a hammer—and beams are ready to hoist into position. There are no loose parts; no screws to burr; and the timber cutting and intermediate propping required for conventional shuttering is eliminated. Kindred trades can work unhindered in the area below.

FREE PLANNING SERVICE Mills Drawing Office provides a free planning service to users of the Pecco-Beam. Also a six page leaflet, containing a loading table and full details of the Beams, is available from your nearest Mills Depot.


THERE'S NO LIMIT TO THE SUPPORT

WHY MILLS pecco-beam GIVES MAXIMUM STRENGTH AND SAFETY

The plate section of the Pecco-Beam is a strip of steel moulded to a 'V' shape (see head-on drawing) so the steel is 'doubled' along the length of the beam, instead of being only a single strip as on some other plate sections. The Pecco-Beam has a high degree of horizontal and torque stability. On site considerable savings are possible in transport, maintenance and labour costs, because—THE GREATER LOAD CAPACITY OF PECCO-BEAM MEANS YOU CAN SHUTTER LARGER AREAS WITH FEWER SHORES.



Unique wedge-lock secured at one hammer blow. Adjustment made positive by a combination of camber and load.



Bearing prongs are drop forgings, welded to beams. Dove-tailed to avoid overlapping.



horizontal shoring which can spans up to 27' 7"


LEVEL SLAB ASSURED UNDER LOAD

Top bearing sections of the Pecco-Beam have a rolled-in camber. This levels out under load giving a flat surface, but because high grade steel is used to make the beams, the camber remains unaffected even after the shoring has been used hundreds of times.

MILLS SCAFFOLD CO. LTD.

(A subsidiary of Guest, Keen & Nettlefolds, Ltd.)

Crusley Works, Hammersmith Grove, London, W.6 (Riverside 3011)
Depots: Birmingham · Bournemouth · Bradford · Brighton
Bristol · Canterbury · Cardiff · Coventry · Croydon · Glasgow · Hastings
Hull · Ilford · Liverpool · London · Manchester · Middlesbrough
Newcastle · Nottingham · Oxford · Preston · Plymouth
Portsmouth · Reading · Rotherham · Southampton · Swansea




VARIOUS BEAM COMBINATIONS

Pecco-Beams have two lattice sections, one 8' 6" long, the other 11' 10" long. The plate section is also 8' 6". Spans from 8' 6" to 27' 7" can be obtained by alternating the types of beams used.

YOU CAN GET FROM

MILLS

The first prestressed concrete bridge in New Zealand




Blackett's Road Bridge at Whatawhata.

The tender for Blackett's Road Bridge, the first prestressed concrete bridge in New Zealand, was 11 per cent cheaper than the nearest tender by a conventional design. The success of the project has been reflected in over fifty prestressed concrete bridges since erected in New Zealand—all using Johnsons wire. For further details write for leaflet.

Johnsons were in at the start with wire for prestressed concrete. Their technicians worked with the Continental pioneers in the development of the technique, and today Johnsons wire is specified in a large number of important prestressing contracts.

Sponsor: Waipa County Council
Engineer: J. N. Anderson.
Design: Pre-stressed Concrete
(N.Z.) Ltd.
Contractors: B & B Concrete Co.
Ltd., Precast Units; M & S
Construction Co., Erection

wire was essential –
Johnsons
of course!



AIREBOROUGH RAWDON BENTON PARK SCHOOL
For the West Riding of Yorkshire County Council

Architects: Sir John Burnet, Tait & Partners,
10 Bedford Square, London W.I.

In collaboration with:
A. W. Glover, F.R.I.B.A., The County Architect.

Consulting Engineers:
Ove Arup & Partners,
8 Fitzroy Street,
London W.I.

SIMMS
SONS & COOKE LTD

for

**REINFORCED CONCRETE
CONSTRUCTION**

HEAD OFFICE: HAYDN ROAD, SHERWOOD, NOTTINGHAM
TELEPHONE : 66264

LONDON · MANCHESTER · BIRMINGHAM · LEEDS
and **TORONTO, Canada**

Testing concrete cubes on site

MILBANK-WELLS


**HYDRAULIC PRESS
AND CUBE MOULDS**

Immediate Delivery

Two Sizes : 4 in. and 6 in.

PRESSES and CUBE MOULDS

Testing to 16,000 lb. per sq. in. to
B.S. 1881.



Approved for
all Government
Contracts

IN USE
ALL OVER
THE WORLD

6-IN. PRESS
258 TONS

£235

4-IN. PRESS
110 TONS

£120

MILBANK FLOORS LTD


PRESTRESSED CONCRETE CONSTRUCTION

RIVER HOUSE, EARLS COLNE, ESSEX

Telephone: Earls Colne 410



PRESTRESSED FLOORS & ROOFS SPANS UP TO 40 ft.
FRAME BUILDINGS ALL TYPES



THE MOST ADAPTABLE FRAME BUILDINGS
FOR INDUSTRY AND AGRICULTURE

SINGLE SPAN • MULTI SPAN CANTILEVER

Established 1834

WILLIAM

COWLIN

AND SON LIMITED



Building Contractors



Head Office

STRATTON STREET, BRISTOL 2


Telegrams: CONSTRUCT, BRISTOL Telephone: 22132 (7 lines)

South Wales Office

PENARTH ROAD, CARDIFF

Telephone: Cardiff 32736 (2 lines)

*The Pioneers of Reinforced Concrete Construction in the
West of England*



An Electrically Driven PC3 Concrete Pump with mixer. Capacities from 20 to 24 cu. yds. per hour. Ranges actually obtained 135 ft. vertical or 1,500 ft. horizontal. Also smaller model PC4—8-10 cu. yds. per hour.

FOR SALE AND HIRE

EFFICIENT RECONDITIONING SERVICE

CONCRETE BY PUMP AND PIPELINE

- The latest and most efficient method of placing concrete.
- Life of Pump practically indefinite : all essential surfaces in contact with concrete are renewable.
- Pumpable concrete must of necessity be good concrete.
- Pump and Mixing Plant can be located at the most convenient position within the pumping range.
- The continuous output of the Pump at a constant speed governs the working of the whole concreting gang.

THE REGISTERED TRADE MARK OF

PUMPCRET

THE CONCRETE PUMP COMPANY LIMITED

THE CONCRETE PUMP COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone : Western 3546

Telegrams : Pumcret, Kens, London



shell roof
construction

RICE

& SON LTD

CONTRACTORS FOR
WORKS IN
REINFORCED CONCRETE

LONDON

BRIGHTON

MARGATE

CRAWLEY



..... thinking of rooflighting ?

or any other glass and ferro concrete structure, for that matter.

Lenscrete Limited can provide the answer.

The two pieces of literature illustrated provide useful information and technical data on all types of natural lighting for buildings. Details are given of Lenscrete's comprehensive range of translucent concrete construction and fibreglass, perspex and glass roof domes and metal ventilators.

Lenscrete Limited will be pleased to send you this literature on request.

Send for this catalogue ▶



LENSCRETE LTD

QUEEN'S CIRCUS LONDON SW8 Telephone: MACaulay 1063

COPPER STRIPS

for expansion joints

All Reinforced Concrete Engineers recognise the advantages of using copper strips for sealing joints in concrete work. Copper is ductile, will not crack under repeated bending, is non-corrosive and is unaffected by wet concrete. We specialise in the supply of perforated copper strips of all required lengths and widths for expansion joints, and shall be pleased to submit prices against detailed specification.



ALEX J. CHEETHAM LTD.


MORTON STREET • FAILSWORTH • MANCHESTER

Telephone : FAILsworth 1115/6

DS.14



MODERNISATION OF MOTIVE POWER DEPOT, YORK



Arched ribs in Concrete Spanning
55 ft. on to framed steel beams 204
feet in length.

Completed section in foreground is
of pre-stressed concrete beam con-
struction bearing on in-situ columns
and is glazed throughout.

Photographs by kind permission of
British Railways.

For the design, manufacture and erection of concrete structures

consult

Concrete Services Ltd

OUSE ACRES · BOROUGHBRIDGE ROAD · YORK · Tel. 70476

BERKELEY deserved the **BEST**

Reliable and accurate weigh batching.

300 tons storage of bulk cement.

Simple trouble-free control of aggregates.

Continuous recirculation of cement.

OUTPUT

350 cu. yds. concrete/day.

TO PRODUCE THE QUANTITY AND QUALITY OF CONCRETE REQUIRED BY THEM AT BERKELEY POWER STATION—DESIGNED AND CONSTRUCTED BY A.E.I. JOHN THOMPSON NUCLEAR ENERGY CO., LTD.—BALFOUR BEATTY & CO., LTD., CHOSE EONIT PLANT



EONIT

EONIT ENGINEERING COMPANY LTD., Structural and Mechanical Engineers, SLADE GREEN, ERITH, KENT. Tel: Erith 3441

A. E. FARR LTD.

Specialists in
Reinforced Concrete
Construction
for over
half a century

Head Office : WESTBURY, WILTS.

CUT YOUR CONCRETE COSTS

with the

A.B. MOULD MIXER- DRIVE SHOVEL


ALL BRITISH DESIGN AND MANUFACTURE

(Patent applied for)

At last !

The perfect combination of a winch unit attached to and driven by the mixer, but operated from the press-button-controlled shovel.

**THE BUILT-IN JIB ELIMINATES
SITE INSTALLATION COSTS.**



**LOW CAPITAL OUTLAY RECOVERED IN TEN WEEKS
NO RUNNING COSTS
FITTED TO MOST MIXERS**

Ask for a demonstration from :

A. B. MOULD & CONSTRUCTION CO., LTD.

VULCAN WORKS, VULCAN WAY
NEW ADDINGTON, SURREY

Telephone : Ledge Hill 2347

Telegrams : Ahmould, Croydon

MAIN RAILWAY LINE DIVERSION AT GLOUCESTER

This Contract for the British Railways, Western Division, included the construction of two concrete arch viaducts with an aggregate length of approximately 250 yards, a bridge spanning the River Severn and $\frac{1}{2}$ of a mile of embankment and double track.



DOUGLAS

CIVIL ENGINEERING AND BUILDING CONTRACTORS

SPECIALISTS IN REINFORCED AND PRESTRESSED
CONCRETE CONSTRUCTION

ROBERT M. DOUGLAS (CONTRACTORS) LTD


BIRMINGHAM

SWANSEA

STOCKTON

LONDON OFFICE: 47 VICTORIA STREET, S.W.1

TELEPHONE: ABBEY 4077



35-TONS PRECAST BRIDGE SECTION

We illustrate one of the 35-tons sections produced by Anglian Building Products Ltd., of Atlas Works, Lenwade, Norwich, and 14 Stanhope Gate, London, W.I., for British Railways L.M. Region. Main Contractors: Leonard Fairclough Ltd.

WOODEN MOULD


was produced by

MAY & BUTCHER LTD

SPECIALISTS IN TIMBER SHUTTERS AND MOULDS FOR CONCRETE

More and more Contractors and Precast Concrete Makers in all parts of the country are taking advantage of the first-class service we offer in the supply of timber shutters and moulds to any design and size. This service has proved over and over again that by ordering your shutters and moulds from us you effect every possible saving in time, labour and money. However intricate the shutter or mould, you are assured of accuracy in every detail and a product with long trouble-free life. Shutters and moulds can be supplied with a plastic lining if desired. Full details of this class of work carried out by us are available on request.

HEYBRIDGE BASIN, MALDON, ESSEX. TELEPHONE: MALDON 698/9



LONGDENS

OF SHEFFIELD


ST. PETERS CLOSE : SHEFFIELD 1 : TELEPHONE 26457

HILTON GRAVEL

SEVEN
PITS

250
LORRIES

8,000
TONS
PER DAY



FOR QUALITY & SERVICE

REGULAR DELIVERIES THROUGHOUT

- | | | |
|----------------|---|-----------------|
| STAFFORDSHIRE | • | CHESHIRE |
| DERBYSHIRE | • | NOTTINGHAMSHIRE |
| WEST RIDING | • | LANCASHIRE |
| SHROPSHIRE | • | WARWICKSHIRE |
| LEICESTERSHIRE | • | RUTLAND |

The illustration above shows one of our seven pits equipped with the most modern washing and grading plant for producing concrete aggregates that will satisfy the most exacting requirements for cleanliness and grading to specifications.


READY
MIXED
CONCRETE

20 miles radius
MANCHESTER

From our Plant
at
RICE STREET
MANCHESTER 3

DEAnsite 5455

HILTON GRAVEL LIMITED
HEAD OFFICE: HILTON, DERBY. Tel: ETWALL 422



SHELL ROOF CONSTRUCTION

We illustrate here a model of a covered market with an unusual type of north light shell roof now in course of construction by us at Plymouth. Architects: Messrs. Walls & Pearn. Designed by British Reinforced Concrete Engineering Co. Ltd.

A. N.

COLES

(CONTRACTORS) LIMITED



**LONDON, BRISTOL
PLYMOUTH & ISLES OF SCILLY**

Head Office: Sutton Road, Plymouth.
Telephone: 63207-9.


Bristol Office: Cornwall House, The Parade, Clifton, Bristol, S
Telephone: Bristol 30601

London Office: 49 St. Peterborough Place, W.1.
Telephone: Bayswater 7226.

ASSOCIATE COMPANIES:

ELLMORE & CO. LTD.,
CHURCH, BANK AND SHOP FITTERS,
SUTTON ROAD,
PLYMOUTH.

COLMORE ELECTRICAL LTD.,
ELECTRICAL ENGINEERS
AND CONTRACTORS,
SUTTON ROAD, PLYMOUTH.



In dams of this type—the very hub of extensive hydro-electric schemes—waterstops have a triple function to perform: seepage must be rigorously combatted, movement of concrete mass must be allowed for and future repairs obviated by the waterbars being resistant to corrosion.

As in the case of the dam shown here, Expandite waterstops, whether Rubber or Polyvinyl Chloride, have proved to be unsurpassed in performance where problems such as these have to be taken into consideration. Expandite have also developed an extremely economical Hydrofoil (PVC) having a unique profile: various widths are available.

These form only a section of the complete range of Expandite Products, sufficiently varied to solve joint-filling or sealing problems that occur in any form of constructional undertaking.

The Expandite Technical Service Department offers advice — without any obligation — to architects, civil engineers and builders on all questions of 'joints—that-move!'

**ANOTHER
JOINTING
PROBLEM
SOLVED**

EXPANDITE
LIMITED

*Specialists in the manufacture and use of Joint-Fillers,
Sealing and Waterproofing Compounds, Concrete Additives,
Anti-Corrosion Treatments & Mechanical Appliances.
Chase Rd., London, N.W.10. Tel: ELGar 4321 (14 lines)*

Northern Depot: Trafford Park Road, Manchester 17. Eire: Expandite (Ireland) Limited, Greenhills Road, Walkinstown, Dublin

ASSOCIATES AND DISTRIBUTORS THROUGHOUT THE WORLD



POWER for industry

Our range of industrial engines are a practical proposition for many types of industrial equipment . . . compressors, cranes, pumps, contracting equipment, earth borers, generators, railcars, welding plant, works trucks, tractors and conversions. Simple design, modern flow-line production methods and common interchangeable parts contribute to the low cost of these high efficiency engines. And remember, every engine is fully backed by a World-wide Parts and Service Organisa-

sation. Take your choice from a wide power range . . . Diesel 20 to 86 b.h.p. and Petrol 11 to 87 b.h.p. (12-hr. rating).

DIESEL ECONOMY—have you considered the replacement of existing power units in your equipment and trucks with the famous 4D Diesel engine? You'll have the unique advantages of economy, long-life and low running costs . . . plus the best service in the World!

Wherever you are, whatever your problem,



MOTOR COMPANY LIMITED
ENGLAND

are at your service

For further details of our

INDUSTRIAL ENGINES

and the equipment they power,
send the coupon to your nearest Ford Dealer
or direct to

Please send me technical brochures of your
*PETROL/DIESEL Industrial Engines. The
maximum B.H.P. required is.....at.....
R.P.M. Also, please send details of the follow-
ing equipment powered by your engines.

Name.....

Address.....

Nature of Business.....

Telephone No.

* Delete where not applicable

G51-21-1

RANALAH

for

STEEL MOULDS



Phone

BRIGHTON 62216-7-8-9

for IMMEDIATE ACTION

RANALAH STEEL MOULDS LTD
LOWER BEVENDEAN • BRIGHTON • SUSSEX



Rawlbolt charts showing full range of sizes and types with illustrated literature available on receipt of letter-heading or business card.

6

HEADS are better than one!

You never need to improvise with Rawlbolts. There are types exactly right for every bolt-fixing job. No. 5, for example, for the support of pipework, and No. 2 for use with Pipe-hangers and other gas fittings. Hook and Eye Rawlbolts (Nos. 3 and 6) have many uses, such as providing anchorage for guy ropes and cables, supporting suspended ceilings, etc. There's the Loose Bolt Rawlbolt (No. 1), inserted after the machine is slid into position, and the Bolt Projecting Type (No. 4), ideal for wall-fixings.

Rawlbolts give you bolt-fixings of enormous strength in a fraction of the time taken by any other method.

1 Loose Bolt Rawlbolt	2 Pipehanger Rawlbolt	3 Eye Rawlbolt
4 Bolt Projecting Rawlbolt	5 Rawlbolt fitted with Pipe Clip	6 Hook Rawlbolt

Every bolt-fixing job is far quicker with
RAWLBOLTS

THE RAWLPLUG CO. LIMITED




CROMWELL ROAD • LONDON • S.W.7

520


LACO POWER-OPERATED BAR BENDERS

THREE MODELS AVAILABLE FOR EITHER
 $1\frac{1}{4}$ ", $1\frac{1}{2}$ " or 2" CAPACITY



The **LACO** power-operated Bar Bender will handle round bars up to $1\frac{1}{4}$ " diameter. Several bars can be bent simultaneously according to the diameter of the material.

MAINTENANCE NEGIGIBLE



ALSO AVAILABLE THE 'LACO' RANGE OF BAR CROPPING MACHINES UP TO 2" CAPACITY

Hire purchase terms readily available

LAWLER, AYERS & CO. LTD

29 Broad Street House • 54 Old Broad Street • London EC2

Telephone: London Wall 6331 Telegrams: Jimcrow, London

MAIN FEATURES:

Two Turntables revolve simultaneously, the fast Turntable at more than 10 r.p.m. enabling a 1" hook to be bent in 3 seconds; the slow Turntable at $2\frac{1}{2}$ r.p.m. will bend a $1\frac{1}{2}$ " hook in 12 seconds.

FEEDING:

Bars are fed into the machine from left or right. Hooks are made clockwise or counter-clockwise. Flexibility of the machine ensures minimum handling of the bar during operation. This saves time.

AUTOMATIC STOP:

Turntables can be set to stop automatically at any angle to an accuracy of $\frac{1}{8}$ ". Identical bonds are repeatedly obtained. All gears steel and precision cut, pinions of heat-treated alloy steel. All shafts, even the slowest, fitted with grease-packed ball bearings.

EASE OF CONTROL:


One control only. Hand lever integral with foot pedal for operating machine in either direction.

Powered with either electric motor, gasoline or diesel engine to customer's requirements.

Coal conveyor trestles and tunnels

for North Thames Gas Board
at Beckton Gas Works

ENGINEERS North Thames Gas Board London S.W.



Concrete Piling Ltd

CIVIL ENGINEERING CONTRACTORS

10 WESTMINSTER PALACE GARDENS
ARTILLERY ROW LONDON S.W.1.

PHONE: ABBEY 1636/7



The first 1" thick

homogeneous fibreboard expansion joint filler

made in Great Britain

PD RESILEX

Complies with Air Ministry Specification 20158 - Part III Class 400.

Road and Runway grade of
asphalt sealing compound
available on request.

Standard Sizes

Thicknesses: 1" and ½".
Lengths: 4', 5', 6', 7', 8', 9',
and 10 feet.

Widths: From 2" to 48".
Special sizes and shapes to
order.

... also available in ½" thickness

The first British made 100% wood fibre expansion joint filler manufactured entirely from home produced materials which has many unique advantages wherever concrete is used.

It is impregnated by a new solvent injection process with a low volatile high residual binder guaranteeing saturation of all fibres.

It will not disintegrate when wet because of its water resistance and high wet strength.

Resilex is not laminated or otherwise fastened together; is unaffected by road and runway grade of sealing compound and can be delivered in pre-selected sizes. Fully descriptive leaflet on request.


MARKETED BY

LEARY'S FIBREBOARDS LTD.,
King William Street House,
Arthur Street, London E.C.4.
Telephone: MINCING LANE 2424 (25 lines)

THOMAS & PRICE (TIMBER) LTD.,
Lewis Road, East Moors,
Cardiff.
Telephone: CARDIFF 31506.



Recipe for right curing



Take a lifetime of experience (practical experience both on the job and in the research laboratory).

Add an intimate knowledge of concrete structures of all kinds, under all sorts of climatic conditions. (The S.B.D. technical team travel 500,000 miles every year meeting and solving concrete problems on the site).

Mix enthusiasm with this sort of practical 'know-how' (enthusiasm, as well as knowledge, is essential).

And what have you got?

"Ritecure"

the finest membrane
curing for concrete



STUART B. DICKENS LTD.

Reservoir in the Khyber Pass cured with "Ritecure".



Curing the St. Albans By-Pass with "Ritecure".



Clifton Bridge, Nottingham, cured with "Ritecure".

FREE LITERATURE

Of course, you know about "Ritecure". But just in case you haven't seen the literature write to the address below

Manor Way, Boreham Wood, Herts.
Tel: Elstree 2211.



The water tower illustrated has a protective Stic B stone covering stipple finish similar to that shown in the smaller photograph. Treated in this way it is completely protected from the atmosphere and will require no further attention for many years. Stic B can

be applied direct to new or old concrete and most other building surfaces. No other material affords such lasting protection, while remaining so easy to apply.

Descriptive literature available.

STIC B PAINT SALES LTD.

99 WANDSWORTH ROAD,

Telephone: REliance 5566/2178 Telegrams: Sticbelim, London, S.W.8

VAUXHALL, S.W.8

Steel Reinforcement



A complete service of Design, Fabrication and Fixing of Steel Reinforcement for all types of Reinforced Concrete Construction.

M.S. Bars to B.S.S. 785, bent, bundled and labelled, delivered to site ready for fixing. No loss of time in checking and sorting material. No loss of material due to prolonged storage on site.

T. C. JONES
AND COMPANY LIMITED



REINFORCEMENT ENGINEERS
11 BUCKINGHAM PALACE GARDENS,
LONDON, S.W.1 Tel: SLOane 6271
Head Office: Wood Lane, London, W.12
Tel: Shepherds Bush 2029
South Wales Office: Bute Street, Cardiff
Tel: 28786
Works: Shepherds Bush, London, Hammersmith, Middlesex,
Treasury, Glam.

P.S.C.


for all

FREYSSINET SYSTEM




... CONE
ANCHORAGE
FREYSSINET
POWER EQUIPMENT ...

One of the most recent developments in the Freyssinet system of prestressing has been the introduction of power stressing. An electric or I.C. operated motor driving an hydraulic pump is trailer mounted and the hydraulic circuit has been simplified to only two controls which require the operator's attention. These are mounted on the trailer assembly and the jack is thus completely remote-controlled. The advent of power stressing has increased the rate of tensioning by three or four times that of hand pumping.



... P.S.C. ANCHORAGE The 8/276

P.S.C. "MonoWire" Anchorage illustrated here shows a "Hydrarigid" welded seam-jointed metal sheath which screws into the anchorage. A new type of high-impact plastic cable spacer is also available. These anchorages can be supplied for cables of one to twelve wires.



P.S.C. MONOWIRE POST-TENSIONING ...

This illustration shows the P.S.C. lightweight single-wire jack stressing one of twelve wires on a 12/276 "MonoWire" anchorage. The jack is available with 4" or 6" extensions, and has a spring return.

prestressing equipment



... P.S.C. GROUTING EQUIPMENT

We have made considerable investigations into the grouting of prestressed cable ducts, particularly with regard to the composition of the grout, its mixing and injection. This experience has enabled us to produce trouble-free grout injection pumps, both hand and power operated, designed specifically for cable duct grouting. The illustration shows the use of hand diaphragm-operated direct displacement grouting equipment.

P.S.C. MONOWIRE PRE-TENSIONING . . .

The P.S.C. "MonoWire" pre-tensioning jack illustrated here is available with extensions from 9" to 24". The hand-operated equipment is extended hydraulically and returned pneumatically. The power-operated pump (electric or I.C.) is recommended where a large number of long extensions is anticipated.




HYDRADUCT SHEATHING FOR PRESTRESSED CONCRETE

This range of sheathing includes "Hydrarigid" and "Hydraflex". It is highly efficient and easy to use, and is strong enough to take the weight of men without damage, yet flexible enough for all normal prestressing requirements. Supplied in standard lengths in diameters from 2" to 4".

... BRIDGE BEARING PADS

The Freyssi Bearing Pad,

Illustrated here, has proved its economy and efficiency on over 400 bridge contracts. Each pad is designed specifically for individual requirements from information obtained from a technical questionnaire, on which we ask certain design considerations. Full details are available on request.



FREYSSI FLAT JACKS . . .

Freyssi Flat Jacks are hydraulic jacks of unusual and unconventional design, which permit enormous forces to be exerted or regulated where the movement required is small. They have applications in underpinning, levelling and thrust control in engineering structures.

PSC



EQUIPMENT LTD

HEAD OFFICE AND WORKS: ARUNDEL ROAD, INDUSTRIAL TRADING ESTATE, UXBRIDGE, MIDDLESEX

Telephone: Uxbridge 5242

PIONEERS OF PRESTRESSED CONCRETE IN GREAT BRITAIN

THE GAMMON-MORGAN WATER-IN-SAND ESTIMATOR



MOISTURE VARIATIONS IN THE SAND

ENGINEERS should specify that the concrete mix shall be adjusted for moisture variation in the sand, so that the total water in the batch shall consist of the water carried in the aggregates plus the water added in the mixer.

No weighing or chemicals are required, and an adequate sample is used. The GAMMON-MORGAN WATER-IN-SAND ESTIMATOR should be available alongside every mixer, so that the water content of every mix may be correctly gauged. Full details will be sent on request.

PRICE £3 10s. 0d. each (10 Canadian or U.S. dollars).
CARRYING CASE £1 15s. 0d. (5 Canadian or U.S. dollars).

ACCURATE
SIMPLE
RAPID
measuring of
WATER CONTENT
IN SAND

COLCRETE LTD.

Appearance enhanced, protection assured . . . with

'PUDLO'

CEMENT
WATERPROOFING POWDER

Owner: A. J. BINGLEY, Esq., Bristol
Architect: MAJOR G. RAYMOND
MORGAN, F.I.A., F.I.A.S., etc.



SPECIFICATION

2 parts coarse, washed sand, well graded and perfectly clean, passing a $\frac{1}{2}$ " sieve down to that retained on a 50×50 sieve.

1 part Portland cement.

5 lb. 'Pudlo' cement waterproofer to each 100 lb. of cement.

The rendering was applied in two coats to a total thickness of $\frac{1}{2}$ " with a final dashing of white spar.

The simple addition of 'PUDLO' Cement Waterproofer to the rendering used on this very attractive house has ensured that the exterior will stay bright and clean for years to come. 'PUDLO' Waterproofer not only stops penetrating damp but also prevents dirt from being drawn into the wall surface.

OTHER 'PUDLO' PRODUCTS INCLUDE:

Waterproof Cement Paints, Cement Paint Primer, Cement Bonder, External Water Repellent, Plaster Bonder, Frost Protector/Rapid Hardener, Mortar Plasticiser, Cement Hardener/Dust Proofer, 'Feusol' Fire Cement.

The word 'PUDLO' is the registered Trade Brand of Kerner-Greenwood & Co. Ltd., by whom all articles bearing the Brand are manufactured.

'PUDLO'

Sole Proprietors and Manufacturers

KERNER-GREENWOOD & CO. LTD., KING'S LYNN, NORFOLK

"COL-O-ROCK"

Registered Trade Mark

EXPOSED-AGGREGATE PANELS

by

J. A. KING & CO., LTD

Write or Phone

181 Queen Victoria St., LONDON, E.C.4

Telephone: CENTRAL 5866 (5 lines)

Telegrams: Kinovique Cent London

GUNITE SPECIALISTS

WM. MULCASTER

& CO. (CONTRACTORS) LTD.


We invite inquiries for Gunite Linings and Renderings
for new or old structures of every kind in any part
of the country.

HASLINGTON

Telephone: Hasling 2265-4.

CREWE

reinforcement



BY PASHLEY & TRICKETT

Reinforcement for all types of concrete construction is supplied accurately bent to schedule, clearly identified and delivered by our own road transport to the site as required. Quotations are dealt with promptly.



Pashley & Trickett Ltd

STOKE STREET · SHEFFIELD 9

TELEPHONE: 41136-7

BEHIND EVERY JOB...



25 years' experience in
the scientific repair of
engineering structures.

WHITLEY MORAN

AND CO. LTD

GUNITE SPECIALISTS



5 OLD HALL ST, LIVERPOOL, 3
TELEPHONES: CENTRAL 7975/6
TELEGRAMS: 'GUNITE' L'POOL 3



IT'S THE RIBBED SECTION THAT



KEEPS DURAJOINT WATERTIGHT




"Durajoint" is a registered trade name. British patent number 646268. An arctic grade is available to withstand temperatures down to -40° C.

DURAJOINT, THE PVC CONCRETE EXPANSION JOINTING -WATERTIGHT, FLEXIBLE & TOUGH

In tests at the R. H. Stanger Laboratory, Durajoint 9" wide withstood a pressure of 150 lb./sq. in. (350 ft. head). Durajoint is supplied in standard rolls in widths of 2½", 3½", 6" and 9". The ends are easily spliced to make continuous lengths and T, X and L joints can be prefabricated at our works or made on site — write for a copy of our booklet "Durajoint and Duraseal".

There is nothing quite like DURAJOINT



 THE MICANITE & INSULATORS CO., LTD.,



Architects:
S. N. Cooke & Partners
F.R.I.B.A.

Main Contractors:
William Townson & Sons
Ltd., Bolton.

Maxweld reinforces it



The reinforcement fabric used in the Metal Box Company factory at Bolton was supplied by Richard Hill. Do you need reinforcements? Then call up the Maxweld man! He can give you all the facts on the type and quantity of fabric you'll need plus a rough idea of the cost.

And he's backed by the

Richard Hill Design Service

who can then draw up more detailed plans and estimates. You can get him at Middlesbrough (2206), London (Mayfair 3538), Birmingham (Mid. 5525),

Manchester (Central 1652), Leeds (2-7540),

Bristol (24977), Glasgow (Central 2179),

Nottingham (Bulwell 27-8383),

Bournemouth (Westbourne 63491),

Cardiff (46552), Belfast (29126).

Maxweld fabric

is manufactured by RICHARD HILL LIMITED (Established 1888)

Newport Wire and Rolling Mills, Middlesbrough, Yorkshire. Tel: Middlesbrough 2206

A MEMBER OF THE FIRTH CLEVELAND GROUP



CIRE 21 103

• PRESTRESSED PRECAST CONCRETE

Send your enquiries to
**FERROCONCRETE
(LANCASHIRE) LTD**

for all forms of prestressed structural members, precast concrete flooring and staircases, Cast Stone, and General Building Products.


WINDOW LANE, GARSTON,
LIVERPOOL 19

WOOLTON RD., ALLERTON STN.,
LIVERPOOL 19

ASHBURTON & REDCLIFFE ROADS,
TRAFFORD PARK, MANCHESTER



BOLTS & NUTS



**TIE-RODS
ETC.**

**FOR THE
CONTRACTOR**

Manufactured by

B. PRIEST & SONS LTD • OLD HILL • STAFFS • ENGL.
PHONES CRADLEY HEATH 6227 B 9 & 6220

**CONCRETE ROADS FIRST
because
CONCRETE ROADS LAST**



SOUTHPORT. 8" concrete carpet reinforced with two layers of mesh.

McCALL & COMPANY (SHEFFIELD) LIMITED

TEMPLEBOROUGH • SHEFFIELD • P.O. BOX 41

Telephone ROTHERHAM 2076 (P.B. Ex. 8 lines)

LONDON: SLOANE 0428

PORTSMOUTH: COSHAM 78702

BIRMINGHAM: ACOCKS GREEN 0229

NEWCASTLE: 38793

McCALL & COMPANY (SHEFFIELD) LIMITED

McCALLS MACALLOY LIMITED

PRECISION ROOFS LIMITED

McCALLS MACALLOY (AFRICA) (PROPRIETARY) LIMITED

McCALLS MACALLOY (AUSTRALIA) PTY. LIMITED

McCALLS MACALLOY (CANADA) LIMITED


SR.B. 91

THE DEMOLITION & CONSTRUCTION CO., LTD.
3 ST. JAMES'S SQUARE,
LONDON, S.W.1

Telephone : Trafalgar 7833

Turbo Alternator House

R. C. Design by G.K.N. Reinforcements Ltd.




**MODERNISATION OF
EAST GREENWICH WORKS
FOR S.E. GAS BOARD**

THE DEMOLITION & CONSTRUCTION CO., LTD.
3 ST. JAMES'S SQUARE, LONDON, S.W.1

Telephone : Trafalgar 7833

**Blending
Bunkers**

Consulting Engineer:
Major W. V. Zinn,
B.Sc., M.I.C.E.



The

**Demolition &
Construction**

Co. Ltd.

WW

REINFORCEMENT SERVICE *including* SUPPLY & BENDING

We are manufacturers of mild steel bars for reinforced concrete, and have every facility for supplying bars cut to required lengths. We also bend ready for fixing if desired for contracts in any part of the country. Include our name on your list for future reinforcement requirements.

WALKER WRIGHT & CO. LTD

DARNALL, SHEFFIELD, 9

TELEPHONE: 41063



Model VP 350-A (Swivel Base or Barrow Mounting)

Prompt Delivery. Highly Competitive Prices. Genuine Service. Re-Sale Terms Available.

* We operate a 48-hour Shaft Repair Service for all makes. Write to-day for 8-page fully descriptive Catalogue. Agents throughout the world.

30 years' experience in the design and manufacture of flex-shaft tools.

THE FLEXIBLE DRIVE & TOOL CO., LTD.

EDENBRIDGE, KENT. Telephone: 3385-6

LONDON OFFICE: 17 QUEENSBERRY WAY, S.W.7. Telephone: KENSINGTON 3583

For Greater Strength, Firmer Bonding
and Better Surfacing of Concrete—

"BAXTUL"
Regd. Trade Mark British Made

Extra-High Frequency
INTERNAL CONCRETE VIBRATORS



- The model illustrated here operates at 9,000 to 15,000 Vibrations per minute from low flexible shaft speeds of 4,500 to 7,500 R.P.M.
- Petrol or Electric Drive.
- Robustly built throughout and backed by genuine service.
- Fitted centrifugal clutch, long-life flexible drive and Vibrator.

This unique machine, with quick-change additional tools, can also be used for: SURFACING, WET-RUBBING CONCRETE, GRINDING, DISC SANDING, AND DRILLING (up to 1½" in Concrete, 1" in Steel, and 2" in Wood).

STRAND OR WIRE STRESSING

PRE- AND POST- TENSIONING

Here is an economical and portable stressing set of high quality. Interchangeable components enable the same jack to be used for stressing wire or strand.



Three standard forms are available:

1. For 3/8" and 7/16" diameter strand.
2. For 0.128", 0.200" and 0.276" diameter wire.
3. For both wire and strand.

The jack works in conjunction with an instant-release grip, which permits rapid change-over on multiple work, and caters for long extensions (a second or third bite can be commenced within seconds of reaching maximum jack travel).

The set comprises self-retracting 6" or 12" extension jack, hand pump, pressure gauge, 6' length flexible hose with quick couplings, instant-release grip and jaws. These are all contained in a stout wooden box from which the pump may be operated without removal.

U.K. Ex-Works prices as follows:

	6" extension	12" extension
Complete Set for Strand Stressing	£95	£115
Complete Set for Wire Stressing	£87	£107
Complete Set for Both Wire and Strand	£114	£134
Conversion Set Strand to Wire	£19	
Conversion Set Wire to Strand	£27	

Send for our new booklet covering both pre- and post-tensioning.

STRESSING DEVELOPMENTS LTD.

95 KINGSTON HILL, KINGSTON-UPON-THAMES

TELEPHONE: KINGSTON 2372

Precision in Concrete Cover...



for fully
illustrated
brochure

Write Now!

A revolutionary economy
for lightness, speed of
handling, and range of
application—for reinforcing
bars in concrete.

with **ABIT**  Plastic Distance Pieces

PATENTED. Regd. Design 893503.

Samuel & Son (moulders) Ltd

WREN MILL, CHADDERTON, LANCS. Sales Office: Tel: Manchester DEA 4671/2
Sole Manufacturers and Distributors of ABIT pk Plastic Distance pieces (A.B.
ABERG No. 31269/58) in Great Britain, The Commonwealth and Eire.

means 

NEW ECONOMY

MACALLOY

The Lee-McCall system of prestressing concrete using 'Macalloy' bars offers striking economies to the contractor:

General ease of construction and supervision on site.

The large-diameter 'Macalloy' bars are easy to feed into preformed ducts; make a rigid sheathed tendon easily located and needing a minimum of support.

Tolerances permit minor variations in unit length to be accepted without extra cost.

Bars with rolled threads do not need critical setting up.

Grouting is economical and trouble-free.

Bars with wedge anchorages can be kept on site and used from stock.

These and many other points of superiority make 'Macalloy' bars the most economical, simple, reliable and practical system of prestressing.

McCALLS MACALLOY LIMITED TEMPLEBOROUGH • SHEFFIELD • P.O. BOX 41

Telephone: ROTHERHAM 2096 (P.S. Ex 8 lines)

LONDON: SLOANE 0428 PORTSMOUTH: COSHAM 78792
BIRMINGHAM: ACOCKS GREEN 0229 NEWCASTLE: 38793

Prestressing
STEEL
By McCall's


MC CALL & COMPANY (SHEFFIELD) LIMITED
MC CALLS MACALLOY LIMITED
PRECISION ROOF LTD

MC CALLS MACALLOY AFRICA (PROPRIETARY) LIMITED
MC CALLS MACALLOY (AUSTRALIA) PTY. LIMITED
MC CALLS MACALLOY (CANADA) LIMITED

one of the most widely used BAR-BENDERS throughout the world

THE 1960 ARD.50 MODEL illustrated at the top of the facing page is a machine to ensure accuracy, simplicity and economy in all bending operations. The machine has an automatic control which permits the desired bending angle to be pre-set, greatly facilitating repetitive bending. The ARD.50 is a twin-head machine to bend all diameter bars from $\frac{1}{2}$ " to 2". The illustration in the centre of the facing page shows the bending of an angle loop in one operation and the bottom illustration on the facing page shows the ARD.50 fitted with the backstop cage for multiple bending of small diameter bars. This machine is supplied complete with standard accessories for bends on a 4D basis and can be fitted with Electric motor, Air-cooled Petrol engine or Air- or Water-cooled Diesel engine.

THE 1960 RAS.40 MODEL illustrated below is a single-disc machine which is specifically designed for an extraordinary high-bending production of bars up to 1½" diameter. A full head takes three seconds' bending time. This model can be supplied motorised or engine driven.



We also supply, at extra cost, a special device for bending Hoops and Spirals, and formers and backrests for special steel such as "Square Grip", and "Twisteel", etc. For full details, send to

CEMENT & STEEL LTD

SECOND AVENUE,

CHATHAM,

KE


Telephone: Chatham 45580.

Telegrams and Cables: Cembelgi, Chas

JANUARY, 1960.



CONCRETE AND CONSTRUCTIONAL ENGINEERING

2612



1960 ARD.50 MODELS

FOR SALE
OR HIRE



**WATERTIGHT
LININGS
FOR
RESERVOIRS,
SWIMMING
POOLS, ETC.**



**LININGS
FOR
TUNNELS,
SEWERS,
TANKS.**

*Specialists in the Repair and Reconditioning of
Reinforced Concrete Structures, etc.*

THE

Telephone :
Comite
Hitchin

GUNITE
CONSTRUCTION CO LTD
WESTERN HOUSE, HITCHIN, HERTS.

Telephone :
Hitchin
4371

**Best Quality
CONCRETE
AGGREGATES
in all grades**

DELIVERED BY ROAD OR RAIL
WM. BOYER

& SONS LTD

MEMBERS OF S. & G.A. of G.B.

ESTABLISHED 1810

IRONGATE WHARF, PADDINGTON, W2

TELEPHONE : PADDINGTON 20244

**SCHMIDT
CONCRETE TEST HAMMER**



for immediate non-destructive determination of compressive strength
O. A. VOLKMANN, 3 ST. AUGUSTINE'S ROAD, BIRMINGHAM, 16
Telephone : Edgbaston 1353



9-STORY BLOCK OF FLATS AND MAISONETTES FOR THE BOROUGH OF WOOLWICH. DESIGNED AND REINFORCEMENT SUPPLIED BY JOHNSON'S REINFORCED CONCRETE ENGINEERING CO. LTD. REINFORCED CONCRETE CONSTRUCTION BY MESSRS. O. H. GROVES & CO. LTD., LONDON, S.E.I.

Borough Engineer: W. H. Gimson, O.B.E., B.Sc. (Eng.), M.I.C.E.

JOHNSON'S


REINFORCED CONCRETE ENGINEERING CO. LTD.

*for reinforced concrete design
and electrically-welded
steel wire lattice in
rolls or flat sheets*

Artillery House, Artillery Row, London, S.W.1. Telephone: Abbey 2648.
18 Booth Street, Manchester; 191 Corporation Street, Birmingham.

CURVED CONCRETE ROOF

The extensions carried out by us at Sunderland Technical College included the construction of a curved concrete roof, illustrated here. Architect: Mr. H. C. Bishop. Reinforced Concrete Design by British Reinforced Concrete Engineering Co. Ltd.



GEO. H. PLEMPER LIMITED

BUILDING CONTRACTORS AND
SPECIALISTS IN REINFORCED CONCRETE

ST. HILDAS WORKS,

OLD CHESTER ROAD,
TELEPHONE: 58222/3

SUNDERLAND

It is

safest to specify STENT!

STENT PRECAST CONCRETE PILES

12" x 12"
14" x 14"
16" x 16"
18" x 18"

Preferred by constructional engineers for their unchanging supremacy, Stent Precast Concrete Piles have proved their qualities wherever used.

STANDARD SIZES

12" x 12" in lengths 15 ft. to 40 ft.
14" x 14" in lengths 15 ft. to 55 ft.

Other sizes made to order.

AVAILABLE FOR IMMEDIATE DELIVERY

May we forward full details.

STENT PRECAST CONCRETE LTD.

Chequers Lane, Dagenham Dock, Essex. Dominion 0971

concrete
protection
during
construction

PROMPT DESPATCH
COMPETITIVE PRICES

CHAPMAN'S WATERPROOF CONCRETING PAPER

conforms to B.S. 1521, Class B, and is available at short notice in large or small quantities for contracts in any part of the country.

AND POLYTHENE ROLLS

can be supplied in various widths for many protective purposes in building work.

H. W. CHAPMAN LTD, THE EMBANKMENT, WELLINGBOROUGH, NORTHANTS

TELEPHONE: WELLINGBOROUGH 2214

FOR THE LONG HAUL
RELY
ON

PLAZCRETE

THE MODERN AID FOR A WELL-DESIGNED CEMENT MIX

PLAZCRETE RETARDS THE SET

Permits longer haulage time
Avoids day joint problems

**PLAZCRETE IMPROVES WORKABILITY AND
PLASTICITY**

Makes pumping easier
Saves time placing and vibrating
Improves consolidation, particularly around reinforcement

**PLAZCRETE PERMITS A REDUCED WATER/
CEMENT RATIO**

Reduces shrinkage
Eliminates laitance, bleeding and segregation

**PLAZCRETE IN THE MIX REDUCES THE COST
WITHOUT ANY LOSS OF STRENGTH**

For further information write to Dept. PC.:

SEALOCRETE PRODUCTS LTD.,
ATLANTIC WORKS, HYTHE ROAD,
LONDON, N.W.10.

Telephone : *Ladbroke 0015, P.B.E.*
Telegrams : *Sealocrete, Wesphone, London.*



TRUCK-MIXED CONCRETE

**is regularly specified
for contracts
in this area**

PLANTS AT

Oxford Road, Ryton-on-Dunsmore, near Coventry.
Telephone: Tollbar 3204 and 3392

Tuttle Hill, Nuneaton.
Telephone: Nuneaton 4459

Cock Hill Lane, Rubery, Birmingham.
Telephone: Rubery 29



**A FIRST-CLASS SERVICE
is available to all users of
TRUCK-MIXED CONCRETE
in the area shown above**

*Include our name on your
list for future enquiries*

TRUCK-MIX (MIDLANDS) LTD

OXFORD ROAD

RYTON-ON-DUNSMORE

COVENTRY

TELEPHONE: COV. TOLLBAR 3204 and 3392



IBECO

WATERPROOF PAPER

IN CONCRETE ROAD CONSTRUCTION

Recommended quantities for concrete work are IBECO No. 40 to BS 1521/1949 Class B and IBECO No. 60, the choice depending on the stresses involved. The former fully meets the specification at the lowest possible cost. As well as preventing seepage from the mix IBECO also checks the upward penetration of harmful acids and other chemicals frequently occurring in subsoils. It also has useful applications as a curing overlay. There is no free bitumen in IBECO to sweat out under exposure to hot sun. We will gladly send samples on request.

For the essential retention of water in a concrete mix to ensure sound setting and hardening, careful contractors are more and more depending on IBECO... Like no other waterproof paper, IBECO is waterproof *throughout its texture*. The proofing bitumen is part of the paper itself. Folding, creasing, even heavy trampling will not impair IBECO's impermeability... It's easy and quick to handle—speeds the work as well as lowering its cost and ensuring a better job. Remember IBECO for contracts in hand and in prospect.


DAVIDSONS PAPER SALES LTD.

Head Office: Muglemoss Mills, Buckburn, Aberdeen. Branches: 82/84 St. John Street, London, E.C.I. 31 North John Street, Liverpool 2. 9 Albion Street, Leeds. 42 Corporation Street, Newcastle-on-Tyne. Laird Place, Bridgeston, Glasgow, S.E. Boroughmuir Square, Edinburgh. 4 Trinity Quay, Aberdeen.

ALL-BRITISH



HYDRAULIC BAR CROPPERS

FOR SALE
OR HIRE

for
Reinforced Concrete
Contractors

The Standard Bar Cropper, illustrated on the left, has a capacity ranging from one 1½-in. bar to eight ½-in. diameter or smaller bars, including rounds, squares and flats.

for
Precast Concrete
Makers

The small model, also illustrated, is specially designed to meet the requirements of the precast concrete maker. Its capacity includes one 1-in. bar down to multiples of smaller diameter bars, including rounds, squares, and flats.

E · P · ALLAM & CO. LTD.

LONDON: 132-135 Sloane Street, S.W.1. Telephone: Sloane 9976 (5 lines)
Works: Southend-on-Sea Tel.: Eastwood 22243

AGENTS & DISTRIBUTORS: Strangford Ltd., Belfast and Dublin; A. Gunn & Co. Ltd., Altringham, Chas.; O. L. Davis Ltd., Part Talbot, Glam.; J. Lewis (Machinery) Ltd., Burslem, Stoke-on-Trent; G. B. Carter & Son, Leeds and Huddersfield; John Rawlinson Ltd., Newcastle-on-Tyne; W. R. Salwood, Ltd., Chandler's Ford, Southampton; J. A. McRae & Co. Ltd., Glasgow.



P15 PORTASILO working on the construction
of Wilmslow Grammar School, Cheshire.
Contractors : L. Brown & Sons Ltd. Wilmslow

FOR HANDLING CEMENT IN BULK

- Fully proved on thousands of sites
- A range to suit all Concrete Mixers
- No condensation problems
- Backed by a first class after sales service
- Fully automatic, remote push button control provided by the addition of the Portasilo 'Autofeed' which can be interchanged between Portasilos as required
- FOR SALE OR HIRE

PORTASILO LIMITED

CONTRACTORS PLANT DIVISION, CORONATION ROAD, PARK ROYAL, LONDON N.W. 10
Telephone : ELGAR 6314 - 6215 - 3728

HEAD OFFICE : YORK
AND AT BIRMINGHAM, MANCHESTER, GLASGOW, BRISTOL, BELFAST AND DUBLIN

Write or phone today for details of full range of 11, 15, 20 and 30 ton capacity models or ask for a representative to call

PORTASILO

REGD.

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

Volume LV, No. 1.

LONDON, JANUARY, 1960.

EDITORIAL NOTES

Towards the Robot.

AT Queen's University, Belfast, recently, the Duke of Edinburgh again pleaded for the better education of technologists. In the course of his remarks he said:

"The conception of the university as simply a means to enhance the commercial prosperity of the State reduces higher education to the level of cattle breeding. So many square feet per student, so many years to mature, a course of technical instruction, graded by examination, packed in a diploma and delivered to industry free of charge, and another statistic joins the commercial battle. That way of thinking must be resisted at all costs. Unless higher education combines vocational training with the proper development of mind and character the universities are doing only half their job. The two great dangers of the commercial view of universities are that it encourages an unacceptably high degree of specialisation and that it produces men who are productive and useful only at the beginning of their careers instead of throughout the forty years of their expected working life. Science and technology will always be the controlling force in the nation's prosperity, but only so long as the manager-technologist has the benefit of a broad-minded traditionally liberal university education centred on his technical specialisation."

This is not the first time that His Royal Highness has commented on the shortcomings of our teaching system. In 1953, speaking at Edinburgh University, he dwelt on the "narrowness of mind which too many of the products of good schools and universities seemed to show", and emphasised the value to scientists and technologists of the more liberal education that imparts a broader outlook on specialised subjects. The Duke thus adds the weight of his authority to the views of many lesser men who have spoken and written in the same strain on a problem that is vital to the well-being of a nation that must increasingly depend upon its capacity for invention, which in turn depends only on powers of reasoning, to maintain its standard of living. There can, however, be no improvement without a higher standard of education of the students accepted by the universities and technical institutes. The educationists seem to be obsessed with the idea that the imparting to students of the rudiments of science and technology is more important than general education. This is largely the fault of those universities that have lowered the standard of education required of students

who sit for their entrance examinations, and refuse to educate the uneducated people whom they have admitted to their technological courses. London University has gone so far as to omit English as a subject in its examination for degrees in technical subjects, and we have the ridiculous—and alarming—state of affairs that a man who cannot express himself intelligibly in his own language can receive a degree from an institution that used to be known as a seat of learning. "Writing maketh an exact man" is as true now as when Bacon wrote it; lack of the ability to write clearly results in the loose thinking that is so prevalent amongst technologists—and their teachers—to-day. In most Continental countries the schools devote much more time to general education and less to science and technology, with the result that the students are better fitted to take advantage of the technical training offered by the universities and technical high schools.

It is possible that the changes in ideas of the purpose of education and the tremendous increase in the numbers undergoing technical training will prevent any improvement, and that uneducated technologists will in future be more common than they are to-day. Uneducated men now being awarded technical degrees (and even doctorates of philosophy) will be the lecturers and professors of tomorrow. Few of these men will be able to teach more than their own specialised subject, and their uneducated students will in turn be awarded degrees and become professors and lecturers; indeed this is already happening. In the schools the liberal arts are being taught less and less because the teachers know little or nothing of these subjects; recently the National Association of School-masters stated that 29,000 of its members are "untrained", which can mean only that they are unfitted to teach. As time goes on it seems inevitable that the standard of education will become progressively worse.

It does not seem likely that much will be done to implement the plea of the Minister of Education for liberal education in technical colleges. Among the members of the Association of Teachers in Technical Institutions strong opposition to this suggestion has been expressed in illogical statements such as: To assert that students engaged in vocational studies should in addition be compelled to attend non-vocational classes is essentially illiberal, and The chances of passing examinations may be materially reduced by presumptuous and misguided insistence on liberal studies. What could be more misguided than to suggest that education should not be compulsory in the case of a technologist? There is little doubt that such opposition is due to the fact that many of the teachers are as ignorant as their pupils of anything beyond the narrow rut of technicalities. And so we have a system in which instructors in schools and technical institutions cannot teach their pupils how to express themselves in their own language, and the universities accept such young people for technical courses and give them no further education. The result can only be future generations of uneducated technologists except for the few who have the will to educate themselves. It is also desirable that our leaders should set a better example of clear expression. It may be thought to be unfair that technologists should be blamed for using a language that is unintelligible to others when a Junior Minister can assure the House of Commons that he is "fully conscious" when he means that he knows, and a peer can inform the House of Lords that there is "unemployment in the steel industry due to shortfall of offtake".

Design of a Helical Stair Built in 1908.


THE helical stair shown in the illustrations was built for use as an observation platform at the Franco-British Exhibition held at the White City, London, in 1908. The stair was designed by Messrs. L. G. Mouchel & Partners, by whose courtesy we are able to reproduce on the following pages the calculations and some of the drawings. It is seen that the calculations for determining the stresses and for estimating the quantities of concrete and steel are a remarkable contrast to the amount of arithmetic often used to-day to achieve the same result.

Reference is made in the calculations to the English formula for the relation between the load, the stresses, and the dimensions of a helical spring made of material of rectangular cross section. This formula can be written


$$f = \frac{WR\sqrt{b^2 + d^2}}{0.514b^2d^2}$$

in which f is the shearing stress (in kilogrammes per square centimetre), W is the total load (in kilogrammes), R is the mean diameter of the stair (11 ft. = 335 cm.), and b (162 cm.) and d (71 cm.) are the width and overall thickness respectively of the rectangular member. We have been unable to trace the source of this formula, but the results obtained by its use are practically the same as those obtained by applying the corresponding expression given by Professor Unwin and other authors in the early years of this century.

The stair was demolished when the London County Council built houses on part of the exhibition grounds in the 1930's.



DETAIL FROM WORKING DRAWING.
 (See also cross sections on facing page.)




Helical Stair Built in 1908. (See page 3.)


DESIGN OF A HELICAL STAIR BUILT IN 1908.

DETAIL FROM WORKING DRAWING.
(See facing page for positions of cross sections.)


SECTION ON LINE CD



SECTION ON LINE EF



SECTION ON LINE EF



Helical Stair Built in 1908. (See page 3.)


QUANTITIES AND LOADS.

2911	<u>Sprial Staircase</u>
17 January of	
Calc of outside stinger.	
Run diam = 15' 6"	400
Step height = 8 1/2" (inc ground level)	2120
Length $\sqrt{15^{\frac{3}{4}} \times 15^{\frac{3}{4}} + \frac{1}{4}} = 19^{\frac{1}{2}} \text{ (last)} \quad \frac{2144}{2744}$	
Calc = $19^{\frac{1}{2}} \times 8\frac{1}{2} = 125 \text{ ft}$	45
Calc of inside stinger 8' 6 1/2" height 8 1/2"	119
Length $\sqrt{\frac{1}{4} + 8\frac{1}{2} \times 8\frac{1}{2}} = 40.0$	
Calc = $40.0 \times 8\frac{1}{2} = 62.5 \text{ ft}$	
	$125 + 62.5 = 186 \text{ ft.}$
Volume of one step	$11\frac{1}{2}'' \times 4\frac{1}{2}'' \times 8'' = 0.96 \text{ cu ft.}$
Volume of concrete beneath one step	
say $11\frac{1}{2}'' \times 4\frac{1}{2}'' \times 6\frac{1}{2}'' = 2.00 \text{ cu ft}$	8.00
Total volume of concrete of stair	9.00
$125 + 62.5 + 53 \times (0.96 \text{ cu ft}) = 347 \text{ cu ft}$	
Volume of platform at top	
Clearing 7' + 12' 6" = 87' 5"	
Floor $87\frac{5}{8}'' \times 4\frac{1}{2}''$	29 ft
Bear $2\frac{1}{2}'' \times 12\frac{1}{2}''$	24 ft
	$\frac{53}{50} \text{ ft}$
Total volume 347 + 50 = 397	say 400 ft
Dead weight 400 + 70 = 28,000	
Supported by 200 iron 53 steps 10600 lb 160 ft of platform = 4400	$\left. \begin{array}{l} \\ \end{array} \right\} 15,000$
Load at Ground level = <u><u>43,000 lbs.</u></u>	
Parapet not included	

Helical Stair Built in 1908. (See page 3.)

DESIGN.

Taking English formula for spiral spring made of rectangular wire and assuming the section of the "wire" to be $5\frac{1}{4} \times 2\frac{1}{4}$ as per sketch



$$W = \frac{0.514 f}{335} = \frac{0.514 \times 162 \times 71}{335 \times 111} = \frac{26200}{335 \times 111} = 512.40$$

$$f = \frac{26200 + 36200 + 36200}{0.514 \times 36200 + 36200} = \frac{19.5}{6.27} = 3.12 \text{ in. C.G.}$$

Total load on section $3.12 \times 162 \times 71 = 47,000 \text{ lb.}$


$$I = \frac{47000}{162000} = \frac{47000}{162000} \text{ in. }^4$$

Aug 8 to $15\frac{1}{8}$ at top & bottom of each beam

$\frac{47000}{16200} = 43.02 \text{ ft.}$
 $\frac{1}{4}$ of these bars are taken to the top of the

Spiral Average weight for foot including beams of say $2\frac{1}{16}$ or $\frac{1}{4}$ every 6' or 8' 106 lb. per beam

2 horizontal bars in steps $1\frac{1}{8}$ "



Helical Stair Built in 1908. (See page 3.)

FOUNDATION.

SlabLoad on slab at facing stay 43000.

$$\frac{33 \times 30}{250} \text{ Area of slab } 16' 0'' \times 16' 0'' = 256 \frac{2}{3} \text{ ft}^2$$

Average load per ft^2 on ground say 0.2

$$\frac{43000}{256} = 170 \text{ Kips}$$

To be on the safe side let us take 2000.

Flooring 5". $3.75 \text{ ft} \times 6 \text{ ft}$.

Brace. On each $2000'' \times 1.60 = 3200$ per $\text{ft} \times \text{in}$

$$\frac{9 \times 16}{2} \text{ m. } \frac{3200 \times 335}{2} = 17000 \text{ Kips}$$

$$1 \text{ ft} \times 10 \text{ in}$$

Longitudinal beams under stanchions.

18" x 24" $3 \frac{1}{4} \times 40 \text{ Kips}$

Quantities $256 \frac{2}{3} = 28 \frac{1}{3} \text{ cu ft}$

Flooring
beam. $5 \times 16 \cdot 1$
 $\times 10$

$2 \times 16 \times 2$

C	I
105	168
82	400
184	1920
329	<u>2888 $\frac{2}{3}$</u>
$12 \frac{1}{4} \text{ ft} \times 10 \frac{1}{2} \text{ ft per jd}$	$= 225 \text{ ft}^2$

Helical Stair Built in 1908. (See page 3.)

A Helical Stair.

THE stair illustrated below is at a shop in Norwich. The flight is 11 ft. 9 in. high and 9 ft. 3 in. in diameter. The helical slab is $9\frac{1}{2}$ in. thick, and is reinforced with fourteen mild-steel bars of $\frac{1}{2}$ -in. diameter and $\frac{1}{4}$ -in. links at 6-in. centres on the centre-line of the stair. In order to complete the work quickly high-alumina cement was used; seven days after the

concrete was cast the shuttering was removed and the stair was used for light traffic, and full use of the stair was permitted seven days later. The architect of Dolcis, Ltd., Mr. Ellis E. Somake, F.R.I.B.A., was responsible for the work. The stairway was designed by Messrs. Malcolm Glover & Partners and built by Messrs. R. G. Carter, Ltd.



Competition for the Design of an Elevated Motorway.

In the competition arranged by the Prestressed Concrete Development Group for designs for an elevated motorway over an existing road the first prize of £500 has been awarded for the design submitted jointly by Mr. W. F. G. Crozier, Mr. J. D. Bennett, and Mr. C. G. Kerry. The second prize of £200 was awarded for the design submitted jointly by Mr. E. O. Measor and Mr. A. Bailey, O.B.E. Prizes of £100 each were awarded for the designs submitted by Mr. F. Graham, Mr. R. W. Hobbs, and jointly by Dr. Ulrich Finsterwalder and E. Paulus. There were twenty-five entries.

The requirements were that prestressed concrete, either alone or in conjunction with reinforced concrete, be used and that the structure be supported on piers over a strip dividing the two carriageways of the lower road on which traffic would continue during construction and after completion. A design was also required for part of the elevated road to be away from the lower road so as to permit a more economical arrangement for the supports; the area under this part of the road would be used as a car park.

The Assessors' Report

The designs placed first and second are illustrated on the facing page.

The assessors, who acted in a personal capacity, were Mr. H. C. Adams (Ministry of Transport), Mr. C. P. Andren (University College, London), Mr. A. G. Jury (City Architect, Glasgow), Lt.-Col. G. W. Kirkland (Past President, Prestressed Concrete Development Group) and Sir Herbert Manzoni (City Engineer, Birmingham).

The assessors report that there was no outstanding design "which, while being aesthetically good, was also adequate in structural design, in arrangements for traffic flow and in ease of construction. The safety of pedestrians using the lower road has generally been ignored, and little thought has been given to the problem of expansion joints in the wearing surface.


All the designs contain defects in one or more of these aspects. In some cases, however, the defects could be remedied or reduced without fundamental alteration to the main design."

DESIGN PLACED FIRST.—

In commenting on the winning design (Figs. 1 and 1a) the assessors state : This is aesthetically acceptable, structurally good, and provides a reasonable traffic solution for a speed of 50 miles an hour. The transverse members are designed for all possible conditions of loading. The stresses are satisfactory for all the cases considered, but there may be a critical plane about 7 ft. from the end of the cantilever. The central longitudinal beam would be prestressed after the concrete deck had been cast in place. The combined effect is not considered in the calculations, in which it is assumed that the entire prestress is in the central beam. The calculations are thorough and give a satisfactory analysis of the problems related to torsion and concentrated loads. The car-park section of the motorway is in reinforced concrete designed by the load-factor method.

DESIGN PLACED SECOND.—

In their comments on the design awarded the second prize (Fig. 2) the assessors state : The design is structurally sound and provides the best solution of the traffic problem. Its appearance is considered to be poor in that too much consideration appears to have been given to functionalism, the elements are over-elaborated, and the parapets appear to be unpleasantly heavy. The design is structurally simple, comprising prestressed I-beams longitudinally and a topping cast in place. The calculations generally are thorough, but high stresses would occur in some places and the losses of prestressing force allowed for in some of the members with pre-tensioned steel appear to be low. The construction method appears to be simple and satisfactory.



Figs. 1 and 1a.—Design Placed First. By Mr. W. F. G. Crozier, Mr. J. D. Bennett, and Mr. C. G. Kerry.



Fig. 2.—Design Placed Second. By Mr. E. O. Measor and Mr. A. Bailey, O.B.E.

January, 1960.

A Prestressed Tank.

A NEW reservoir (*Fig. 1*) at Whatborough, Leicestershire, for the River Dove Water Board is a cylindrical tank having a capacity of 2,000,000 gallons, and comprises a reinforced concrete base slab 8 in. thick, a prestressed wall of 143 ft. internal diameter, 19 ft. 9 in. high, and 8 in. thick, and a prestressed domical roof 3 in. thick.

The joints at the top and bottom of the wall are shown in *Fig. 2*. It was calculated that a radial contraction of $\frac{1}{2}$ in. would occur when the wall was prestressed. To prevent the wall bending vertically, the joint at the base of the wall is flexible, and comprises two circumferential strips of rubber, each $1\frac{1}{2}$ in. wide and $\frac{1}{2}$ in. thick, separated by a PVC water-bar. The resistance of the rubber strips to horizontal shearing forces is known accurately and is small, so that lateral movement of the base of the wall is practically unrestricted. The joint between the roof and the top of the wall likewise permits movement of the wall.

High-tensile wire of 0.176-in. diameter was used for prestressing. The $2\frac{1}{2}$ tons of wire used for prestressing the beam around the perimeter of the dome was galvanised and was embedded in cement mortar as it was being wound in a recess which was later filled with gunite. About $6\frac{1}{2}$ tons of wire was wound around the wall of the tank which was then filled with water so that the gunite, which was applied in a layer $1\frac{1}{2}$ in. thick, would not be subjected to tensile stresses.




Fig. 2.—Joints at Top and Bottom of Wall.

The engineer of the River Dove Water Board is Mr. H. Wallhouse, and the tank was designed and constructed by Preload, Ltd.



Fig. 1.—The Tank Before Guniting.

The U.S.A. Embassy in London.

THE new building (Fig. 1) for the U.S.A. Embassy in Grosvenor Square, London, is a reinforced concrete structure containing some precast and cast-in-place construction. The main building is rectangular on plan and is 275 ft. by 143 ft., with entrance stairs projecting on the south, east, and north sides. The basement, the lower ground floor, which is at about the level of the pavement, the ground floor, and the first floor cover the whole of this area, and a sub-basement covers part of the area. Above the first floor the building is U-shape in plan and is of four stories. It is separated from the rear rectangular part by a joint $\frac{1}{4}$ in. wide which is provided in case of settlement and extends into the foundations.

The foundations are mainly strip footings of plain concrete extended 3 ft. into clay, with reinforced concrete distributing beams which are formed either separately or by thickening the floor of the sub-basement. All the columns were cast in place. The floors of the sub-basement and basement are mainly of reinforced concrete 9 in. thick. Around the periphery of the rectangle there is a 9-in. retaining wall coated on the outside with asphalt which is protected by $\frac{4}{4}$ -in. brickwork. The wall extends to the lower ground floor, where it is thickened to form the base for cruciform columns which extend to the first floor. At the ground floor, the beams which carry the ground floor span between the columns.




Fig. 2.—Construction of Walls above First Floor.

Above the first floor the construction consists basically of three reinforced concrete towers which extend from the foundations and are connected with one another by a cast-in-place beam-and-column "spine" construction which supports the upper floors. The central tower contains two lift shafts with 5-in. reinforced concrete walls cast in place. The




Fig. 1.



Fig. 3.—Cantilevered Diagonal Beams at First Floor Level.

other towers are constructed similarly but contain stairs, lavatories, and services.

The reinforced concrete columns in the lower part of the structure are mainly at 11 ft. centres and, with the reinforced concrete towers, support the diagonally-intersecting reinforced concrete beams of the first floor (*Fig. 3*). The beams, which are at 7 ft. 9 $\frac{1}{2}$ in. centres in both directions, were cast in permanent shuttering formed of precast concrete (*Fig. 4*). The shutters are 2 ft. 2 in. deep and 11 in. wide; the sides taper from 1 $\frac{1}{2}$ in. thick at the bottom to 1 in. thick at the top. There are castellations in the bottom of the shutter. The reinforced floor slab

cast in place over the beams is generally 4 in. thick. For about half the area of this floor, a space of 1 ft. is provided between the top of the beams and the underside of the slab to accommodate services. For this area 2-in. precast slabs were used as permanent shuttering on which was cast a 2-in. topping. These shutter slabs were cast on the site and placed in position after the services had




Fig. 4.—Diagonal Beams and First Floor Slab.




Fig. 5.—Details of Wall Frames.

been installed. Where ducts were not required a precast member having the shape of an inverted U was used instead of the flat slabs.

The diagonal beams cantilever about 5 ft. from the face of the columns (*Fig. 2*) and carry at their ends the precast concrete wall frames, which support the loads from the upper floors and are provided around the entire periphery of the building. The wall frames are rectangular and




Fig. 6.—Part Elevation.

1—January, 1960.



Fig. 7.—Temporary Struts for Wall Frames.

each comprises two 8½-in. by 7-in. columns of one-story height connected at the top and bottom by a lintel and a sill respectively (*Fig. 5*). The frames are at 11 ft. centres which results in the columns being at 5 ft. 6 in. centres. The frames in any story are staggered in respect to the frames in the stories immediately above and below (*Fig. 6*). Two threaded mild-steel bars project from the bottom of each column in such a position that they fit into holes in a plate on the frame below. Nuts and washers are fitted above and below the plate and, after adjustment, the connection is completed by filling the remaining space with concrete. At the top of each column, on the inner face, there is a nib which supports the floor beam and projects sideways to support the lintel. A member similar to the lintel forms the sill and is bolted to the back of the frame. The temporary strutting used for aligning the wall frames is shown in *Fig. 7*.

The upper floors comprise I-beams at 5 ft. 6 in. centres. Prestressed precast concrete planks 4 in. thick form the bottom flanges of the beams (*Figs. 8* and *9*). Castellations are formed on the top of the planks to form a key for the upper




Fig. 8.—Details of Upper Floor up to 1 ft. 3 in. Thick.

part of the beam, which is cast in place. The top flange of the beam is formed by the floor slab, which consists of a reinforced concrete topping generally $1\frac{1}{2}$ in. thick laid on inverted precast concrete troughs serving as permanent shuttering. In the north-east and south-east corners, where there are junctions of beams at right-angles to each other, there are Y-beams each of which consists of a straight precast beam and a cranked beam forming the two arms. The straight part of the Y-shaped beams is prestressed. The tops of the beams are castellated to bond with a 4-in. concrete topping cast in place. The overall depth of beam and slab is $17\frac{1}{2}$ in.

At the rear of the area between the two wings of the U-shape building there is a roof, at the level of the first floor, which is supported by prestressed concrete beams




Fig. 9.—Details of Upper Floor of 1 ft. 7 1/2 in. and Greater Thickness.

at 11 ft. centres spanning 55 ft. The wires in the beams were post-tensioned. The beams were cast monolithically with the roof slab and there are four large holes through each for services. The slab was cast on inverted precast troughs between the beams; the beams are so designed that a four-story extension can be erected upon them at a later date.

The architects are Messrs. Eero Saarinen & Associates in association with Messrs. Yorke, Rosenberg, and Mardall. The consulting engineers are Messrs. Felix J. Samuely & Partners. The general contractors are Messrs. Pauling & Co., Ltd., the sub-contractors for the structural concrete are Messrs. Wates, Ltd., the precast members were made by the Modular Concrete Co., Ltd., and the prestressed planks by Messrs. Cawood Wharton & Co., Ltd.

Impurities in Sand.

THE result of an investigation, made at the Finnish State Institute of Technical Research by T. Karttunen and T. Sneck, on the effect of humus in sand on the strength of concrete is given in "Inverkan av Humushaltig Sand på Betongens Hållfasthet". It is concluded that the usual colorimetric test for the cleanliness of sand is unsatisfactory because it does

not indicate the chemical properties of impurities. Some sands that produced a dark colour in sodium hydroxide were found to be harmless whereas some sands that did not change the colour of sodium hydroxide would be harmful if used in concrete. It is suggested that inorganic salts in humus may act as accelerators in the presence of alkali.

A College at Manchester.

THE construction of the new Domestic and Trades College at Fallowfield, Manchester, is almost complete (*Fig. 1*). A photograph of a model of the buildings was given in this journal for January 1959.

The college comprises five buildings. The two-story catering and administration building is the shape of a U on plan. The areas within the sides of this building are for use as car parks, above part of which is an assembly hall with a domed roof and supported at the centre by a column with a flared head. Across the open end of the U is the six-story teaching building, beyond which is a gymnasium and a tailoring building.

The ground consists of 1 ft. of made-up ground and top soil below which is a stratum 20 ft. thick of stiff boulder clay overlying bunter sandstone. Tests of samples obtained from boreholes indicated that the foundations of the buildings should be on the boulder clay and that the net pressure applied should not exceed 2·4 tons per square foot. Generally, the underside of the foundations are at a depth of 4 ft., but in the case of the teaching building the depth is 5 ft. Any ex-

cavation to remove weak ground below these depths was filled with plain concrete. Each building is constructed as a separate structure, and at points of interconnection provision is made for possible differential settlement, which is calculated to be about 1 in. between the teaching building and the catering building, and 1½ in. between the Assembly hall and the catering building.

The buildings are of reinforced concrete cast in place; the crushing strengths of the concrete at 28 days is not less than 3300 lb. per square inch for the foundations and 4500 lb. per square inch for the superstructures. The maximum and minimum limits of the cement content were also specified. Owing to the restricted site, ready-mixed concrete was used throughout. The arrangements for the distribution of concrete to the various parts of the works were such that it could be placed in the shuttering within about 45 minutes after mixing. The decision to use high-grade concrete was governed by the desire to reduce the sizes of the members as much as possible and, since much of the concrete is exposed, there was the added advantage of having concrete of good




Fig. 1.—View during Construction.

quality for appearance and resistance to the weather.

Multiple-story Building.

The overall height of the six-story building, on the roof of which there is a garden, is 120 ft. and the length is 221 ft. The building is shown in course of construction in *Fig. 2*, and a cross section is given in *Fig. 3*. The width between the inner faces of the inclined columns of the arched frames, which are exposed as a main architectural feature of the building, tapers from 69 ft. at the ground floor to 46 ft. 8 in. at the third floor and 28 ft. at the sixth floor. There are two lifts to the fifth floor and two stairs at each end of the roof garden. The inclined columns are 3 ft. by 1 ft. 3 in. in cross section and are at 10 ft. centres. An intermediate row of columns is provided up to the third floor, above which all the stories are free of internal structural columns. The foundations

of the external and internal columns are continuous strip footings bearing on the boulder clay. The outward thrust of the inclined columns is resisted by transverse reinforced concrete ties which are provided at 20 ft. and 30 ft. centres, the strip footings acting as horizontal beams spanning between the ties. The walls between the inclined columns are faced with red clay tiles.

The floors are of beam-and-slab construction. The first floor, on which are the bakeries, has a 6-in. reinforced concrete slab designed to carry a general imposed load of 168 lb. per square foot, but in the bakeries the design load is 336 lb. per square foot to allow for heavy equipment being installed in any position. The second to fifth floors have 4-in. slabs, and are designed for an imposed load of 60 lb. per square foot. The sixth and seventh floors have 6-in. slabs and are designed for an imposed load of 100 lb.




Fig. 2.—Tall Building during Construction.

per square foot. Architectural requirements limit the overall thickness of the floors to 2 ft. The total depth of the beams and slab is 1 ft. 10 in. There is 1½-in. finish on the floors and a ceiling suspended below the beams. Pipes for services are contained in the cavity between the ceiling and the underside of the slab. The beams and slabs were cast in one operation.

Assembly Hall.

The assembly hall, a cross section of which is shown in *Fig. 4*, is circular in plan. The first floor has a diameter of 80 ft. and is supported around half of its circumference on projections on the columns of the catering and administrative building, on three separate columns under the other half, and on a circular central column. The diameter of the central column is 3 ft. 6 in. at ground level, and increases to 5 ft. 2 in. at a height of 9 ft. 6 in., above which it flares out and merges into the slab of the first floor. The slab is designed as a circular plate. Depending on the relative settlement of the central column, which is carried on a separate foundation, the top of the slab may be in either tension or compression.

The roof over the hall is a stressed-skin aluminium dome of 72 ft. 6 in. diameter, supported on a reinforced concrete ring-beam with which a drain channel is combined. The ring-beam is supported on fourteen reinforced concrete columns which are 9 in. square and are supported on the floor slab.

Two tower cranes were provided by means of which all parts of the site could be reached. One crane was erected




Fig. 3.—Cross Section of Tall Building.

within the U of the catering and administrative building, and the other at the side of the teaching building near the tailoring building. The cranes travelled on rail-tracks, so that skips of concrete, shuttering, reinforcement, and other materials could be placed where required.

The architect is Mr. C. Howitt, City Architect of Manchester. The consulting civil engineers are Messrs. L. G. Mouchel & Partners. The main contractors are Messrs. J. Gerrard & Sons, Ltd.




Fig. 4.—Cross Section through Assembly Hall.

Precast Arches for a Church.

THE church of Our Lady of the Visitation, at Greenford, Middlesex, is rectangular on plan and is 117 ft. long and 70 ft. wide. The transverse frames (*Figs. 1 and 2*) comprise twelve three-hinge parabolic arches at 8 ft. centres. The span between the springings is 74 ft. and the height from the springing to the crown is 48 ft. Each arch is precast as two ribs, each about 60 ft. long and weighing 6 tons. The breadth of each rib is 9 in. and the thickness 2 ft. 6 in. at the springing and 1 ft. 6 in. at the crown. The concrete

dovetail slot is formed in the curved ends of the ribs. A 1½-in. mild-steel dowel 1 ft. long was placed in the slot after a pair of ribs was erected. In one rib 1 : 1 : 3 concrete was packed around the dowel and consolidated by ramming. The other end of the dowel enters a conduit embedded in the slot in the end of the adjacent rib, and therefore the joint is free to act as a hinge.

The ribs are shown in course of erection in *Fig. 1*. The arches are stabilised permanently by means of precast trough-shape




Fig. 1.—Erecting the Arches.

had a crushing strength of at least 6000 lb. per square inch at six days.

The foundations (*Fig. 3*) of the arches are concrete blocks 11 ft. 6 in. long, 4 ft. wide, and not less than 4 ft. deep. The blocks are connected by longitudinal beams which support the exterior 18-in. brick walls. A steel dowel embedded in and projecting from the lower end of each rib enters a conduit in a recess which was grouted under pressure after the ribs had been erected. The joint was then sealed by filling it with a bituminous compound.

At the crown (*Fig. 2*) of each arch a

members (*Fig. 2*), which were bolted between the arches as they were erected and which later formed permanent shuttering for a beam cast in place under the clerestory windows, the frames of which are of precast concrete. The first arch to be erected was maintained temporarily in position by guy-ropes and was used to stabilise succeeding arches. Additional temporary stability was provided by scaffolding.

The beam under the clerestory window along each side of the building is continuous and was cast around reinforcement projecting from the trough members.




Fig. 2.—Part Cross Section.




Fig. 3.—Hinge at Base.

Precast planks 6 in. thick spanning between this beam and the brick walls form the roofs at the sides of the building. The covering of the main roof (Fig. 2) is of precast planks carried on the 5-in. beams supported on 6-in. by 4-in. posts, which were cast in place with their lower ends in pockets in the ribs.

The north wall over the entrance and the walls at the end of the transept are of cast-stone blocks U-shape in cross section, 1 ft. 1 $\frac{1}{2}$ in. thick, 1 ft. 6 in. wide and 3 ft. long (Fig. 4). The blocks are connected by dowels and are staggered vertically to form mullions between the glazing. The blocks are set in a reinforced concrete frame to which wind pressure on the wall is transmitted.

The architects are Messrs. David Stokes & Partners. The consulting engineers are Consideré Constructions, Ltd., and the main contractors are Messrs. E. H. Burgess (London), Ltd. The precast concrete members were made and erected by Girling's Ferro-Concrete Co., Ltd.




Fig. 4.—Details of Wall Blocks.

Water Tower of 150,000 Gallons Capacity.

THE construction of a water tower (Fig. 1) of 150,000 gallons capacity was completed in 1958 at a fertiliser factory for Messrs. Fisons, Limited, at Mucking, near Stanford-le-Hope, Essex. A requirement was that the bottom of the tank should be 70 ft. above the ground. Four preliminary designs (Fig. 2) were considered from the points of view of aesthetics and cost. The relative estimated cost of structures of the four designs were (a) 1·00, (b) 1·06, (c) 1·21, and (d) 1·32. Although design (c) might be the most striking in appearance it was thought that the additional cost was not justified, and design (b) was accepted as being economical and aesthetically satisfactory.

The structure comprises a cylindrical covered tank of 46 ft. internal diameter and 19 ft. deep supported on six columns equally spaced around the periphery of the tank and a central hollow column of 8 ft. diameter. The radial beams under the floor were cast monolithically with the outer columns and extend from the outer columns to the central column, where they are 3 ft. 6 in. deep. The height from the ground to the underside of the floor of the tank is 69 ft., and the depth of water 16 ft. A reinforced concrete helical stair is provided within the hollow column by means of steps cantilevering from the wall; within the column are also the inlet, outlet, overflow, and rainwater pipes.

Foundations.

When the site was levelled the exposed ground was stiff brown clay to a depth of




Fig. 1.




Fig. 2.—Preliminary Designs.

8 ft. 9 in. overlying stiff blue clay. Triaxial compression tests on samples of the undrained brown clay indicated an average shearing strength of 2560 lb. per square foot, and a reasonable bearing pressure was considered to be 2½ tons per square foot. With this pressure, consolidation tests indicated probable settlements as follows. Under the central column: initial settlement during construction, ½ in.; total settlement after forty years, 1½ in. Under the outer columns: initially, ½ in.; after forty years, 1¼ in. In view of the magnitude of these




Fig. 3.




Fig. 4.

settlements the design pressure on the ground was reduced to be nominally 1½ tons per square foot.

Separate bases are provided under each outer column. Under static load the pressure on the ground does not exceed 1·5 tons per square foot under the outer column bases and 1·25 tons per square foot under the base of the central column. Due to the effects of wind the calculated pressures are 1·6 tons and 1·5 tons per square foot respectively.

The actual settlement on completion of the structure and with the tank full were as follows: ½ in. under the west and southwest outer columns, ¾ in. under the north-west outer column, ½ in. under the north-east outer column, no settlement under east and south-east outer columns, and ¼ in. under the central column.

The base of each outer column is 14 ft. square and 3 ft. 6 in. deep and is reinforced with 1½-in. mild steel bars. The foundation of the central column is 27 ft. in diameter, and varies from 5 ft. deep at the base of the column to 2 ft. deep at the perimeter. It is designed as a circular plate subjected to a central concentrated load and a bending moment.

The SO₄-content of the soil is 0·02 per cent. and of the ground-water 39 parts per 100,000. Sulphate-resistant cement was therefore used for all concrete below ground.

Superstructure.

The proportions of the concrete in the columns and tank are 1 : 2 : 4 complying with B.S. Code No. 114. The reinforcement comprises mild steel bars, the




Fig. 5.—Reinforcement for Beam at Base of Tank Wall.

maximum tensile stress in which is 20,000 lb. per square inch. The tank is lined with asphalt $\frac{1}{2}$ in. thick on the wall and $1\frac{1}{2}$ in. thick on the bottom. The structure is designed to resist the wind pressures recommended in B.S. Code No. 4, Chapter V. The effects of wind are divided between the central column and any two outer columns in proportion to the stiffnesses of these members.

The six outer columns are 27 in. wide ; in the other direction they taper from 7 ft. at the top to 3 ft. 6 in. at the base. The internal diameter of the central column is 8 ft. and the thickness of the wall is 9 in. For design purposes each outer column and beam are assumed to be pinned at the central column and fixed at the base. The main reinforcement in each of the outer columns, which are shown in course of construction in Fig. 4, comprises sixteen $1\frac{1}{2}$ -in. bars with $\frac{1}{2}$ -in. triple binders. The continuation of each column vertically outside the tank is an architectural feature having no structural purpose and is separated from the wall by $\frac{1}{2}$ -in. fibre-board to allow for expansion.

The floor of the tank is designed as a series of triangular panels of 15-in. average thickness, supported by the outer columns and by a peripheral beam, at the base of the wall, which is also supported on the outer columns. The principal reinforce-

ment in the slab comprises $\frac{1}{2}$ -in. bars at 9 in. centres in each of three directions. The peripheral beam, the reinforcement in which is shown in Fig. 5, is designed to resist torsion in addition to ordinary design requirements, because it is segmental in plan and the centroid of the loading is not on the centre-line between the supports of the beam.

The wall of the tank is 8 in. thick and is reinforced to resist circumferential tension. Pipes passing through the wall of the tank are provided with puddle flanges embedded in a thickened part of the wall. A lead collar 6 in. greater in diameter than the pipe is sweated to the pipe and dressed against the first coat of asphalt on the inner face of the wall. The second coat covers the collar and is combined with a 2-in. fillet of asphalt and an asphalt sleeve 6 in. long surrounding the pipe. The flat roof is 8 in. thick and is designed to span radially from the central column to the wall.

The structure contains 774 cu. yd. of concrete and 65 tons of reinforcement, the ratio being 190 lb. of reinforcement per cubic yard of concrete. The structure was constructed in about seven months and cost about £25,000. The consulting engineers were Messrs. Brian Colquhoun & Partners, and the contractors were Messrs. Tileman & Co., Ltd.

A Hyperbolic-Paraboloidal Roof.

A GARAGE in Lincoln is 96 ft. by 106 ft. 9 in. on plan, and has a roof composed of two pairs of hyperbolic-paraboloidal slabs (*Fig. 1*). Each pair is separated by a strip 9 ft. 9 in. wide containing glazing and ventilators. The slabs are arranged so that their highest points are at the four corners of the building and on the centre-line parallel with the longer side.

Each hyperbolic paraboloid is 47 ft. 6 in. square on plan and is generally $2\frac{1}{2}$ in. thick increasing to 9 in. at the edges (*Fig. 2*). The external edges are stiffened by upstanding beams 1 ft. wide and 1 ft. 6 in. deep. The internal edges are

ties were precast in lengths of 60 ft. 6 in. and each contains sixty 0·276-in. wires and twelve deformed bars of high-tensile steel 1 in. in diameter. The wires and bars protruded 3 ft. at both ends to be embedded in the concrete of the roof.

Tubular scaffolding and timber shuttering were used for each pair of slabs; one slab was cast at a time and required two days for casting. On completion of the first pair of slabs the scaffolding and form-work were re-erected for the second pair. The two highest points are at the middle of the roof and these were supported on a steel tower until the structure was complete. The cost of the structure,



Fig. 1.

supported on three upstanding beams each 1 ft. wide and 2 ft. 6 in. deep, one on each side of the glazing and spanning 95 ft. and one intersecting them at right angles and spanning 105 ft. 9 in. The shorter beams are supported by V-shaped reinforced columns and the longer beams by rectangular columns 2 ft. by 1 ft. in cross section. Tubular steel columns 6½ in. in diameter are provided at the four corners of the building to prevent vertical movement.

The horizontal thrusts exerted by the slabs are each about 100 tons and act diagonally, and are resisted by four precast prestressed ties 10 in. wide and 1 ft. 6 in. deep; these are 15 ft. above ground-floor level and span 67 ft. The


excluding the foundation, was £7 10s. per square yard of area covered.

The architects are Messrs. Dennis Clarke Hall, Sam Scorer and Roy Bright, the consulting engineer is Dr. K. Hajnal-Kónyi, and the main contractors were Messrs. Gee, Walker & Slater, Ltd. The prestressed tie-beams were made by Messrs. Cawood Wharton Co., Ltd.

"CONCRETE SERIES"
BOOKS ON CONCRETE

For a complete catalogue giving prices in
sterling and dollars, send a postcard to :
CONCRETE PUBLICATIONS, Ltd.
14 Dartmouth St., London, S.W.1

A HYPERBOLIC-PARABOLOIDAL ROOF.



SECTION A.A.
Fig. 2.—Details of Roof.

New Lighthouse at Dungeness.

THE illustration, which is reproduced from a painting by Mr. A. H. Walker, is of the new lighthouse being built at Dungeness on the Kent coast. It is the first major lighthouse to be erected by Trinity House for more than fifty years and will be the first of its kind in the country, since it will be fully automatic and will embody new ideas resulting from investigations made by Trinity House in co-operation with the architects and engineers, Messrs. Ronald Ward & Partners.

The tower, which will be 130 ft. high, will be on a base of white-cement concrete forming a spiral ramp which will enclose the machines and the control-room. The overall diameter of the tower will be 12 ft. and the wall will be 6 in. thick. The tower will comprise a number of superimposed concrete rings each 5 ft. high, and will be prestressed with high-tensile steel wires extending throughout its height. The bands of black and white will be in black and white cement with suitable aggregates, so that painting will not be necessary. In the topmost white band there are sixty holes for the loud-speakers which form the fog-signalling device, which will sound automatically when a fog warning is given by the fog-detector at the top of the ramp. The light for the main beam will be provided by a lamp which will be little larger than a domestic lighting bulb but will exceed 600,000 candle-power. The contractors are Taylor-Woodrow Construction Co., Ltd.



"Concrete and Constructional Engineering" Prize Design.

THE prize of £25 awarded each year by this journal for competition amongst the students attending the post-graduate course of concrete technology at the Department of Civil Engineering of the Imperial College of Science and Technology, University of London, has been awarded for the session 1959 to Mr. I. H. Reith. The competition was for designs for a port at Pimlico on the River Thames in accordance with conditions set by

Professor A. L. L. Baker, the Professor of Concrete Technology.

The assessor was Mr. Leslie Turner, M.I.C.E., P.P.I.Struct.E., who in his report states : More than half of the forty entries were of such a high standard that the task of adjudication was difficult, and many of the drawings were exceptionally neat. Mr. Reith's design was for a jetty and warehouse, and was awarded the prize because it was consistently excellent in all respects.

Precast Construction in Multiple-Story Buildings.

THE construction of the multiple-story buildings at the College of Technology at Derby (*Fig. 1*) and the Civic College at Ipswich (*Fig. 2*) is alike in that the external walls have precast frames, lattice girders are provided to support the first floor and the structure above, and the floors are mainly of precast members.

The building at Derby has a main part 115 ft. high, 123 ft. long, and 70 ft. wide, in which there are a ground floor, eight stories of classrooms, and a penthouse. The central part of this structure is 62 ft. by 17 ft. in plan and is of reinforced

columns cast in place in the middle of each building.

Floors.

The average span of the floors is 26 ft.; they are 1 ft. thick and are constructed with prestressed precast inverted tee-beams and a 2-in. concrete topping which was cast on corrugated asbestos-cement sheets which serve as permanent shuttering. The beams are at 2 ft. centres at Ipswich, and 3 ft. 1 in. at Derby where the imposed load is smaller and the beams span between the external wall-frames and




Fig. 1.—College at Derby.

concrete beam-and-slab construction cast in place; it contains the stairs, which are precast, the lifts, and the chimney from the heating chamber. The reinforced concrete frame of this part resists the wind forces.

The two teaching buildings at Ipswich are each 117 ft. high and have floor areas of 63,000 sq. ft. and 27,000 sq. ft. respectively, and are connected by a structure containing the stairs and lifts. Wind is resisted by the floors acting as beams which transmit the forces transversely to concrete walls cast in place at the ends of the buildings, and longitudinally to

the central core or to the three-span main frames provided to resist the wind.

Precast Wall Frames.

Each wall-frame is one story high and comprises two vertical members and a lintel cast in one piece. Precast sills are fixed by bolts to the frames after erection. The lintels project lengthwise beyond the vertical members. At Ipswich the projecting ends of adjacent frames abut (*Fig. 4*). At Derby (*Fig. 5*) there is a gap between the ends which is closed, after erection of the frame, by a precast piece.

Steel tubes bolted to each vertical member and to the floor are provided as temporary inclined struts (*Fig. 4*) to keep the frames in position during erection; the lengths of the struts are adjusted by turnbuckles. Halved joints are provided in the vertical members at Ipswich, where the bases of the vertical members of the frames immediately above the first floor are bolted to the floor. A similar connection (*Fig. 3*) is provided at each floor at Derby, where the frames are 12 ft. high, and the vertical members are 1 ft. 3 in. by 7 in. and are rebated and splayed. The lintel is 10 ft. 10 in. long including two cantilevers each about 2 ft. 3 in. long and the overall size is 1 ft. by 1 ft. The lintel is ell-shape in order to provide supports for the floor beams. The sills are 4 in. deep by 9 in. wide and are provided between all vertical members; at Ipswich sills are provided in alternate bays only.

Lattice Girders.

Lattice girders and V-shape columns of reinforced concrete are provided as the main supports along some of the edges of the first floor in all the buildings (*Figs. 1, 2, 5, and 6*).

The girders along the front of the



Fig. 3.—Connection at Bottom of Wall Frame.




Fig. 2.—College at Ipswich.

building at Derby were precast in two parts each 31 ft. long, 4 ft. 10 in. deep, and 1 ft. 10 in. wide overall and each weighs about 8 tons. The bottom boom is horizontal and the top boom is notched to provide a support for the first-floor beams. Bars projected outwards from the top boom to connect to the gutter, which was cast in place. The girders were supported on staging during erection, and the connection between the two parts, the connections at the ends, and the connections to the inclined members forming the V-shaped columns, which were cast in place, were made by placing concrete around bars projecting from the members, so that a monolithic frame is formed. The lattice girders at the end walls were also precast but are shorter; therefore the inclined members of the V-shaped columns were cast monolithically with the girder to form a precast



Fig. 4.—Precast Wall Frames.

K—January, 1960.




Fig. 5.—Wall Frames.

unit 18 ft. 6 in. by 18 ft. 6 in. overall and weighing about 4 tons.

The bottom booms of the precast lattice girders along one face of the larger of the teaching buildings at Ipswich college are not horizontal (Fig. 6) and contain ducts to receive prestressing wires. The V-shaped columns are generally at 20 ft. centres but are at 30 ft. centres at the main entrance, and were precast. The columns and lattice girders were erected and propped in position and the joints between the precast parts were grouted. When the grout had hardened, 0·276-in. wires in the bottom boom were tensioned to prestress the girders.

Assembly Hall.

The assembly hall to be erected at the Ipswich site will have a floor area of 3000 sq. ft. The roof of the tower over the stage will be of column-and-beam construction cast in place, but the roof over the auditorium will comprise 2½-in. reinforced concrete slabs cast in place to form a series of inverted vees, the distance between the apexes of which will be 10 ft. and the height 3 ft. The roof will rise 11 ft. from the eaves to the ridge, and will be supported by precast trifurcated columns.

The consulting engineers for the two colleges are Messrs. Felix J. Samuely & Partners. The architects for the Ipswich college are Messrs. Johns, Slater & Howard, the general contractors are Messrs. J. Gerrard & Sons, Ltd., the prestressed floor and roof units and the precast members of the roof of the




Fig. 6.—Columns and Lattice Girders.

assembly hall are supplied by Messrs. Saunders (Ipswich), Ltd., and the precast units for the main teaching buildings are supplied by Messrs. Cawood Wharton & Co., Ltd. The architects for the Derby

college are Messrs. Grenfell Baines & Hargreaves, the general contractors are Messrs. Gee, Walker & Slater, Ltd., and the contractors for the precast concrete work are F.C. Construction Co., Ltd.

Walls Acting as Beams.

THE details on page 33 are of the walls of the secondary modern school now in course of construction at Richmond, Yorkshire. The two-story building is about 300 ft. long and 75 ft. wide. Transverse reinforced concrete walls, which are at 25 ft. centres between the classrooms on the first floor, act as beams supporting the first floor and spanning 52 ft. 6 in. between columns 2 ft. 6 in. by 1 ft. and cantilevering about 10 ft. at each end. A large unobstructed area for the dining hall, assembly hall, and gymnasium is thereby provided on the ground floor.

The walls are about 10 ft. high and are designed to resist the lateral bending moments caused by the unbalanced loading on either side, tensile forces due to the suspension of the first floor, and as beams supporting the first floor and roof.

Doorways are provided through the walls, and a strip of glazing 20 ft. wide is provided along the middle of the roof. The greater depth of the wall at the glazed part of the roof compensates partly for the absence of the roof slab in this position and which would form part of the compression flange of the wall beam.

The walls were cast in lifts of 4 ft. for the entire length of 75 ft., and support

the reinforced concrete roof and the first floor which is monolithic with, and suspended from, the walls. The first floor comprises prestressed precast beams 5 in. wide and 7 in. deep at 2 ft. 3 in. centres. The beams support wood-wool slabs 2 ft. square and 2 in. thick on which 2½ in. of concrete is cast in place. Each precast beam and the topping forms a tee-beam which is continuous over five bays. The beams at the edges of the floors are 1 ft. deep and about 2 ft. wide, and have a projecting nib. They were cast in place and support the glazing of the external walls, and provide a trimming to the ceiling-board which is nailed to timber fillets built in the underside of the ribs of the prestressed beams. Double walls are provided at the transverse expansion joints, which are 125 ft. apart.

Since the concrete of the transverse walls is exposed, horizontal vee-shape recesses are provided along the line of the construction joints and form a decorative feature in alignment with the heads of doors and black-boards.

The architect is Mr. D. Clarke Hall, the consulting engineer is Dr. K. Hajnal-Konyi, and the contractors are Messrs. F. Shepherd & Son, Ltd.

WALLS ACTING AS BEAMS.




FIG. 1.—Details of a Typical Wall Acting as a Beam.
(See facing page.)

January, 1960.

A Combined Chimney and Water Tank.

In Fig. 1 is shown a combined chimney and water tank at Aldridge, Staffordshire, and Figs. 2 to 4 give details of a similar structure recently built at a school at Stafford.

The top of the chimney is about 70 ft. above the base and the internal diameter of the reinforced concrete shaft is 3 ft. and the thickness of the wall 8 in. The shaft is lined throughout with acid-resistant brickwork $4\frac{1}{2}$ in. thick. The uppermost 3 ft. of the shaft is constructed

in concrete made with sulphate-resistant cement. The shaft projects 6 ft. 8 in.



Fig. 1.




Fig. 2.—Cross Section.

January, 1960.

A COMBINED CHIMNEY AND WATER TANK.

above the cylindrical water tank, the bottom of which is about 55 ft. above the base of the chimney. The internal diameter of the tank is 15 ft. 10 in. and its capacity is 6500 gall. Because the wall is only 5 in. thick, the tank is lined with asphalt. The outside of the tank is faced with timber.

The foundation of the chimney is a slab 1 ft. 9 in. thick and 15 ft. square, reinforced with $\frac{1}{4}$ -in. twisted square bars at 6 in. centres in two directions.

The County Architect for Staffordshire is Mr. A. C. H. Stillman. The design was prepared by the British Reinforced Concrete Engineering Co., Ltd., who also supplied the reinforcement. The contractors for the structure described were Tideswell Brothers, Ltd.




Fig. 4.—Sectional Plan of Chimney.





Fig. 3.—Sectional Plan of Chimney and Tank.

North-light Roof for a Factory.



THE north-light roof illustrated is at the factory at Redditch of Messrs. Herbert Terry & Sons, Ltd. It covers 57,600 sq. ft. and comprises twenty-four units of "shell" construction, each unit being 26 ft. 6 in. wide and 90 ft. long including a 20-ft. cantilever. The units are in groups of three and are carried on beams prestressed with post-tensioned cables by the P.S.C. method, each cable containing twelve 0.276-in. wires. Intermediate

columns are provided at the junctions of the units only. The longitudinal valley beams accommodate the ducts from the air-conditioning plant, and all the beams are designed to enable heavy factory equipment to be suspended from them.

The architects are Messrs. Francis W. B. Yorke, Harper & Harvey. The design and construction of the reinforced concrete were by Truscon, Ltd.

Bridge with a Span of 500 ft.

TENDERS have been invited by the Ministry of Transport for the construction of a bridge to carry motorway M2 over the River Medway near Rochester. The deck will provide two carriageways, cycle tracks, and footpaths, and will be at a height of about 116 ft. above the river. There will be a central span of 500 ft. and side spans of 313 ft. each over the river and seventeen spans of from 100 ft. to 135 ft. in the viaducts forming the approaches.

For the main bridge, tenders may be submitted for two designs in steel and one in prestressed concrete. The concrete design comprises hollow reinforced concrete piers supporting longitudinal prestressed hollow girders over each side span and cantilevering 200 ft. over the

central span; suspended girders 100 ft. long are to be supported on the ends of the cantilevers. The designs in steel comprise two hollow girders supporting a steel deck.

The piers of the viaducts are to be reinforced concrete frames supporting prestressed precast beams and a slab cast in place. The beams are designed as freely supported members carrying the dead load but acting as continuous members in conjunction with the slab to carry the live load.

The piers of the main bridge will be founded on hard chalk. The piers of the viaducts will be supported on piles or footings.

The consulting engineers are Messrs. Freeman, Fox & Partners.

Jetties for Oil Tankers on the Thames.

PRECAST BEAMS.

Two new jetties and adjacent dolphins (Fig. 1) recently completed at Thames Haven for London & Thames Haven Oil Wharves, Ltd., have a dredged depth of 45 ft. and can accommodate oil-tankers of 80,000 tons dead-weight. The positions of the jetties are such that advantage is taken of the velocity and direction of the currents at various depths at all stages of the tide without interfering with the use of two adjacent older jetties.

Jetties.

The jetties are constructed of precast reinforced concrete in bays each 30 ft.

Twelve piles are parallel to the axis of the jetty at a slope of 1 in $2\frac{1}{2}$, twenty-four piles are at right-angles to the axis at a slope of 1 in $2\frac{1}{2}$, and twenty-four similarly at a slope of 1 in 3. The lateral raking piles, which are at the ends of the structure, are 115 ft. long and support loads up to 95 tons. The average length of the vertical piles is 105 ft. and each pile supports a load of 80 tons. After welding, the piles were sand-blasted, primed, and painted with two coats of bituminous enamel. When the piles had been driven they were filled with concrete after removing any water in them.




Fig. 1.

long, supported on piled trestles. The concrete deck was cast in place. The hollow square piles are of steel, on which reinforced concrete cross beams were cast and carry precast longitudinal reinforced concrete beams. The lengths of the jetties are 474 ft. and 774 ft.

The jetty-heads are structurally identical (Fig. 2), and comprise two reinforced concrete slabs, generally 3 ft. thick, supported on eighty vertical and sixty raking steel hollow square piles. The upper deck is about 7 ft. above mean high water at spring tides, and the lower deck is 8 ft. above mean low water at spring tides.

The soffit of the lower deck is 2 ft. 4 in. and 5 ft. above mean low water at neap and spring tides respectively, and the time available for erecting and removing the shuttering, even in calm weather, was therefore short. The upper deck was constructed first. The shuttering was supported on 1-ft. 6-in. by 7-in. steel joists spanning across the entire width of the jetty-head. The ends of the joists were supported on longitudinal joists, which were suspended from the outer vertical piles by high-tensile steel rods. When the concrete in the upper deck had hardened the pile bracing was removed, the soffit

shutters were lowered a convenient distance, and the shuttering was altered to suit the lower deck. The shuttering was then lowered at low tide to the level required for the lower deck and secured to the vertical piles to resist the action of the waves. When the lower deck had been cast the shutter was again lowered and the joists were pulled out transversely by a crane on a barge. The amount of concrete in each placing was 65 cu. yd. in the upper deck and 33 cu. yd. in the lower deck. The total quantity of concrete in the two jetty-heads is 6500 cu. yd. The concrete for the lower decks amounted to 3000 cu. yd., and was deposited through metal trunking passing through temporary holes in the upper deck.

Fenders.



The fenders (*Fig. 2*) are of greenheart timbers 1 ft. 6 in. square faced with elm rubbing-strips. Each fender is supported laterally on a stout greenheart cross-head at the level of the top deck and at the lower deck. Two solid rubber cylinders, which when compressed absorb part of the energy, are provided between the cross-heads and the decks. The basis of the design is that the fenders should be capable of absorbing 2800 in.-tons of kinetic energy, this being a quarter of the energy of a vessel of 45,000 tons dead-weight (60,000 tons displacement) approaching the jetty at right-angles with a velocity of 1 ft. per second.

Dolphins.

Seven mooring dolphins are provided. Each dolphin, which comprises a concrete slab 21 ft. by 27 ft. and 5 ft. 6 in. thick supported on five vertical and eleven raking square hollow steel piles, is designed to withstand a pull on the bollards of 150 tons. The shuttering for the underside of the slab was suspended from the four vertical corner piles and was designed to support the weight of concrete in the first casting of one-third of the thickness of the slab. The side shutters were erected for the entire thickness of the slab. The concrete was deposited in three layers each containing 45 to 50 cu. yd. The first layer was allowed to harden for five days before the second was placed.

The working area, where the precast

beams were made and the timber fenders were fabricated, was about 100 ft. behind the river wall. The concreting plant comprised two 21/4 mixers and equip-



PART PLAN OF LOWER DECK

JETTIES FOR OIL TANKERS ON THE THAMES.

ment for weigh-batching and storing loose cement, and was capable of an output of 17 to 20 cu. yd. per hour.

The preliminary investigations, design,

and supervision of the work were made by Messrs. L. G. Mouchel & Partners. The contractors were Messrs. Peter Lind & Co., Ltd.




Fig. 2.—Elevation, Plans, and Sections.

A Low-cost Warehouse.

A NEW single-story warehouse (*Figs. 1 and 2*) at the chemical works of the Clayton Aniline Co., Ltd., Manchester, is 179 ft. long and 126 ft. wide. The roof comprises precast prestressed beams supporting reinforced concrete planks 2-in. thick. Natural lighting is provided by four roof-lights extending across almost the entire width of the roof. The beams, the height under which is 15 ft., are supported on precast reinforced concrete columns. There are only eight internal columns in an area of 22,800 sq. ft. The foundations are 7 ft. deep. The walls are of brick and are supported on precast beams which are at the level of the ground floor and are supported on the foundations of the exterior columns. The ground floor is a reinforced concrete slab

with 1½-in. granolithic finish which is coloured and includes a hardening compound. The arrises of the columns and the edges of concrete ramps, loading platforms, and the like are protected by steel angles which are galvanised as a protection against the corrosive atmosphere of the works.

The time of construction was 5½ months, most of which were in a severe winter. The total cost of the work was 38s. 5d. per square foot. The cost of the ground floor and foundations, including excavation, was 5s. per square foot. The cost of the structural parts of the superstructure, that is the precast and prestressed beams in the walls and roof, the columns, eaves beams, 2-in. roof slabs, and canopy, was about 10s. 6d. per square foot, exclud-



Fig. 1.




Fig. 2.

ing finishes, preliminary costs, and insurance.

The architect was Mr. S. Stothert, and the consulting engineers were Messrs. Taylor, Whalley & Spyra. The general

contractors were Messrs. G. & W. Smith (Builders), Ltd., and the precast prestressed work was made and constructed by the Fram Reinforced Concrete Co., Ltd.

Fifteen-story Flats Built in Five Weeks.

THE first of six fifteen-story structures in Paisley, Renfrewshire, is shown in *Fig. 1*. The reinforced concrete columns, walls, and floors from ground to roof level were constructed in five weeks with the aid of sliding shutters which were raised at a rate of about 9 in. per hour by means of ninety jacks operated simultaneously from one position. The floor slabs are 5 in. thick and are supported by walls, which are generally 6 in. thick, and columns. The walls are faced externally with bricks supported on projecting concrete nibs at each floor level, and the nibs are covered with "brick tiles" 1*1*/₂ in. thick to give the appearance of a continuous brick wall. The imposed loads assumed in the design are 60 lb. per square foot on the floors and a pressure due to wind of 14·7 lb. per square foot on the walls.

The mixture of concrete was 250 lb. of cement to 641 lb. of washed sand and 1030 lb. of washed gravel to which 10·1 gallons of water were added; this was calculated to be equivalent to a 1 : 1*1*/₂ : 3 mixture. For concrete to be used in the sliding shutters a water-cement ratio of 0·55 was used and for other concrete the water-cement ratio was 0·37. The aggregate-cement ratio was 6·3. The average compressive strength of this concrete at 28 days was 6000 lb. per square inch.

To ensure a continuous supply of concrete during the raising of the shutters two 18/12 mixers were used, each having an hydraulically-powered shovel and weigh-batcher and a tank, which on the operation of a lever supplied sufficient water for a batch of concrete. The concrete was mixed at a rate of 10*1*/₂ cu. yd. per hour, 1900 lb. of dry material being used in each batch. The mixers discharged into hoppers on bogies travelling on tracks, so that each mixer could supply either of two tower cranes which were used to elevate the concrete to the top

of the shutters; the cranes were 102 ft. high to the top of the tower and were capable of lifting 2*1*/₂ tons at a distance of 30 ft. to a height of 176 ft. The shuttering for the floors was of plastic-faced plywood supported on telescopic centres. The period occupied in dismantling the shuttering and erecting it for the next structure was four weeks.

The buildings were designed by the Paisley Burgh Engineer, Mr. J. M. M'Gregor, O.B.E., and the general contractors are Messrs. Blackburn (Dumbarton), Ltd. The Prometo system of sliding shutters is used.



Fig. 1.

Reservoir and Water Tower at Ipswich.

THE structures illustrated in Fig. 1, which comprise principally a covered reservoir having a capacity of 4,000,000 gallons, a pump-house, and a water tower having a capacity of 125,000 gallons, are now nearing completion. The work was commenced in June 1958, and is for the Ipswich Borough Council.

Reservoir.

The reservoir has two compartments each 164 ft. long and 124 ft. wide. The height from the floor to the underside of the roof is 17 ft. 10 in. (Fig. 2). The floor and roof slope 1 ft. and the average depth of water is 16 ft. 11 in.; there is a freeboard of 5 in. at the overflow weirs. Baffle-walls are not provided, but circulation of

joints are provided but during construction gaps 3 ft. wide were left in the floor and walls at about 30 ft. centres. After not less than twenty-eight days, when most of the shrinking had taken place, the gaps were filled. The roof slab was constructed in alternate bays. At construction joints, the surface of the concrete placed first was hacked to expose the aggregate over the entire face of the joint. Water-bars were not provided.

On completion of the concrete work and before depositing the earth forming the embankments and cover, each compartment was filled with water for twenty-eight days. The tests were made during the dry summer of 1959, and the absence of the insulation, provided later by the



Fig. 1.

the water is obtained by placing the inlet and outlet at opposite corners. The reservoir and water tower are on sand. The floor of the reservoir comprises a reinforced concrete slab 7 in. in thickness overlying a blinding layer of plain concrete 3 in. thick. The walls are designed as propped cantilevers and vary in thickness from 1 ft. 3 in. at the base to 8 in. at the top; the inner face is vertical. Excavation was simplified by forming the wall footings and column bases above the floor slab. The roof is a flat slab 7 in. thick with thickened panels and is supported on columns 1 ft. 2 in. square at 14 ft. centres.

No permanent contraction or expansion

earth, during the prolonged hot weather constituted a severe test. A few small leaks occurred, but by the end of the period of the test they stopped.

Water Tower.

The water tower is 84 ft. high and has a tank of 40 ft. internal diameter and 17 ft. 8 in. deep. The tank, the shape of which is octagonal on the outside, is lined with asphalt, and is supported on eight columns which taper from 2 ft. by 5 ft. at the foundation to 2 ft. by 4 ft. 2 in. at the underside of the tank. There are no intermediate braces. The central shaft is octagonal in cross section and encloses a reinforced concrete stair spanning

January, 1960.

RESERVOIR AND WATER TOWER AT IPSWICH.




Fig. 2.—Section through Reservoir and Pump-house.

between opposite walls of the shaft leaving spaces from the ground to the underside of the tank on either side of the stair for pipes. Access to the roof is by means of a ladder in a small circular shaft in the centre of the tank. When it was tested the tank was quite watertight.

Water for the tank is supplied from the reservoir by three 24-h.p. centrifugal

pumps each capable of delivering 500 gallons per minute; the pumps are automatically started in sequence as the level of the water in the tower falls.

Mr. J. B. Storey is the Borough Engineer & Surveyor and Water Engineer of Ipswich. The consulting engineers are Messrs. L. G. Mouchel & Partners. The contractors are Messrs. Howard Farrow, Ltd.

Retirement of Mr. R. V. Chate.

MR. R. V. CHATE, who has retired from the secretaryship of the Reinforced Concrete Association, will have the good wishes of a host of friends. Few men have so unobtrusively done so much to help the concrete industry. The Reinforced Concrete Association was started in the year 1931, when a few of the leading firms of reinforced concrete designers decided to form such a body with the primary object of furthering the interests of reinforced concrete as a sound and economical structural material, and in particular to negotiate with government departments and public authorities responsible for regulations and by-laws that sometimes hindered the use and development of reinforced concrete.

Mr. Chate, who had a long experience of design and construction in reinforced concrete, was invited to undertake the preliminary work of forming the Association, which was incorporated in 1932, and as its secretary he has since been the counsellor of a long succession of presidents and members of council. In the year 1945 he started the "Reinforced Con-

crete Review", in which periodical many valuable papers and other contributions have been published.

The Association has been fortunate in having as its executive officer a man who combines much wisdom and organising ability with sound technical knowledge, and whose unassuming manner has endeared him to all who know him. The extent of the ever-ready help he has unstintedly given to all who sought his advice, whether or not they were members of the Association, is known only to him. In his retirement Mr. Chate will be able to look back with pride at the progress made by the Association during the long period of his secretaryship, and in the knowledge that when he laid down the cares of office reinforced concrete had become accepted as the most important material for most types of structure and that most of the restrictive by-laws and regulations had been swept away. He was elected an Associate Member of the Institution of Civil Engineers in the year 1915 and a Member of the Institution of Structural Engineers in 1926.—H. L. C.

A Church with a Precast Roof.

A NEW Baptist Church (*Fig. 1*) at West Norwood, London, is 114 ft. wide, 95 ft. long, and 36 ft. high. There are also a side chapel and changing-rooms in a single-story building about 97 ft. by 27 ft. and 13 ft. high, a hall 102 ft. long, 40 ft. wide, and 22 ft. high, a store, and a basement. The church has a reinforced concrete frame and brick walls.

The roof of the church is at two levels (*Fig. 2*). The central part (*Fig. 3*) comprises precast curved ribs carrying 4-in. precast lightweight concrete slabs and supported on two longitudinal primary beams. The roofs over the sides of the church are at a lower level and comprise reinforced concrete slabs cast in place and spanning from the primary beams to eaves beams which are supported on the exterior columns.

The primary beams are 9 ft. deep and 1 ft. 9 in. wide and span 96 ft. 6 in. between the main columns at the ends of the church. They are designed to be freely supported and were cast in place in three parts, the middle part being cast after the ends. Parts of the shutters for the sides of the beams were omitted temporarily to allow the concrete to be placed in the lower part of the beam. Vibrators were used




Fig. 1.

internally and externally to compact the concrete, and the bars in the beam were arranged (*Fig. 4*) so that vibrators could be inserted between them. For a length of about 1 ft. at each end the concrete was omitted temporarily, and into this space bars projected from the beam




Fig. 2.




Fig. 3.




Fig. 4.—Elevation and Section of Part of Main Beam.



Fig. 5.—External Columns.

and from the column on which it rested. A strip of compressible material was placed between the column and the beam (*Fig. 3*) so that the joint between them was temporarily a hinge. When the concrete in the beams had hardened, the shutting and props were removed and the beam was allowed to deflect. The props were replaced and the precast roof members were erected. The concrete was placed in the spaces at the ends of the beams and around the projecting steel, thereby forming a continuous joint with the column. In this way the risk of cracks due to the shrinking and deflection of the completed structure was greatly reduced.

The curved ribs are at intervals of 5 ft. 3½ in., which conforms to the spacing of the fixings for the sheets of copper with which the roof is covered. The lower parts of the ribs were precast and bars project from them to form an anchorage to the compression flange formed by concrete cast in place between the ends of the precast roof slabs (*Fig. 6*). The slabs are of concrete containing 1½ parts of rapid-hardening Portland cement, 1½ parts of fine aggregate and 3½ parts of lightweight aggregate in the form of nodules of fused pulverised-fuel ash; this concrete has a density of 90 lb. per cubic foot and a crushing strength of 1500 lb. per square inch.

The exterior columns (*Fig. 5*) were precast in two parts, the lower part extending up to the level of the balconies which are cantilevered reinforced concrete slabs cast in place. The cross section of both parts is approximately rectangular (*Fig. 2*). The main columns, which are ell-shape in cross section, form the ends of the side chapel and the end walls of the church. These columns are fixed at the bottom.

The foundations, which are designed for a pressure of 1 ton per square foot, comprise principally two reinforced concrete rafts, one under each end of the church, where the greatest concentrations of load from the main columns supporting the roof beams occur. The walls and intermediate columns are on strip footings which are assumed to distribute part of the weight directly to the ground and to transfer the remainder to the rafts between which the footings span. Under the raft at the western end of the church there is a slab of plain concrete 4 ft. 3 in. thick. The raft at the eastern end forms




Fig. 6.—Cross Section through Roof and Detail of Precast Rib.

the floor of the boiler room, which is stiffened by two reinforced concrete beams.

The architects are Messrs. Ansell &

Bailey, the consulting engineers are Messrs. Scott & Wilson, Kirkpatrick & Partners, and the contractors Messrs. H. Fairweather & Co., Ltd.

Prestressed Pipe-Bridges.

THE construction, near Barrow in Furness, of three prestressed bridges to carry two 21-in. water mains is nearing completion. The bridges, two of which are over tidal water, have spans of 75 ft., 65 ft., and 42 ft. and are about 7 ft. 6 in. wide, thereby allowing a walkway of about 2 ft. 6 in. between the saddles supporting the pipes. One of the bridges is illustrated in Fig. 1. The two larger bridges comprise four precast I-beams, each made up of five blocks which were assembled, jointed, and prestressed with cables at the site. The assembled beams are also prestressed transversely by short cables. The smaller bridge is of similar construction but the precast blocks are smaller.

Due to the low bearing capacity of the ground, each abutment is formed by three

bored piles, the caps on which support the beams. Sliding joints, which are provided at each end of the two larger bridges and at one end of the smaller bridge, comprise copper plates one of which is attached by dowels to the underside of each beam and one on top of each pile-cap; a sheet of greased paper is placed between the pairs of plates. Anchor straps fastened to bolts built into the pile-caps are provided at each abutment to resist hydrostatic forces due to the change in direction of the pipes.

The design was prepared for Mr. H. C. Postlethwaite, Engineer of the Water Department of Barrow in Furness, by the British Reinforced Concrete Engineering Co., Ltd. The contractors are Messrs. Lane Brothers (Blackpool), Ltd.



Fig. 1.—Precast Beams in Position.

A Large Office Building.

THE illustration is of Bow Bells House, which has frontages to Cheapside, Bread Street, and Watling Street in the City of London, and the construction of which is nearing completion. The building comprises three parts—one of five stories, one of six stories, and one of eight stories. The frame was originally designed in steel-work but was later re-designed in reinforced concrete. In order to reduce the number of columns in the basement, part of which will be a car park and garage, some of the columns start at the ground floor which is designed as a distributing and stiffening slab and is 3 ft. thick. The basement is entered by means of a concrete ramp which is wide enough for two lines of traffic. A mechanical parking device will be installed. The foundation consists of bored piles of 2 ft. diameter and about 47 ft. long; the heads of the piles are 15 ft. below the level of the street.

The tank and lift-motor room are on the main roof and are in a penthouse, the roof of which cantilevers about 4 ft. but is apparently, but not actually, supported on circular precast concrete columns of

4 in. diameter and with an artificial stone finish. The underside of the balconies at the sixth and seventh floors of the highest block are faced with faience tiles, which are also used for some of the exterior walls. In general the walls will be faced with Portland stone and green ceramic tiles. The surrounds of the windows and the plinth will be of black granite. The three main stairs will be finished with terrazzo. The upper floors will be free of permanent partition walls. Cables for electrical floor heating will be embedded in the floor topping. A reinforced concrete cantilevered canopy faced with Portland stone is provided at the main entrance.

The time taken for the construction of the reinforced concrete frame and foundation piles was ten months, and the cost of this work was about £250,000. The architects are Messrs. Cotton, Ballard & Blow, and the consulting engineers are Messrs. W. V. Zinn & Associates. The contractors are Tersons, Ltd. The building is to be used as offices by Messrs. Balfour, Beatty & Co., Ltd.



A Winder Tower at a Colliery.

THE winder tower shown in *Fig. 1* is at Rising Sun Colliery, Northumberland, and details of the design are given in *Figs. 2* and *3*.

The tower is of reinforced concrete and is 69 ft. long, 43 ft. 6 in. wide, and 110 ft. high to the level of the lower roof above which there is a penthouse containing the air-filters and fans. There is a ground floor, three upper floors, and a penthouse (*Fig. 2*). The two 750-h.p. friction-winders (*W*) are on the third floor (*Fig. 3*); the drums of the winding plant are at (*D*). There is also a 22-tons winch operating over sheaves in the penthouse on the roof for servicing the cages and ropes, and a 10-tons overhead travelling crane for servicing the winders and for lifting materials from the ground to any of the floors through the hatch (*C*). A well (*L*) for a lift with a capacity of $\frac{1}{2}$ ton is also provided. On the second floor there are two electric generators and switchgear and four guide ropes for the counter-weights are attached to this floor; a 5-tons weight is suspended from each rope.

The main supports of the tower are four



Fig. 1.

January, 1960.




Fig. 2.




Fig. 3.—Plan of Third Floor.

ell-shaped columns each of which is supported on twenty-one bored piles of 1 ft. 5 in. diameter and 50 ft. long. Each column comprises a wall 1 ft. 6 in. thick by 14 ft. long and a pilaster 4 ft. by 2 ft. 6 in. The wall extends from the ground floor to the roof, but the pilaster extends up to the third floor only.

The third floor and the columns carrying this floor are designed to resist the forces imposed should the ropes supporting one of the two cages break, that is 220 tons from this cause, 124 tons due to the weight of the main equipment on the central area of the floor, 31 tons due to other plant, and a uniformly-distributed load of 100 lb. per square foot. The four primary beams, which form a 40-ft. square, are 8 ft. 6 in. deep and 2 ft. 6 in. wide. The two pairs of beams under the winders are at 12 ft. 3 in. centres and have a minimum depth of 7 ft. and a width of 2 ft. 6 in. Investigation of the natural frequency of the tower, and in particular of the supports of the winders, showed that at normal speeds of operation of the winders there would be no resonance in the beams.

The structures are for the National Coal Board. The consulting engineers are Messrs. Posford, Pavry & Partners. The main contractors were Messrs. J. L. Kier & Co., Ltd.

Lectures on Building.

THE following lectures have been arranged by the Ministry of Works. Admission is free.

The Builder and his Contract. By N. P. Greig. Technical College, Denzil Road, London, N.W.10. January 19. 7.15 p.m.

Prevention of Accidents in the Building Industry. By J. A. Hayward. College of Building, Cauldon Place, Stoke-on-Trent. January 20. 7.15 p.m. Also at Lambeth Town Hall, London, S.W.2. January 26. 7.15 p.m.

Methods and Plant for Concrete. By A. B. Harman. New School of Engineering, University, Bristol. January 21. 6 p.m.

Work Study in the Building Industry. By R. Geary. Guildford Hotel, The Headrow, Leeds 1. January 22. 7.15 p.m.

Thermal Insulation of Buildings. By F. King. College for Further Education, Avenue Road, Grantham. January 26. 7.15 p.m.

Building and Civil Engineering Subjects (film show). Lord Nelson Hotel, Milford Haven. January 27. 7 p.m.

Practical Formwork Design and Construction. By J. G. Richardson. Technical College, Bell Street, Wakefield. January 28. 7.15 p.m.

A Large Reservoir in Kent.

NEW WALL SHUTTERS.

A SURFACE reservoir at Singlewell, near Gravesend, Kent, constructed for the Medway Water Board, has a total capacity of 4,000,000 gallons in two compartments, is 300 ft. long by 150 ft. wide and 17 ft. 6 in. high, and is constructed of reinforced concrete. The roof is supported on columns at intervals of 15 ft. 6 in. in both directions. Expansion joints with plastic water-bars are provided at intervals of about 31 ft. in the walls, floor, and roof. The floor was cast on building paper laid on a concrete sub-base. The foundations of the walls, and the walls to a height of 3 in. above floor level, were cast together and a metal water-bar is embedded in the construction joint at this level.



Fig. 1.—Internal Shutters.



Fig. 2.—Compacting the Concrete at a Gap in the Inner Shutters.

The concrete was mixed in the proportions of 1 : 1.6 : 3.2 with graded aggregate of $\frac{1}{4}$ in. maximum size and with a water-cement ratio of 0.56. The slump did not exceed 1 in. and the strength at 28 days was not less than 4500 lb. per square inch.

Parts of the side walls up to 30 ft. long were cast in one lift 17 ft. 3 in. high (Fig. 1) in a new type of shuttering which has hinged flaps 2 ft. 3 in. high through which the concrete is placed at different heights. The shuttering panels are 5 ft. high by 4 ft. wide and are bolted to vertical members which are 10 ft. high by 1 ft. wide and are stiffened by a tube and two mild-steel lattices which are welded to the back of the member (Fig. 2). The panels and vertical members comprise sheet-steel frames covered with $\frac{1}{2}$ -in. plywood.

The shuttering for the external face was moved, in sections about 31 ft. long and 18 ft. high, by a crane and supported in position by diagonal struts (Fig. 3) which are adjustable to enable the shuttering to be aligned. The shuttering for the

sloping inner face was fixed to the outer shuttering by spacers which passed through the wall and were variable in length. This shuttering was moved in sections 6 ft. wide and 18 ft. high, which were erected with gaps 4 ft. wide between them to provide access to the spacers. When these sections had been aligned, panels were bolted across the gaps up to a height of 6 ft.

Concrete was placed from a bottom-opening skip (*Fig. 3*) through hinged flaps in the outer shuttering; the flaps are hinged at the bottom (*Fig. 4*) and, when open, form chutes to direct the concrete to the interior. The concrete was compacted by means of poker vibrators passed through gaps in the inner shutters as shown in *Fig. 2*. When the concrete reached the bottom of the hinged flaps of the outer shutters, the flaps were closed and the gaps in the inner shuttering were covered to a level 6 ft. higher, to




Fig. 4.—Hinged Flap through which the Concrete is Placed.




Fig. 3.—View of External Shutter.

which level more concrete was placed. In this way sections of the walls up to 30 ft. long and 17 ft. 3 in. high were shuttered and cast and the shuttering removed within fifty-six hours.

The reservoir was designed by the F.C. Construction Co., Ltd. The general contractors were Messrs. Thomas Lowe & Sons, Ltd. The shuttering is a new type produced by Kwikform, Ltd.

Prestressed Concrete.

THE Prestressed Concrete Development Group is arranging an exhibition of prestressed concrete at the Institution of Civil Engineers, Great George Street, London, S.W.1, from January 14 to 21. On January 14 the following papers will be read: "Prestressed Concrete Bridges in the British Isles", by Mr. A. Goldstein. "Prestressed Concrete Bridges Abroad", by Mr. A. J. Harris. "Research on Prestressed Concrete Bridges", by Mr. R. E. Rowe. "Bridges on the Maidstone By-pass", by Mr. H. Bowdler (County Surveyor of Kent) and Mr. F. M. Bowen. Tickets for admission are obtainable from the Secretary at 52 Grosvenor Gardens, London, S.W.1.

January, 1960.

Grain Silo of 50,000 Tons Capacity.

A STRUCTURE (Fig. 1) being built at Meadowside, Glasgow, for the Clyde Navigation Trust provides storage for 50,000 tons of grain. The grain is brought in by conveyors through two gantries served by pneumatic unloading plants on the adjacent quay and is transferred to the bins by means of eight band-conveyors. The structure is of reinforced concrete, but the external faces of the walls of the bins are faced with brick-work. Other walls are of cavity construction comprising bricks and precast slabs with exposed granite aggregate.

The storage section is 90 ft. wide and 315 ft. long, and is divided into twenty-

above the other. To provide space for the elevator platforms to the upper group of conveyors, the floor over the bins is at the unusual height of 20 ft., which, combined with the three stories below the bins, makes the height of the storage section 157 ft. Expansion joints are provided above and below the bins at about the third points and above the bins at the ends of the storage section. The bins are constructed monolithically. Services are in a two-story structure cantilevered from one face of the storage section at the levels of the first and second floors and extending the length of the middle third of this section.




Fig. 1.

one rows of six bins each 15 ft. square, except in the end rows where there are twelve bins. A ten-story working-house 188 ft. high is provided at each end of the silos. Below the bins there are three stories providing accommodation for the chutes, automatic mobile weighers and, on the ground floor, three longitudinal railway tracks. Access for road vehicles is provided transversely. The main building is carried on a reinforced concrete raft 4 ft. thick bearing on boulder clay. The columns of the working-houses are supported on separate reinforced concrete footings each 10 ft. square.

Above the bins eight band-conveyors are arranged in two groups of four, one

The bins were constructed in six separate parts by means of continuously moving timber forms suspended from steel yokes and operated by oil-jacks. The average time taken to construct the walls for each part was seven days. No two adjacent parts were erected successively, and the time between the completion of one part and start of the adjoining part was about 3½ weeks. The whole of the work built with moving forms was completed in less than six months. Because a facing of brick was to be applied to the walls of the bins, greater accuracy was necessary in the vertical and horizontal alignment of the forms; in the few cases where correction

was required this was achieved by the application of horizontal forces applied from a scaffold tower erected against the outer face of the wall.

The engineer of the Clyde Navigation

Trust is Mr. A. Thomson. The consulting engineers are Messrs. L. G. Mouchel & Partners. The contractors for the civil engineering work, the cost of which is £725,000, are Messrs. Holst & Co., Ltd.

A Water Tower in Essex.

THE reinforced concrete water tower (*Fig. 1*) for the Southend Waterworks Company at Thundersley, Essex, has a capacity of 200,000 gallons. The tank is 56 ft. in diameter, and is supported on ten rectangular columns 2 ft. 3 in. by 2 ft. 4 in. in cross section and a central access shaft of 13 ft. diameter. The top water-level is 63 ft. above the ground.

Trial bores showed a fine sand for a depth suitable for a raft foundation and London clay at a depth of about 22 ft. Experience of this sand at a neighbouring site had shown its tendency to sponginess when it was exposed, so the structure is carried on sixty-five bored piles. One of the piles was tested to twice its working load by an hydraulic jack bearing against four adjacent piles ; the settlement was 0·13 in., which was reduced to 0·07 in. when the load was removed.

The concrete in the foundation and central shaft was a 1 : 2 : 4 mixture, and in the columns and tank a 1 : 1½ : 3 mixture. The tank was designed in accordance with the Code of the Institution of Civil Engineers for Liquid-retaining Structures and was provided internally with a rubber lining. Twisted square reinforcement bars were used in the walls and floor so that any cracks that might occur would be widely distributed and of negligible width.

Access to the working platform below the tank is by a curved staircase fixed to one half of the circumference of the central shaft ; each landing spans across the shaft as a chord of the shaft, leaving space on the other side of the shaft for the pipes for filling and cleaning the tank.

The lining is of natural rubber ¼ in. thick and was installed by the Dunlop



Fig. 1.

Rubber Co., Ltd. Metalwork throughout (other than the Company's equipment) is of aluminium in order to reduce the risk of corrosion. The outer face of the concrete was washed with a slurry of cement and silver sand and rubbed with a carbordum disk.

Mr. Adam Hope is the Engineer of the Water Company. The consulting engineers were Messrs. Leslie Turner & Partners and the contractors Messrs. Holst & Co., Ltd. The piles were constructed by Holmpress Piles, Ltd. The cost of the work, excluding the pump and pipework, was about £29,300.

Precast Concrete in a Factory Building.

PRECAST members, most of which are prestressed, are being used in the construction of a two-story factory building in Battersea, London. The work now in progress comprises six parts, each about 76 ft. wide and 78 ft. long, which form the major part of the building, and expansion joints are formed to separate the parts. As is seen in Figs. 1 and 2 the roof is of a novel design.

The columns are of precast reinforced concrete, some to the full height of the building and some to first-floor level only; they are spaced at intervals of 39 ft. in one direction and 38 ft. in the other. The method of assembling the beams and

columns, and a joint between two sections of the building, are shown in Fig. 3; at such a joint two main beams support the first floor. The first floor is formed of precast slabs 13 ft. long, 7 ft. 2 in. wide, and 6½ in. thick which are supported on secondary beams 38 ft. long and containing 92 pre-tensioned wires of 0·2 in. diameter. When the slabs are in position concrete is placed around mild-steel reinforcement projecting from the secondary beam and in slots formed in the ends of the slabs (Figs. 3 and 6).

At the ends of each secondary beam on the underside are ½-in. mild-steel bearing plates which rest on similar plates




Fig. 1.—Cross Section of Roof.




Fig. 2.—Precast Roof.




Fig. 3.—Arrangement of Columns and Beams.




Fig. 4.—Parts of Main Beam in Position.




Fig. 5.—Erecting a Rib.

provided at intervals of 13 ft. along the lower flange of the main beams which are partly precast and partly cast in place.

The precast portion of each main beam is of inverted tee-section and about 38 ft. long and is prestressed with 220 wires of 0.2-in. diameter, each of which is tensioned

with a force of 3200 lb. The top flange, which is level with the top of the floor, is cast in place around reinforcement projecting from the precast portion (Fig. 6). Concrete is also placed at the side of the beam between the lower flange and the soffit of the floor to provide added protection against fire.

Above the first floor the internal columns are discontinued and the roof is supported by precast beams about 78 ft. long bearing on the outer columns (Fig. 2). These beams are 4 ft. deep and are in two parts each with a top flange 20 in. wide and a bottom flange 10 in. wide (Fig. 3), and are precast in lengths of 11 ft. 10 in. In Fig. 4 one of these beams is shown assembled ready for concrete to be placed between the precast parts.

While the beams are being erected the precast parts are supported on scaffolding with the halves of the beam 3 ft. 7 in. apart. U-shaped ribs of reinforced concrete (Figs. 5 and 1) to carry the roof are erected transversely between the precast sections (Fig. 6). Fifty wires of 0.276 in. diameter are then placed along the inner




Fig. 6.—Construction of Floor and Roof.

face of each half of the beam and through steel plates in the ribs. The wires pass through two anchor-blocks provided at the ends of the beams (*Fig. 7*) and are fixed by P.S.C. 4-wire anchors. Concrete in the proportions 1 : 1 : 2½ with aggregate of $\frac{1}{2}$ in. maximum size and rapid-hardening Portland cement, and having a maximum slump of $\frac{1}{2}$ in., is placed in all the joints. When the concrete has hardened the wires are each tensioned with a force of 9900 lb., including an allowance of 16 per cent. for losses. The wires are then covered with concrete.

The cross section through the roof (*Fig. 1*) shows hollow prestressed purlins 14 in. wide and 6 in. deep supported by prestressed beams which rest on the arms of the ribs (*Fig. 6*) and are fixed in position by two bolts projecting vertically from the end of each arm. Before the main beams are prestressed weights are placed on a platform suspended from the centre of each beam (*Fig. 2*) to prevent it deflecting upwards while the roof is being erected.

Minor beams are connected to the columns by means of steel plates projecting from the lower part of the end of the beam and welded to steel tee-sections projecting from the column (*Fig. 3*). Reinforcement projecting from the upper portion of the end of the beam is threaded at the ends and connected by threaded sleeves to corresponding reinforcement in




Fig. 7.—Cables at End of Roof Beam.

the column. When the beam has been aligned the connection is welded and concrete is cast around it to form a continuous joint between the beam and the column.

The architects are Messrs. L. D. Tomlinson & Partners, the general contractors are Messrs. W. H. Gaze & Sons, Ltd., and the design and erection of the concrete frames and floors are by Concrete, Ltd. Prestressing is by the P.S.C. MonoWire system.

Salaries in the U.S.A.

YOUNG men considering emigrating to the U.S.A. will be interested in an article in "Engineering News-Record" for June 4, 1959, which gives summaries of interviews with the heads of U.S.A. universities on the employment of graduates in civil engineering. It is stated that the demand for such men by state and local authorities and by industry is greater than ever before. The graduates experience no difficulty in finding employment, and are able to be selective in choosing an employer.

The starting salary for a graduate with a bachelor's degree is said to average 500 dollars a month. At the present rate of exchange this equals £2140 a year. Some idea of the value of such a salary in the U.S.A. may be had by comparing it with the rewards received in other

walks of life. For example, the average basic wage of a bricklayer in New York is 4.25 dollars an hour; on the basis of 48 working weeks of 40 hours each a bricklayer's basic wage would be £2900 a year. In Great Britain the highest basic rate for a bricklayer is 4s. 9d. an hour, which amounts to £456 in a working year of 48 weeks of 44 hours each, and this may be compared with a starting salary of £700 or so a year offered in Great Britain to graduates in civil engineering. In the U.S.A. the graduate is paid less than a bricklayer's basic wage rate, whereas in Great Britain he is paid more than the bricklayer's basic rate—no doubt in the U.S.A., as here, the bricklayer's pay packet generally contains a good deal more than the basic rate agreed with the trade unions.

Eighteen-story Flats in London.

THE tall blocks of flats being erected at the Brandon Estate, Southwark, for the London County Council are now almost complete. There are six structures of eighteen stories (*Fig. 1*) and the construction, which is a combination of precast and cast-in-place concrete, was planned to enable the buildings to be erected without an external scaffold (*Fig. 4*); climbing cranes were used inside the buildings and tower cranes outside. A cross section is shown in *Fig. 2*, and plans of a typical floor and the foundations are shown in *Fig. 3*.

Foundations.

The ground consists of 4 ft. of filling overlying ballast and sand from 7 ft. to 24 ft. thick below which is London clay of a silty nature. The foundations comprise 180 bored concrete piles 20 ft. to 50 ft. long. The normal loads on the piles are 30 or 40 tons, which is increased by not

more than 25 per cent. due to dead and imposed loading combined with the effects of wind. The lengths of the piles were determined to ensure uniform settlement of the pile caps.

Superstructure.

The loads are carried by concrete walls and columns cast in place. On the east




Fig. 1.




Fig. 2.—Cross Section.




Fig. 3.—Plans of Upper Floor and Foundation.

EIGHTEEN-STORY FLATS IN LONDON.

and west elevations precast columns extend through four stories. At each fourth floor the columns are supported on a deep fascia beam, which is an architectural feature and is also of structural importance.

Wind forces are resisted by the concrete walls around the lift shafts and entrance lobbies acting as vertical cantilevers extending from the foundations. The structures on each side of the lobby act separately. The floor slabs are designed as horizontal beams transmitting the forces due to the wind to the walls. The dead loads on the walls are such that

under the most adverse conditions of wind the tensile stresses in the walls are very small.

The floor slabs are 4 in. thick and span 10 ft. and were cast in place. They are supported on beams 6 in. wide, which coincide in position with the partitions between the rooms. Most internal columns and walls are 6 in. thick; the flanges of the columns also are in line with the partitions.

Precast slabs are used for the external walls and are supported on precast beams bolted to the columns (*Fig. 5*). The slabs, which have an exposed-aggregate




Fig. 4.

finish of white calcined flint, are designed to allow all fixing to take place from inside the building (*Fig. 6*). Sufficient clearance is allowed between the precast beams and the columns and also between the beams and the slabs to enable the beams and slabs to be fixed in their correct positions even if the members cast in place are slightly out of line or level. The joints are waterproofed by a plastic sealing compound, which was applied from a suspended cradle. Should the seal fail, or should condensation occur on the back of the slabs, a means of drainage is incorporated at the back of the slabs and moisture is discharged into a gutter at the bottom of the wall.

Design Data.

The buildings were designed before the London County Council had accepted the recommendations of B.S. Code No. 114 (1957), and the design is therefore in accordance with the earlier by-laws of the Council. The concrete in the columns and walls in the lower stories is a 1 : 1 : 2 mixture, and the direct compressive stress permissible is 1140 lb. per square inch. Elsewhere the concrete is a 1 : 2 : 4 mixture and the compressive stress permissible in bending is 1000 lb. per square inch. These stresses were increased by 10 per cent. for vibrated concrete.

Reinforcement in compression and stirrups are of mild steel, but bars in tension are cold-twisted square bars the tensile stress permissible in which is 30,000 lb. per square inch. There are in each structure about 46 tons of high-tensile steel and 64 tons of mild steel.

The total cost of each structure, includ-




Fig. 6.—Fixing Wall Slabs.

ing the foundation, was about £58,000, of which about one-fifth was the cost of the foundation. The rate of erection was about one story in five working days. The buildings were designed by Mr. Hubert Bennett, Architect of the London County Council, and Mr. Whitfield Lewis, principal Housing Architect of the Council. The consulting engineers are Messrs. Felix J. Samuely & Partners. Professor A. W. Skempton advised on the foundations. The contractors are Messrs. Wates, Ltd.





Fig. 5.—Fixing Precast Beams.

Grouting Prestressed Concrete.

A SYMPOSIUM on Grouting Prestressed Concrete will be held under the auspices of the Fédération Internationale de la Précontrainte and R.I.L.E.M. in Trondheim, Norway, from June 20 to 22, 1960. There will also be an exhibition of grouting equipment. Contributions for presentation at the symposium should be sent to Professor I. Lyse, Norges Tekniske Høgskole, Trondheim, Norway, by March 15, 1960.

CONCRETE SHUTTERING

A SIMPLE CLAMP ENABLING THE
USE OF STANDARD SCAFFOLD TUBE
FOR ALIGNMENT OF SHUTTERING



Manufactured and Supplied by

A. A. BYRD AND CO., LIMITED (Dept. C)

210 Terminal House, Grosvenor Gardens, London, S.W.1

'Phone : SLOane 5236.

'Grams : Byrdicom. Wesphone, London.

**THE DESIGN AND SUPPLY
OF THE ENTIRE FORMWORK
FOR THE PRECAST UNITS FOR**

**DUNGENESS
LIGHTHOUSE**

WERE ENTRUSTED TO US



One of the first complete formworks leaving our new works en route to the works of Spun Concrete Ltd., who are responsible for the precasting programme of this lighthouse. Architects and Engineers: Messrs. Ronald Ward & Partners. Contractors: Taylor-Woodrow Construction Ltd.

YOU TOO CAN DEPEND ON US

STELMO

*the most comprehensive
mould service in the world*

STELMO LTD. · WESTWELL LEACON · CHARING · ASHFORD · KENT. Tel: Charing 395-7

Prestressed Roof Trusses.

THE curved roof of the assembly hall at West Derby Technical School, Liverpool, is shown on the right of Fig. 1. On the left is a small pyramidal roof which is raised to provide a clerestory.

The assembly hall is 79 ft. long, 60 ft. wide, and 18 ft. high to the eaves. Bowstring trusses are provided across the hall at 10 ft. centres and support prestressed tee-shaped purlins at 4 ft. centres with a covering of strawboard and bituminous felt. At one gable intermediate columns are provided and at the other gable a stronger truss was constructed with hangers to support a roof at a lower level.

The trusses have 9-in. by 8-in. rafters cast in place and prestressed ties comprising 5-in. by 4-in. precast members 3 ft. long with a hole on the longitudinal axis through which were passed $\frac{1}{2}$ -in. high-tensile steel-alloy bars. A 1 : 1 cement-sand mortar was placed between the units, and when this had hardened sufficiently a pull of 18.3 tons was applied

to each bar, which extended 2.73 in. The bars were then pressure-grouted in the concrete members and the ends of the bars cut off. The anchor-plates, which are 6 in. by 7 in. and $1\frac{1}{2}$ in. thick, project from each side of the tie into the concrete of the arch to transmit the thrust from the arch to the tensioned bar (Fig. 2). Each tie is suspended from the arch by two $\frac{1}{2}$ -in. mild-steel bars encased in 4-in.-square precast units.

When the ties were in position the arch was cast, except for a length of 2 ft. at the middle which was cast fourteen days later to allow for shrinking. After fixing the purlins in position and when the concrete had sufficiently matured the shuttering was removed.

The gable arches are similar to the internal arches except that the ties were cast in place and prestressed with two $\frac{1}{2}$ -in. tensioned bars in each and the rafters are 18 in. deep.

The roof of the kitchen consists of a



Fig. 1.




Fig. 2.


pyramid 19 ft. by 22 ft. on plan formed by four triangular slabs 4 in. thick supported at the corners by columns and stiffened along the edges with horizontal beams 2 ft. 4 in. wide.

The roof was designed by the method described by Mr. A. J. Ashdown in "The Design of Prismatic Structures". The

architects are Messrs. Harold E. Davies & Son in collaboration with Dr. R. Bradbury, the City Architect. The main contractors were Messrs. R. J. Barton & Son, Ltd., and the precast members were made by Truscon, Ltd., who were the sub-contractors for the design and construction of the reinforced concrete work.

FIFTY YEARS AGO.

From "CONCRETE AND CONSTRUCTIONAL ENGINEERING", January, 1910.



Test on Arch Roof.—Before the publication of the London County Council Regulations for reinforced concrete in 1915 loading tests were common to satisfy the authorities that a structure was sound. An example is the roof of the public swimming bath at Hammersmith, a cross section of which is illustrated above. It is stated that, "The load was applied as nearly as possible in the same manner as the load which was to be borne by the principals, and for this purpose cradles were slung from two of the principals. The load was applied by means of bags filled with ballast, each bag weighing 1 cwt (the bags were placed on the cradles). There was no spread at the abutments. The roof was superloaded to an extent of 50 per cent. of the permanent dead load. The greatest deflection measured was only $\frac{1}{5}$ in., and after removal of the load the roof principals recovered their original form."

work in progress



Wherever the sign of Howard Farrow appears there is work in progress.

This photograph illustrates the Ipswich Reservoir and Water Tower in the course of construction for Ipswich County Borough.

Other work in progress includes sewerage, tunnelling, concrete structures, factories and domestic buildings.

A folder giving a selection of Howard Farrow contracts covering a wide field of projects will gladly be sent on request.

The plant was designed by Mr. J. B. Storey, Borough Engineer, and Water Engineer of Ipswich.

Architects: Messrs. R. P. Maggs and S. Simmons.


Consulting Engineers: Messrs. L. G. Mouchel & Partners.

A Company Member of the British Institute of Management

HOWARD FARROW

CIVIL ENGINEERING AND BUILDING CONTRACTORS

BANK BUILDING, RUSSELL PARADE, GOLDERS GREEN RD, LONDON, N.W.11 MEA 3232



CONWAY BRIDGE

*From an original by C. W. Glover, M.I.C.E.,
M.I.Mech.E., M.I.Struct.E., M.Cons.E.,
of C. W. Glover & Partners, Consulting Engineers.*

As the cement suppliers for the construction of the new bridge at Conway, we are proud to be associated with the contractors responsible for this fine structure.

The contract was supplied from our Padeswood Works, near Mold in Flintshire. This modern Works is splendidly sited to supply the growing industrial needs in the Wirral and on Merseyside and, at the same time, the many important developments taking place in North and Central Wales.

As the country's industrial capacity expands so must the practical and technical skills of the Building Industry. Our modern Padeswood Works, with first-class laboratory, technical and advisory facilities is an example of our contribution to the needs of the Industry which we serve.

THE TUNNEL PORTLAND CEMENT CO LTD

105 PICCADILLY, LONDON, W.1

Telephone: GROsvenor 4100

alignment while being driven through the hard ballast by a temporary steel structure (*Fig. 2*). Should it be necessary to raise the river wall in the future, provision has been made for the part of the platform

at the wall to be cut away and replaced by a ramp. The architect is Mr. C. Oboussier, the consulting engineers Messrs. Lewis & Duvivier, and the contractors Messrs. W. & C. French, Ltd.

Stair with a Curved Roof.

THE stair illustrated in *Fig. 1* is at the entrance to the extensions recently completed at Sunderland Technical College. The new works include classrooms, assembly hall, and workshops. The stair is at the entrance to the assembly hall, which is on the first floor. The structure of the hall comprises upper rectangular reinforced concrete frames 29 ft. high, the columns of which are 10 in. thick and taper from 30 in. wide at the top to 10 in. at the level of the first floor, where there is a hinged joint at the head of each of the columns in the lower story.

The entrance is between two of the upper frames. The external stair, which extends from the first floor to the ground, is covered by a curved concrete roof

supported at one end on a beam between the two frames. The thickness of the roof is $2\frac{1}{2}$ in. An intermediate support, beyond which the roof cantilevers 8 ft., is provided by two reinforced concrete raking struts which extend to the bases of the columns of the bottom story of the building.

The stair comprises precast concrete treads and a precast intermediate landing carried on two cranked stringer beams, which are supported intermediately by a beam between the raking struts.

The Borough Architect of Sunderland is Mr. H. C. Bishop. The reinforced concrete work was designed by the British Reinforced Concrete Engineering Co., Ltd., and the contractors were Messrs. Geo. H. Plemper Ltd.




Fig. 1.

NEW GARAGE, SHOWROOM, AND OFFICES

for The Lincolnshire Motor Co. Ltd.

This unusual and extremely modern group of buildings is an excellent example of Gee, Walker & Slater's ability to build in concrete.

A rectangular office block, a circular showroom and directors' office, and a garage, the roof of which is composed of hyperbolic paraboloid shells, were all constructed in reinforced and pre-stressed concrete.

CONSULTING ENGINEER *Dr. Hajnal-Konyi, M.I.C.E., M.I. Struct. E.*

ARCHITECTS *Denis Clarke-Hall, Sam Scorer and Roy Bright, F/A.R.I.B.A.*

MAIN CONTRACTORS



HEAD OFFICE: 100 PARK LANE, LONDON, W.1. ALSO AT DERBY AND BRIDGEND

CONCRETE IN SULPHATE- LADEN SOILS

To eliminate risk
**CIMENT FONDU
SHOULD BE USED**

To ensure
complete protection
**CIMENT FONDU
MUST BE USED**

Concrete
made with
CIMENT FONDU is
COMPLETELY IMMUNE
from the effects of
SULPHATES
in any concentration

Concrete made with Ciment Fondu provides an additional margin of safety! It is also resistant to attack by dilute acids often prevalent in sulphate-bearing clays, made-up ground and many industrial effluents.



*Send for leaflet TSS-16 "The Influence of Mineral Sulphates on the Permanence of Concrete Structures."

LAFARGE ALUMINOUS CEMENT COMPANY LTD., 73 Brook St., London, W.1. Tel: MAY 8848

AP/69

Prestressed Concrete Underpinning Beam.

THE entrance to a garage on the ground floor of an extension to a building occupied by Messrs. W. H. Smith & Son, Ltd., in Fetter Lane, London, is through the original building. To provide access of sufficient width it was necessary to remove a cast-iron column of 10-in. diameter supporting a corner of the older building, which comprises four stories and has load-bearing brick walls carried at the level of the first floor on steel girders spanning between cast-iron columns.

The load on the cast-iron column which was removed was transferred to a new beam spanning 24 ft. from a bracket on one of the columns of the new building to a new column provided to support the end of the beam (*Fig. 1*). The total load is 65 tons, and is applied at one of the third-points of the span of the beam, the depth of which was restricted to 2 ft. in order to provide sufficient height for the vehicles using the garage.

The depth of 2 ft. made a reinforced concrete beam impracticable, and a prestressed concrete beam was provided. The tendency of such a beam to camber upwards due to the prestressing force

would counteract the downward deflection due to the load and thus greatly reduce any possible movement of the old load-bearing brickwork. To reduce the effect of possible settlement of the new foundation, the prestressed beam was not cast until the column of the new building was carrying most of its dead load.

A Freyssy flat-jack was provided at the top of the new column so that adjustment could be made for excessive deflection or settlement. A fire-resistance of two hours was required, and consequently not less than $2\frac{1}{2}$ in. cover of concrete was necessary over the prestressing cables. At the plane of greatest bending moment on the beam, the head of the cast-iron column restricted the width of the beam in which prestressing cables could be placed. Consequently it was necessary for the beam to be 3 ft. 6 in. wide.

B.B.R.V. cables are used in order to reduce the number of cables and ensure that they should have the greatest possible eccentricity. Four cables tensioned to 93 tons in $2\frac{1}{2}$ -in. diameter metal sheaths and two cables tensioned to 55 tons in $1\frac{1}{2}$ -in. sheaths are provided.




Fig. 1.


The strength of the concrete was specified to be 6000 lb. per square inch at 28 days. The cables were tensioned ten days after the beam had been concreted, and a week later were again tensioned to ascertain the reduction of prestress. The greatest reduction was 2 tons in one of the cables tensioned to 93 tons and was due almost entirely to the order in which the cables were tensioned, since a reduction of the force occurs in the cables tensioned first due to the elastic shortening of the beam caused by tensioning subsequent cables.

After grouting the cable ducts, gauges were placed between the beam to measure the deflection when the cast-iron column was removed. The column was cut first by means of oxy-acetylene flame at a convenient position near the floor. During the operation of burning through the column the head of the column and the beam rose 0.04 in. due to the thermal expansion of the column. Immediately after the column was cut the downward deflection of the beam was 0.01 in. but during a period of two days the deflection reversed to an upward movement of 0.01 in. The probable explanation of these movements is that the initial downward deflection was caused by the elastic shortening and settlement of the columns and that the reversal of the deflection was

due to creep of the prestressed beam caused by an excess of bending moment due to the prestressing force exceeding the bending moment due to the load. The deflections were very small and measurable only with sensitive deflectometers, and the final upward camber was advantageous.

At the moment the column was cut there was a slight jerk in the structure, causing a sideways movement of about $\frac{1}{2}$ in. at the upper part of the column. This action indicated that the column was carrying the load eccentrically, thus producing bending moments the strains due to which were released on cutting the column. The column was later cut at a position 1 in. inside the beam by drilling and sawing at an angle; about a third of the holes had been drilled prior to casting the beam. The flat-jack on the new column did not have to be used owing to the satisfactory final deflections. Should there be any future differential settlement between the new and the old buildings it will be a simple matter to use the jack to counteract this effect.

The architect for the building is Mr. H. F. Bailey. G.K.N. Reinforcements, Ltd., made the structural design and supplied the reinforcement. The main contractors were Messrs. Holland & Hannen and Cubitts, Ltd.



Trent Gravels 10,000 tons per week

Washed & Crushed $1\frac{1}{2}$ in. to $\frac{1}{2}$ in.

We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt delivery guaranteed and keen competitive prices quoted. Send for samples and prices.

TRENT GRAVELS LTD

ATTENBOROUGH

Telephone : Beeston 54235

NOTTS

THE UNIVERSITY OF LEEDS BURSARIES IN CONCRETE TECHNOLOGY


Applications are invited for Bursaries in Concrete Technology tenable from 1st October, 1960.

The value of the Bursaries is £400 per annum, out of which the University fees must be paid. The Bursaries will be awarded for one year and may in certain circumstances be renewed for a second year.

Applicants must hold a degree in Engineering, or its equivalent. The course will include post-graduate lectures, design, drawing and laboratory work.

Applications, giving full details of qualifications and experience, together with the names of two referees, must be received by THE REGISTRAR, The University, Leeds, 2, not later than 1st March, 1960.

Multi-wire strand For prestressed concrete



This photograph shows the stressing of multi-wire "Bridge" Strand at the Perth Narrows Bridge in Australia. "Bridge" Strand is made from Somerset Wire.

CONSULTING ENGINEERS: G. Maunsell & Partners
PRESTRESSED CONCRETE CONSULTANT: E. W. H. Gifford
CONTRACTORS: Christiani & Nielsen Ltd.

**IF YOU WANT TO PUT STEEL INTO CONCRETE
GET IN TOUCH WITH**

G.K.N. Reinforcements Ltd

197 KNIGHTSBRIDGE, LONDON, S.W.7. KENSINGTON 6811

SMETHWICK, BIRMINGHAM (Smethwick 1991) • MANCHESTER (Ardwick 1691)
 GLASGOW (Bell 2444) • MIDDLESBROUGH (3843) • CARDIFF (Cardiff 45220)
 BRISTOL (Bristol 21555) • LEICESTER (Leicester 25114) • LEEDS (Leeds 27311)
 WORKS AT CARDIFF, SMETHWICK, WIGAN & GLASGOW

WELLERMAN BROS.

LIMITED

SHEFFIELD & HYDE

CIVIL ENGINEERING CONTRACTORS

Specialists in
Reinforced Concrete
Prestressed Concrete
Steel & Concrete Piling
Bridgeworks



WELLERMAN BROS. LTD.

DUN STREET, SHEFFIELD 3. Tel. 23238-9

EDWARD STREET, HYDE, CHESHIRE. Tel. 2058

MISCELLANEOUS ADVERTISEMENTS.

Situations Wanted. 5d. a word: minimum, 12s. **Situations Vacant.** 6d. a word: minimum, 15s. **Other miscellaneous advertisements,** 6d. a word: minimum, 15s. **Displayed advertisements,** 40s. per column inch. **Box number 12, extra.**

Advertisements must reach this office, 14 Dartmouth Street, London, S.W.1, by the 23rd of the month preceding publication.

SITUATIONS VACANT.

SITUATIONS VACANT. Detailer and designer-draughtsmen required for rapidly expanding reinforced concrete design office. Permanent supernumerary positions. Five-days week. Excellent working conditions in modern offices with canteen. Write, stating experience, age, and salary required, to THE SECRETARY, THE ROM KINGS CO. LTD., 100 Stewarts Road, Battersea, London, S.W.13.

SITUATIONS VACANT. Reinforced concrete detailers, all grades, required for new office opening in Bournemouth. Good conditions, five-days week, salaries according to capabilities. Interviews London and Bournemouth. Details, with present salary, to Box 4634, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Assistant engineers, steelwork designer-draughtsmen, reinforced concrete designer-detailers, and detailer-draughtsmen required for varied and interesting work on structures for industrial, commercial, medical, and residential buildings. Five-days week. Luncheon vouchers. Apply, with details of experience, and salary required, to JOHN F. FARQUHARSON & PARTNERS, Chartered Structural Engineers, 34 Queen Anne Street, London, W.1. Telephone Langham 6601.

SITUATIONS VACANT. E. J. COOK & CO. (ENGINEERS) LTD. require five reinforced concrete designer-detailers for expanding design office. Not less than ten years' experience H.N.C. or similar level. Salaries £600-£1200 per annum according to experience and ability. Five-days week. Luncheon vouchers. Superannuation scheme after twelve months' service. Application forms from 34 South Side, Clapham Common, London, S.W.4 (Macaulay 5528).

SITUATIONS VACANT. Consulting engineers have vacancies for reinforced concrete detailers, and designer-detailers. Salaries in accordance with experience. Luncheon vouchers. Apply in writing to BYLANDER, WADDELL & PARTNERS, 169 Wembley Park Drive, Wembley, Middlesex.

SITUATIONS VACANT. Small structural engineering office, London, W.C.1 area, with extensive practice, requires additional assistants. Capable men from graduation upwards required for high-class miscellaneous work generally, foundations, dangerous structures, steel, concrete and timber, and able to work with minimum supervision. Reply in confidence, with full particulars, and salary required, to Box 4634, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Designer-draughtsman for wide range of concrete structures. Apply J. H. CROCKETT, consulting engineer. Telephone: Wellington 1906.

ROBERT M. DOUGLAS

(Contractors) LTD.

require

DESIGNERS,

DETAILERS,

DRAUGHTSMEN

Civil Engineering Work. Apply, stating age, qualifications, experience, and salary required, to 395 George Road, Birmingham, 23.

ATCOST

LIMITED

Britain's LARGEST makers and erectors of
Precast Reinforced Concrete Structures

require

DESIGNER-DETAILERS

to work on new and varied
precast concrete projects

Applicants must have at least five years' experience in reinforced concrete design and detailing, and be able to work with minimum supervision. These are well-paid, permanent positions with newly-established Engineers' Department. A pension scheme is in operation. Applications, in writing only, stating age, experience and qualifications, to:

ATCOST LTD., Engineers' Dept.,
The Pantiles, Tunbridge Wells, Kent.
One of the ATCOST Group of Companies.

SITUATIONS VACANT. South London consulting engineers require experienced reinforced concrete engineers, designer-draughtsmen, and detailers. Applicants should have a minimum experience of three years in position applied for. Salary commensurate with experience and ability. Luncheon vouchers, and five-days week. Please write, giving details of age, qualifications, and experience, to LEONARD & GRANT, 344 South Lambeth Road, London, S.W.8.

SITUATION VACANT. War Office require Engineer at Christchurch, Hampshire, for duties concerned with development and testing of construction plant (tractors, scrapers, graders and cranes). Qualifications: A.M.I.Mech.E., or equivalent. Design experience in some branch of mechanical engineering and experience in use and operation of road-making machinery in general and in particular machines used in making and handling of bituminous materials, quarrying and concreting plant. Salary range £780-£1680 according to age and experience. Appointment not established but opportunities to compete for establishment may arise. Forms from MINISTRY OF LABOUR, Technical and Scientific Register (K), 26 King Street, London, S.W.1, quoting C.547/58. Closing date 29 January, 1960.

SITUATIONS VACANT. Reinforced concrete engineers and draughtsmen-detailers required urgently. Permanent positions. Excellent prospects. Interesting work. CLARKE, NICHOLLS & MARCEL. Telephone Bayswater 8981 for appointment.

SITUATIONS VACANT. Reinforced concrete designers and detailers required. Minimum three years' practical experience on structural work. Good salary and prospects for right men. Written applications to JOHN LIVERSIDGE & ASSOCIATES, 43 Portland Place, London, W.1.

STRUCTURAL ENGINEERS

ENGINEERS required in Architect's Department, London County Council. Up to £1,135 in., with good prospects.

(A) *Structural Engineering Division.*—Extensive programme includes multi-storey flats, schools, offices, warehouses and other buildings.

(B) *Structural Engineering Division.*—To deal with applications in respect of special structures under Part IV of London Building Act (A), 1939, and the constructional by-laws. Interesting work involving consideration of unconventional forms of construction.

(C) *District Surveyors' Services.*—Work mainly outside involving negotiations with architects, engineers and surveyors and supervision of works in progress.

Application form and particulars from HUBERT BENNETT, F.R.I.B.A., Architect of the Council, EK/112/59, County Hall, London, S.E.1. (2629.)

CANADA

MANAGER, CONCRETE PRODUCTS DIVISION

An outstanding man to take complete charge of a Concrete Products Manufacturing Division, comprising five plants located in Nova Scotia and New Brunswick, Canada. An engineering degree preferable but not essential. At least five years' experience in manufacturing, and with a thorough knowledge of the efficient operation of a precast concrete products factory. Salary range from \$6500 to \$8000 plus bonus and fringe benefits.

Reply, giving full details as to age and education, as well as experience in organising, planning, controlling, and the motivation of employees, and references, to:-

Dept. L.E.S.,
NATIONAL EMPLOYMENT SERVICE,
61 Great Street,
London W.1.

CIVIL ENGINEER—DESIGN

HUMPHREYS & GLASGOW LIMITED require Assistant Civil Engineers, age 25 to 40, for the design of reinforced concrete foundations and associated work such as Earthworks, Roads, Sewage and Drainage Systems, Water Supplies, Railway, Frame Structures, in connection with their modern industrial projects in the fields of Chemical, Power, Mechanical Handling and Gas Industries at home and abroad.

Details of qualifications and experience and salary required should be sent to:- C. L. ROSENLINGE, Esq., HUMPHREYS & GLASGOW LTD., 22 Carlisle Place, London, S.W.1.

RICHARD HILL, LIMITED

require

JUNIOR AND SENIOR REINFORCED CONCRETE DESIGNER/DETAILERS

in their Middlesbrough and London Drawing Offices

Permanent positions with Superannuation Scheme. Apply in writing, stating age, qualifications and salary required, to:

P.O. BOX 29, Middlesbrough
or
299 OXFORD STREET, LONDON, W.1

PROFESSIONAL SERVICES.

PROFESSIONAL SERVICES. Fully experienced detailer-draughtsman will undertake spare-time work for consulting engineers. Please reply to Box 4656, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

FOR SALE, WANTED OR HIRE.

FOR SALE. Steel guttering, Ironwork, Sheet metal work. E. STEPHENS & SON LTD., Bath Street, London, E.C.1. Clerkenwell 1751.

FOR SALE. 500 tons 3-station concrete slab press, suitable for slabs up to 36 in. x 24 in., and kerbs. Self-contained oil pump unit. Unused. Box 4656, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

FOR HIRE. Lattice steel erection masts (light and heavy), 30 ft. to 150 ft. high, for immediate hire. BELLMAN, 21 Hobart House, Grosvenor Place, London, S.W.1.

WANTED. Regularly. Round M.S. reinforcing bar off-cuts. Minimum lengths 2 ft. Also surplus parcels of rods. H. & J. R. SAUNDERS & CO. LTD., Hainsault Road, Leytonstone, London, E.11. Leystone 4383.

WANTED.

COMPRESSION AND TRANSVERSE CONCRETE TESTING MACHINE REQUIRED. CAPACITY OF AT LEAST 150 TONS. PLEASE COMMUNICATE FULL DETAILS TO GEORGE W. BRUCE LIMITED, 106 CROWN STREET, ABERDEEN



CONCRETING in cold weather

Avoid delays during the winter by using
'417' CEMENT. Please write for a copy of the booklet
'Concreting in cold weather' which gives full details of

'417' cement

QUICK SETTING AND EXTRA-RAPID HARDENING



THE CEMENT MARKETING COMPANY LIMITED
PORTLAND HOUSE, TOTHILL STREET, LONDON, S.W.1.

G. & T. EARLE LIMITED, HULL

THE SOUTH WALES PORTLAND CEMENT & LIME COMPANY LIMITED,
FENARTH, GLAM.



There
are vacancies
for experienced
engineers in several
of our design offices.

The British Reinforced Concrete Engineering Co. Ltd., Head Office & Works: Stafford

Published by CONCRETE PUBLICATIONS LTD., 14 Dartmouth Street, London, S.W.1. Telephone: Whitehall 4831.
Printed by BUTLER & TANNER LTD., The Seawood Printing Works, Frome and London.

